### **Public Document Pack**



Democratic Services White Cliffs Business Park Dover

Kent CT16 3PJ

Telephone: (01304) 821199 Fax: (01304) 872453

DX: 6312

Minicom: (01304) 820115 Website: www.dover.gov.uk e-mail: democraticservices

@dover.gov.uk

4 December 2017

#### **Dear Councillor**

NOTICE IS HEREBY GIVEN THAT a meeting of the **SCRUTINY (POLICY AND PERFORMANCE) COMMITTEE** will be held in the HMS Brave Room at these Offices on Tuesday 12 December 2017 at 6.00 pm when the following business will be transacted.

Members of the public who require further information are asked to contact Rebecca Brough on (01304) 872304 or by e-mail at <a href="mailto:rebeccabrough@dover.gov.uk">rebeccabrough@dover.gov.uk</a>.

Yours sincerely

Chief Executive

#### Scrutiny (Policy and Performance) Committee Membership:

K Mills (Chairman)

M I Cosin (Vice-Chairman)

P M Beresford

T A Bond

R J Frost

B J Glayzer

J M Heron

S C Manion M Rose

D A Sargent

#### **AGENDA**

#### 1 **APOLOGIES**

To receive any apologies for absence.

#### 2 **APPOINTMENT OF SUBSTITUTE MEMBERS**

To note appointments of Substitute Members.

#### 3 **DECLARATIONS OF INTEREST** (Page 5)

To receive any declarations of interest from Members in respect of business to be transacted on the agenda.

#### 4 MINUTES

To confirm the Minutes of the meeting of the Committee held on 25 October 2017 and 14 November 2017 (to follow).

#### 5 **PUBLIC SPEAKING**

Please note that in accordance with the agreed Protocol for Public Speaking at Overview and Scrutiny, the right to speak only applies to agenda items 11, 12 and 13.

The right of the public to speak does not apply to the following agenda items: Apologies, Appointment of Substitute Members, Declarations of Interest, Minutes, the Forward Plan, the Scrutiny Work Programme, any agenda item that is not accompanied by a written report and items that are exempt business.

Members of the public wishing to speak must register to do so by no later than 2.00 pm on the second working day before the meeting.

#### 6 <u>DECISIONS OF THE CABINET RELATING TO RECOMMENDATIONS FROM</u> THE SCRUTINY (POLICY AND PERFORMANCE) COMMITTEE

The following decisions were taken by the Cabinet at its meeting held on 4 December 2017 in respect of recommendations from the Scrutiny (Policy and Performance) Committee:

- Update on the Regent Cinema
- Performance Report Q2, 2017/18

#### 7 <u>ISSUES REFERRED TO THE COMMITTEE BY COUNCIL, CABINET, SCRUTINY</u> (COMMUNITY AND REGENERATION) COMMITTEE OR ANOTHER COMMITTEE

There are no items for consideration.

# 8 ITEMS CALLED-IN FOR SCRUTINY OR PLACED ON THE AGENDA BY A MEMBER OF THE COMMITTEE, ANY INDIVIDUAL NON-EXECUTIVE MEMBERS OR PUBLIC PETITION

(a) <u>Items placed on the agenda by a Member of the Committee or any individual Non-Executive Member</u>

Any individual Councillor may request that a matter is placed on the agenda of one of the Council's Overview and Scrutiny Committees by providing Democratic Support with notice of the matter prior to the agenda being published.

There are no items for consideration.

#### (b) Items the subject of Call-In

Executive Decisions may be called-in by the Chairman or Spokesperson of the Scrutiny (Policy and Performance) Committee or any three non-executive members.

There are no items for consideration.

#### (c) Public Petition

There are no items for consideration.

#### 9 NOTICE OF FORTHCOMING KEY DECISIONS (Pages 6 - 9)

It is intended that Members should use the Notice of Forthcoming Key Decisions to identify topics within the remit of the Committee for future scrutiny.

#### 10 **SCRUTINY WORK PROGRAMME** (Pages 10 - 16)

It is intended that the Committee monitor and prioritise its rolling work programme.

#### 11 **AUTHORITY MONITORING REPORT** (Pages 17 - 173)

To consider the attached report of the Chief Executive.

# 12 RIVER DOUR ENHANCEMENT WORK AND REPAIRS TO DOLPHIN HOUSE GARAGES (Pages 174 - 178)

To consider the attached report of the Director of Environment and Corporate Assets.

#### 13 **OVERNIGHT OPENING OF DEAL PIER** (Pages 179 - 184)

To consider the attached report of the Director of Environment and Corporate Assets.

#### Access to Meetings and Information

- Members of the public are welcome to attend meetings of the Council, its Committees and Sub-Committees. You may remain present throughout them except during the consideration of exempt or confidential information.
- All meetings are held at the Council Offices, Whitfield unless otherwise indicated on the front page of the agenda. There is disabled access via the Council Chamber entrance and a disabled toilet is available in the foyer. In addition, there is a PA system and hearing loop within the Council Chamber.
- Agenda papers are published five clear working days before the meeting. Alternatively, a limited supply of agendas will be available at the meeting, free of charge, and all agendas, reports and minutes can be viewed and downloaded from our website www.dover.gov.uk. Minutes are normally published within five working days of each meeting. All agenda papers and minutes are available for public inspection for a period of six years from the date of the meeting.

 If you require any further information about the contents of this agenda or your right to gain access to information held by the Council please contact Rebecca Brough, Democratic Services Manager, telephone: (01304) 872304 or email: rebeccabrough@dover.gov.uk for details.

Large print copies of this agenda can be supplied on request.

#### **Declarations of Interest**

#### Disclosable Pecuniary Interest (DPI)

Where a Member has a new or registered DPI in a matter under consideration they must disclose that they have an interest and, unless the Monitoring Officer has agreed in advance that the DPI is a 'Sensitive Interest', explain the nature of that interest at the meeting. The Member must withdraw from the meeting at the commencement of the consideration of any matter in which they have declared a DPI and must not participate in any discussion of, or vote taken on, the matter unless they have been granted a dispensation permitting them to do so. If during the consideration of any item a Member becomes aware that they have a DPI in the matter they should declare the interest immediately and, subject to any dispensations, withdraw from the meeting.

#### Other Significant Interest (OSI)

Where a Member is declaring an OSI they must also disclose the interest and explain the nature of the interest at the meeting. The Member must withdraw from the meeting at the commencement of the consideration of any matter in which they have declared a OSI and must not participate in any discussion of, or vote taken on, the matter unless they have been granted a dispensation to do so or the meeting is one at which members of the public are permitted to speak for the purpose of making representations, answering questions or giving evidence relating to the matter. In the latter case, the Member may only participate on the same basis as a member of the public and cannot participate in any discussion of, or vote taken on, the matter and must withdraw from the meeting in accordance with the Council's procedure rules.

#### Voluntary Announcement of Other Interests (VAOI)

Where a Member does not have either a DPI or OSI but is of the opinion that for transparency reasons alone s/he should make an announcement in respect of a matter under consideration, they can make a VAOI. A Member declaring a VAOI may still remain at the meeting and vote on the matter under consideration.

#### Note to the Code:

Situations in which a Member may wish to make a VAOI include membership of outside bodies that have made representations on agenda items; where a Member knows a person involved, but does not have a close association with that person; or where an item would affect the well-being of a Member, relative, close associate, employer, etc. but not his/her financial position. It should be emphasised that an effect on the financial position of a Member, relative, close associate, employer, etc OR an application made by a Member, relative, close associate, employer, etc would both probably constitute either an OSI or in some cases a DPI.



# Notice of Forthcoming Key Decisions

[This updated version of the Notice supersedes all other versions issued in previous months]

Publication Date: 3 November 2017

# Notice of Forthcoming Key Decisions which will be made on behalf of the Council

Key Decisions 2017/18	ltem	Date of meeting at which decision will be taken by Cabinet (unless specified otherwise)
1	Neighbourhood Plans	June 2013 and ongoing (see entry)
2	Dover Town Centre Regeneration: To consider progress on the Compulsory Purchase Order and any issues arising which may go beyond the scope of the resolutions incorporated in Minute CAB 87	8 September 2014/24 April 2015/7 March 2016 and as necessary
3	Approval to develop detailed plans for replacement of Dover Leisure Centre	25 July/20 September and 15 December 2016 (special Cabinet meetings) and 11 September 2017 (special Cabinet meeting)
4	Statutory Brownfield Register	Decision to be taken by the Head of Regeneration and Development – December 2017
5	Review of Tenancy Strategy and Tenancy Policy	4 December 2017 or 15 January 2018
6	Review of Local Plan	(i) 1 March 2017; (ii) October 2018; and (iii) July 2019
7	Property Acquisitions	Ongoing (decisions to be taken by Portfolio Holder for Corporate Resources and Performance)
8	Approval for public consultation on draft South Barracks Conservation Area Appraisal	3 July 2017 and 5 February 2018
9	To consider the results of public consultation on the Waterloo Crescent Conservation Area Appraisal and approve public consultation on proposed boundary extensions	8 May 2017
10	To consider the results of public consultation on the extension of the Nelson Street Conservation Area boundary and the introduction of an Article 4 Direction	8 May and 4 December 2017
11	Approval to cease providing a face-to-face customer service function at Aylesham, Deal and Sandwich area offices	3 July and 4 September 2017
12	Approval of revisions to the 2012 Housing Assistance Policy	3 July 2017
13	Approval of amended Dover District Council Events Policy and Land Hire Agreement	4 September 2017

Key Decisions 2017/18	ltem	Date of meeting at which decision will be taken by Cabinet (unless specified otherwise)
14	Approval to release funding and carry out regular beach maintenance works between Oldstairs Bay and Sandwich Bay	12 June 2017
15	Local Plan Review – Engagement Strategy	8 May 2017
16	Appointment of contractor to carry out building extension and repair works at Kearsney Abbey and Russell Gardens as part of the Heritage Lottery Funded 'Parks for People' project	Decision to be taken by the Portfolio Holder for Property Management and Public Protection – July/August 2017
17	Appointment of contractor to carry out landscape and watercourse restoration works at Kearsney Abbey and Russell Gardens as part of DDC's Heritage Lottery Funded 'Parks for People' project	Decision to be taken by the Portfolio Holder for Property Management and Public Protection – July/August 2017
18	To approve the policy on civil penalties and rent repayment orders for private landlords	2 October 2017
19	To seek approval for wet and dryside improvements to Tides Leisure and Indoor Tennis Centre, Deal	15 January 2018
20	Dover Waterfront Masterplan Area Action Plan	To be confirmed
21	Planning Enforcement Plan	4 December 2017 and dates to be confirmed
22	Representations on the Thanet District Council Local Plan	5 March 2018
23	Fit-out of Aylesham retail units and related funding	3 July 2017
24	Project approval for development of land at Foxborough Close, Woodnesborough to provide affordable housing	3 July 2017
25	Approval of project to deliver new modular homes to provide temporary housing for homeless households	2 October 2017
26	To consider a revised East Kent Growth Framework	4 September 2017
27	The Open Golf Championship 2020	4 September 2017
28	Local Development Scheme	4 September 2017
29	To seek approval for public consultation on the draft Sandwich Walled Town Conservation Area Appraisal	5 March 2018 and date to be confirmed
30	Approval of contracts for works to Middle Street Car Park, Union Road Car Park and general maintenance work to remaining car parks.	4 September 2017
31	Approval to carry out works to area adjacent to River Dour and garages to the rear of Dolphin House, Dover	4 December 2017

Key Decisions 2017/18	Item	Date of meeting at which decision will be taken by Cabinet (unless specified otherwise)
32	Approval to carry out capital project works to Deal Pier	2 October and 6 November 2017
33	Award of replacement pitched roofing contract 2017-2020	2 October 2017
34	Future and funding of Inspire Fund	15 January 2018
35	Development of community-led housing initiatives	6 November 2017
36	Approval to upgrade heating and ventilation plant and controls at Dover Museum	6 November 2017
37	To approve final contract terms for the delivery of Revenues, Benefits and Customer Services functions by a private sector provider, and give authority for partner councils to enter into the contract and associated documentation.	East Kent Services Committee – December 2017/January 2018
38	Hackney Carriage and Private Hire vehicles - access for wheelchair users	15 January 2018
39	Fees and Charges – agreement on levels for 2018/19	15 January 2018
40	Authority Monitoring Report	4 December 2017/15 January 2018
41	Recommendations to Cabinet (and Council) of the draft 2018/19 Budget and Medium-Term Financial Plan 2018/19-2021/22, and approval of various delegations within the Budget	5 February and 5 March 2018

- Note: (1) Key Decisions which are shaded have already been taken and do not appear in this updated version of the Notice of Forthcoming Key Decisions.
  - (2) The Council's Corporate Management Team reserves the right to vary the dates set for consultation deadline(s) and for the submission of reports to Cabinet and Council in respect of Key Decisions included within this version of the notice. Members of the public can find out whether any alterations have been made by looking at the Council's website (<a href="www.dover.gov.uk">www.dover.gov.uk</a>).

# **OVERVIEW AND SCRUTINY WORK PROGRAMME 2017/18**

# **SCRUTINY (POLICY AND PERFORMANCE) COMMITTEE**

		Re	source Implications for S			
Month	Scrutiny (Policy and Performance) Committee	Members	Officers (Corporate	Scrutiny Budget Expenditure		Action
			Expenditure unless otherwise stated)	Projected	Actual	
	Waterloo Crescent Conservation Area Appraisal	Single Meeting	Head of Regeneration and Development	£0	£0	To consider the results of public consultation on the Waterloo Crescent Conservation Area Appraisal and approve public consultation on proposed boundary extensions
	Nelson Street Conservation Area	Single Meeting	Head of Regeneration and Delivery	£0	£0	To consider the results of public consultation on the extension of the Nelson Street Conservation Area boundary and the introduction of an Article 4 Direction.
May 2017	Performance Report Q4	Single Meeting	Director of Governance	£0	£0	To consider the report.
	Appropriation of Land for Play Areas	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To consider the report.
	St Radigund's Play Area Project	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To consider the report.
	Petition – Aycliffe Parking	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To receive the petition.

		Res	source Implications for S	crutiny		
Month	Scrutiny (Policy and Performance) Committee	Members	Officers (Corporate		y Budget nditure	Action
			Expenditure unless otherwise stated)	Projected	Actual	
June 2017	Regent Cinema	Special Meeting (on-going)	Director of Environment and Corporate Assets / Head of Regeneration & Delivery	£tbc	£0	To be held in Deal at a date to be determined (June/July).
	Oldstairs Bay to Sandwich Bay Beach Management Plan	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To consider the report.
	Accommodation Charter for Dover District	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To consider the report.
July 2017	Approval to cease providing a face-to-face customer service function at Aylesham, Deal and Sandwich Area Offices	Single Meeting	Corporate Management Team	£0	£0	To consider the report.
	Outsourcing of Revenues, Benefits, Debt Recovery and Customer Services Functions (Revision of Delegations to the East Kent Services Committee)	Single Meeting	Corporate Management Team	£0	£0	To consider the report.
August 2017	Regent Cinema	On-going	Corporate Management Team	£venue+ micropho nes	£724.80	This will be held in Deal at the Astor Theatre. Date: 3 August 2017
September 2017	Closure of Area Offices	On-going	Director of Shared Services	£0	£0	To consider the further report. [Pre-decision scrutiny had been requested]

		Re				
Month	Scrutiny (Policy and Performance) Committee	Members	Officers (Corporate	Expenditure		Action
			Expenditure unless otherwise stated)	Projected	Actual	
	St James's Development Update	On-going	Head of Inward Investment	£0	£0	A further site visit to the St James's site to view progress. Exact date to be confirmed.
	Dover Leisure Centre	On-going	Director of Environment and Corporate Assets	£0	£0	To consider reports at each relevant stage in the process.[Could be a separate meeting – tbc on date]
	Lorry Parking in Dover	On-going	Director of Environment and Corporate Assets	£0	£0	To continue to monitor the progress in resolving illegal and anti-social lorry parking in Dover.
	Petition – Future of Dover Town	Single Meeting	Corporate Management Team	£0	£0	To receive the petition.
	Petition – Speed Restrictions on Beaconsfield Avenue	Single Meeting	Corporate Management Team	£0	£0	To receive the petition.
	Car Park Resurfacing	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To consider the report.
	Performance Report Q1	Single Meeting	Director of Governance	£0	£0	To consider the report.
	Parks and Open Spaces	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To receive an update on the progress of the service since bringing in-house. [Provided as focus of Performance Report]
October 2017	Report on Petition – Aycliffe Parking	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To receive a report in respect of the petition. [Moved from September due to other petitions received]

		Re	esource Implications for S	crutiny		
Month	Scrutiny (Policy and Performance) Committee	Members	Officers (Corporate	Scrutiny Budget Expenditure		Action
			Expenditure unless otherwise stated)	Projected	Actual	
	EK Services Strategic Service Delivery Options and Potential for Contracting out of Certain Functions	On-going	Corporate Management Team	£0	£0	To consider the report on the business case.
	Report on Petition – Beaconsfield Avenue and surrounding area	Single Meeting	Director of Environment and Corporate Assets	£0	£0	To consider a report in respect of the petition.
	Universal Credit Update	Single Meeting	East Kent Housing	£0	£0	At the 12 September 2017 meeting, members requested an update on Universal Credit from EKH.
	EK Services' Face-to- Face Service Provision at Deal Area Office	Single Meeting	Corporate Management Team EKS	£venue+ micropho nes	£584	Special meeting to be held at the Astor Theatre on 25 October 2017
	Access to Information Procedure Rules	Single Meeting	Director of Governance	£0	£0	To receive a briefing from the Director of Governance.
	Regent Cinema Update	On-going	Director of Environment & Corporate Assets	£0		To receive an update.
November 2017	Lorry Parking in Dover District	On-going	Kent Police	£0		To receive an update.
	Performance Report Q2	Single Meeting	Director of Governance	£0		To consider the report.
December 2017	Overnight Opening of Deal Pier	Single Meeting	Director of Environment & Corporate Assets	£0		To consider the report.

		Re	source Implications for S			
Month	Scrutiny (Policy and Performance) Committee	Members	Officers (Corporate	Scrutiny Budget Expenditure		Action
			Expenditure unless otherwise stated)	Projected	Actual	
	Authority Monitoring Report	Single Meeting	Chief Executive	£		To consider the report.
	Accommodation Charter Update	Single Meeting (Follow-up)	Director of Environment & Corporate Assets	£		To receive an update.
	Planning Enforcement Plan	Single Meeting	Chief Executive	£		To consider the report.
	Deal Pier	Single Meeting	Director of Governance & Director of Environment and Corporate Assets	£		To receive an update
January 2018	To seek approval for wet and dryside improvements to Tides Leisure and Indoor Tennis Centre, Deal	Single Meeting	Director of Environment & Corporate Assets	£		To consider the report.
	Lorry Parking in the Dover District	Single Meeting	Kent Police (conf) Kent County Council (tbc)	£		To consider the issue of illegal and antisocial lorry parking in Dover.
	Dover Town Centre Regeneration	Single Meeting	Corporate Management Team	£		To consider the report.
	Customer Services – Update on Performance Indicators	Single Meeting	Director of Shared Services	£		To receive an update.

		Res	source Implications for So				
Month	Scrutiny (Policy and Performance) Committee	Members	Members Officers (Corporate		/ Budget nditure	Action	
			Expenditure unless otherwise stated)	Projected	Actual		
	Performance Report Q3	Single Meeting	Director of Governance	£0	£0	To consider the report.	
February 2018	Scrutiny of the Council's budget	Single Meeting	Corporate Management Team	£0		To scrutinise the Council's budget for 2018/19.	
	Fees and Charges	Single Meeting	Corporate Management Team	£0		To be considered as part of the budget scrutiny process.	
March 2018							
April 2018	Performance Report Targets 2018-19	Single Meeting	Director of Governance	£0		To consider the report	
May 2018	Performance Report Q4	Single Meeting	Director of Governance	£0	£0	To consider the report.	

Please note items beyond the current month are subject to change depending on Forward Plan, etc.

### Municipal Year 2017/18

Agreed for Inclusion?	Subject		Resource Implications	Action	
Yes	Property Investment Strategy	Single Meeting	Director of Finance, Housing and Community	£	To receive an update
Yes	Dover Town Centre Regeneration	Meeting of both scrutiny committees	Corporate Management Team	£	To hold a meeting of both scrutiny committees to consider the proposals for the regeneration of the wider town centre.
Yes	Update on scaffolding at Tower Hamlets	Single Meeting – Follow up	Director of Environment & Corporate Assets	£	To receive an update.
Yes	Dover Leisure Centre	On-going	Director of Environment and Corporate Assets	£0	To consider reports at each relevant stage in the process.
Yes	Digital Strategy	Single Meeting	Head of Community Services	£	To receive an update on the Council's digital strategy.
Yes	Lorry Parking in the Dover District	On-going	Various	£	To consider issues of illegal and antisocial lorry parking in the wider District.
Yes	Open Golf Championship	On-going	Corporate Management Team	£	To receive updates at appropriate milestones.
Yes	Dover Town Investment Zone	On-going	Various	£	To maintain a watching brief, scheduling scrutiny meetings as appropriate.

Subject: DOVER DISTRICT COUNCIL AUTHORITY MONITORING

**REPORT 2016/17** 

Meeting and Date: 4 December 2017

Report of: Nadeem Aziz, Chief Executive

Portfolio Holder: Councillor Jim Back, Portfolio Holder for Built Environment

Decision Type: Executive Key

Classification: Unrestricted

**Purpose of the report:** To seek approval for the Authority Monitoring Report 2016/17

Recommendation:

Cabinet approves the Authority Monitoring Report 2016/17 attached at Appendix 1 and agrees that it is made available on the District Council's website.

#### 1. Summary

1.1 This is the thirteenth Authority Monitoring Report (AMR) produced by Dover District Council and covers the period from the 1<sup>st</sup> April 2016 to 31<sup>st</sup> March 2017.

- 1.2 The AMR serves a number of purposes, the main ones being:
  - To assess the effectiveness of the Council's current planning policies set out in the Development Plan;
  - To monitor the delivery of the Council's Development Plan and assess whether the Council is meeting the social, economic and environmental objectives set out in the Plan;
  - To act as a record of the amount of development which has taken place in the District during the year; and
  - To set out the Council's progress against its 'Local Development Scheme', a high level project plan for the production of new planning documents and policies.
- 1.3 The key findings from this year's AMR are set out below.

#### 2. Introduction and Background

2.1 The National Planning Practice Guidance (PPG) states that Local Planning Authorities (LPAs) must publish information at least annually that shows progress with Local Plan preparation, reports any activity relating to the duty to cooperate and shows how the implementation of policies in the Local Plan is progressing. LPAs can also use the AMR to provide up-to-date information on the implementation of any neighbourhood plans that have been made, and to determine whether there is a need to undertake a partial or full review of the Local Plan. The AMR should be made publicly available.

#### 3. Key Findings

The Dover District Core Strategy (2010) sets out a number of objectives regarding social issues, the economy, the environment, as well as housing and infrastructure

Dover District Council 17

delivery. The key findings from the AMR 2016/17 for each of these issues are set out within Chapter 1 of the AMR, which is appended to this report.

#### 4. Social

- 4.1 The working age population is still below the Core Strategy target of 72,100 however, at 67,700 (ONS 2014 SNPP). Dover has an older age profile and natural change in the District is negative with deaths outnumbering births. Any future population growth in the District is forecast to be from inward migration. The age profile of the population is also forecast to increase, highlighting a need to plan for an ageing population across the District as part of the Local Plan review.
- 4.2 With regard to deprivation, the District's position in the national ranking has worsened over the plan period and the Dover District remains to be in England's most deprived half of local authorities with 4 Lower-Layer Super Output Areas (LSOAs) falling within the most deprived 10% of LSOAs nationally. Additionally, in the most deprived areas of Dover, life expectancy is 7.7 years and 2.7 years lower for men and women respectively, compared to those in the least deprived areas.

#### 5. The Economy

- 5.1 Over the monitoring period (2016/17) the following employment floorspace (B1, B2 and B8) has been given planning permission; gains of 8,914 sq m, losses of -4,264 sq m resulting in a net overall gain of 4,650 sq m. The principal gains in employment floorspace were seen in B1c (erection of an algae farming facility 2,304 sq m) and B2 uses (erection of R&D manufacturing building 4,230 sq m) both at Discovery Park, Sandwich and losses in B1a office space from Snargate Street and Castle Street in Dover.
- 5.2 Since the last monitoring period (2015/16), the number of jobs in the District has decreased by 700 according to the Business Register & Employment Survey (BRES). Looking at these figures more closely there are gains and losses across a number of sectors. However, the sector with the largest loss over the monitoring period is 'human health and social work activities' with -800 in fact the same sector shows an 800 increase in the previous period 2014/15. KCC have highlighted this figure as being potentially unreliable and if the number of jobs in the District is considered without this sector being included there is no overall change in the monitoring year. Positively, the skill attainment levels in the District have improved as the percentage of working age residents without qualifications has decreased and is now lower than the Kent average.
- 5.3 With regards to development in the retail and leisure sector in the District work has progressed extremely well on the St James's development in Dover Town Centre. Work is underway on the preparation of an Area Action Plan for the Dover Waterfront Area, to deliver new retail, leisure, housing and employment floorspace. In the monitoring year 2016/17 the following retail floorspace has been completed; gains of 461 sq m, losses of -1,176 sq m, resulting in a net over loss of -715 sq m. This is a decrease since the last monitoring year and can be largely attributed to losses from use class A4 (public houses) and loss of retail floorspace through a change of use to other uses. However, the amount of retail floorspace under construction has risen significantly to 12,549 sq m, due to the development at St James's and Lidl, at Whitfield. There has been a slight decline in leisure floorspace (D2) being completed with gains of 469 sq m, losses of -361 sq m resulting in a net gain of 108 sq m. However, the amount of leisure floorspace under construction is 6,695 sq m due to work on the Betteshanger Park mining museum and the cinema at St James's.

5.4 Surveys of the primary and secondary shopping frontages in Dover, Deal and Sandwich have shown that; vacancy rates in Dover have increased from 14% (22 units) in 15/16 to 15.28% (24 units) in 16/17; vacancy rates in Deal have increased from 2% (2 units) in 15/16 to 2.83% (3 units) in 16/17 and vacancy rates for Sandwich have remained unchanged at 7% (6 units). The Local Plan review will consider the health of town centres, and Dover in particular, and propose policy measures to address issues.

#### 6. The Environment

- 6.1 Measures have been taken over the monitoring year to improve the environment in the District, with the completion of the St Radigunds play area project at Triangles Community Centre, Coombe Valley and the opening of a Multi-Use Games area in the Wingham Parish.
- 6.2 The Council's adopted Parks and Amenity Open Spaces Strategy places a very high priority on raising standards and capacity at the District's most popular park; Kearsney Abbey. The Heritage Lottery Fund and Big Lottery fund awarded a £3 million grant to restore Kearsney Abbey and Russell Gardens. The grant was awarded in July 2016 and DDC are in the delivery stage of the phased project which runs until June 2020.
- 6.3 Furthermore, during this monitoring period the Council submitted a planning application for the relocation of a new £26m Dover Leisure Centre based in Whitfield (subsequently approved and under construction).
- 6.4 With regard to the historic environment, the Council has progressed with Conservation Area Character Appraisals in Nelson Street, Deal and Waterloo Crescent, Dover. The Council is also undertaking a review of the District's historic parks and gardens and reports on the outcome of this work are anticipated for spring 2018.

#### 7. Housing

7.1 During the monitoring period there were 406 dwellings completed (net figure). The majority of development over the monitoring period occurred in Deal (179 units), followed by Dover (87 units), Aylesham (78 units) and 62 units being completed from the other settlements across the District. In addition, during 2016/17, 91 affordable homes were delivered in the District, equating to 19.2% of all housing completions, compared to 185 dwellings (25.4%) in 2015/16.

#### 5-Year Housing Land Supply Calculation

7.2 The Council's position regarding the 5-year housing land supply was considered at a Special Cabinet meeting on the 20<sup>th</sup> November 2017.

<a href="http://moderngov.dover.gov.uk/ieListDocuments.aspx?Cld=121&Mld=2835">http://moderngov.dover.gov.uk/ieListDocuments.aspx?Cld=121&Mld=2835</a>. In the form of an advanced extract from the AMR Housing chapter. That extract is incorporated in the housing (Chapter 7 of the AMR 16/17 appended to this report)

#### Infrastructure Delivery

7.3 Over the monitoring period the Council secured £744,518 in S106 contributions from developments across the District. Of this figure DDC received £543,703 (73%) to provide the necessary infrastructure to support growth and the remainder of the

funds £200,815 was passed to KCC to fund transport projects, libraries, social care and education.

#### 8. Progress with Plan-Making

- 8.1 At the end of the monitoring year 2016/17 the Council agreed to commence a Local Plan review. As a result of this decision the Council is currently in the process of producing a new Local Plan and Area Action Plan for the Dover Waterfront. The evidence base that underpins the plan making is in the course of being reviewed. To date the Strategic Housing Market Assessment (SHMA) and the Economic Development Needs Assessment (EDNA) has been completed. Further studies have been commissioned; Retail Needs Assessment, North Deal Study, Sustainability Appraisal/Habitats Regulation Appraisal, Strategic Flood Risk Assessment, Housing and Economic Land Availability Assessment (DDC consultation) and the Gypsy and Traveller Needs Assessment.
- 8.2 The Council's Local Development Scheme (LDS) sets out the timetable for the preparation of these documents and progress against meeting key milestones in their production.
- 8.3 The Council continues to support Parishes in the District with Neighbourhood Planning and has met with a number of Parishes over the monitoring period to provide assistance on this issue. The Council is working with Ash Parish Council who are currently progressing their Neighbourhood Plan.
- 8.4 The duty to co-operate was introduced in the Localism Act 2011 and places a legal duty on LPAs to engage constructively, actively and on an on-going basis to maximise the effectiveness of local plan preparation relating to strategic cross boundary matters. The Council has continued to co-operate with Kent Authorities and key stakeholders in planning the District's future. This has involved a number of meetings over the monitoring period which is outlined in Chapter 4 of the AMR 2016/17.

#### 9. Identification of Options

- 9.1 To approve the AMR attached at Appendix 1.
- 9.2 Not to approve the AMR attached at Appendix 1.

#### 10. Evaluation of Options

- 10.1 Under Government legislation the Council is required to produce an AMR. Given this, there is no option regarding whether or not to produce an AMR, as it is a legal requirement.
- 10.2 The AMR continues to monitor progress against the LDS and the priorities identified in the Core Strategy (2010), identifying successes and issues that require action.

#### 11. Resource Implications

11.1 Once agreed by Cabinet, a copy of the AMR 2016/17 will be made publicly available on the Council's website. There are no further resource implications.

#### 12. Corporate Implications

- 12.1 Comment from the Section 151 Officer: Finance has been consulted and has nothing further to add (SB)
- 12.2 Comment from the Solicitor to the Council: The Planning Solicitor has considered this report and has no further comment.
- 12.3 Comment from the Equalities Officer: This report does not specifically highlight any equalities implications, however in discharging their responsibilities members are required to comply with the public sector duty as set out in section 149 of the Equality Act 2010 http://www.legislation.gov.uk/ukpga/2010/15

#### 13. Appendices

Appendix 1 – Authority Monitoring Report 2016/17

Contact Officer: Katherine Messenger, Assistant Planner, Regeneration Delivery Section





# **Dover District**

**Authority Monitoring Report** 2016/2017

# Contents

1	Overview						
	1.1	Key Findings from the AMR 2016/17	4				
	1.2	Direction of Travel	9				
2	Intro	duction	13				
3	The	The District and its People					
	3.1	Geography	16				
	3.2	Population	19				
	3.3	Health and Social Wellbeing	22				
4	Plan	ning for the Future	29				
	4.1	Current Planning Policies	29				
	4.2	Local Plan Review	29				
	4.3	Planning Documents Under Preparation	33				
	4.4	Duty to Co-operate	42				
5	Mon	itoring of Current Policies	52				
	5.1	Effectiveness of Development Management Policies	52				
	5.2	Number of Decisions Allowed on Appeal	55				
	5.3	Changes to Permitted Development Rights	57				
6	Retail, Services and Facilities						
	6.1 Health of the District's Centres						
	6.2 Changes in Retail Floorspace						
	6.3	Changes in Community Floorspace	66				
	6.4	Changes in Leisure Floorspace	66				
7	Hous	sing	69				
	7.1	Delivery of New Homes	69				
	7.2	Five Year Housing Land Supply	74				
	7	2.1 Background	74				
	7	2.2 The Calculation	76				
	7	2.3 Key Components of the 5 Year Housing Land Supply	77				
	7.3	Housing Trajectory	82				

# Contents

	7.4	Affordable Housing	83				
	7.5	Gypsy and Traveller Pitch Provision	85				
8	The E	Economy	87				
	8.1	Changes in Employment Floorspace	87				
	8.2	Jobs	91				
9	Envir	onment and Sustainability	97				
	9.1	Environment	97				
	9.2	Sustainability	99				
	9.3	Historic Environment	100				
10	Infras	structure	104				
	10.1	Infrastructure Delivery	104				
	10.2	Development Contributions	105				
11	Strate	egic Sites	109				
	11.1	The Port of Dover and Dover Waterfront	109				
	11.2	Mid Town Dover	111				
	11.3	Former Connaught Barracks Complex	112				
	11.4	Whitfield Urban Expansion	113				
	11.5	St James's, Dover	114				
	11.6	Discovery Park Enterprize Zone	115				
12	Overa	all Conclusion	119				
Α	pper	ndices					
1	Moni	toring Indicators	121				
2							
3	Delivery of Housing Allocations1						
4	Extar	Extant Planning Permissions137					
5	Infrastructure Delivery Table						

### 3

# Overview

#### 1 Overview

- 1.1 This is the thirteenth Authority Monitoring Report (AMR) produced by Dover District Council (DDC), reporting on progress in implementing the Council's Development Plan between 1st April 2016 and 31st March 2017.
- 1.2 The Development Plan for the District comprises:
- The Dover District Core Strategy (2010);
- The Land Allocations Local Plan (2015);
- Worth Neighbourhood Plan (2015);
- KCC Minerals and Waste Local Plan 2013 2030 (2016);
- Saved Local Plan Policies (2002); and
- Policies Map.
- 1.3 The AMR serves a number of purposes, the main ones being:
- to assess the effectiveness of the Council's current planning policies set out in the Development Plan;
- to monitor the delivery of the Council's Development Plan and assess whether the Council is meeting the social, economic and environmental objectives set out in the Plan;
- to act as a record of the amount of development which has taken place in the District during the year; and
- to set out the Council's progress against its 'Local Development Scheme', a high level project plan for the production of new planning documents and policies.
- 1.4 The AMR will also be used to monitor progress regarding the preparation of the Council's new District Local Plan, following a decision by Cabinet in March 2017 to review the Core Strategy (2010) and Land Allocations Local Plan (2015) and produce a new NPPF compliant Local Plan.

### 1.1 Key Findings from the AMR 2016/17

1.5 Prior to the adoption of the new District Local Plan, the AMR will continue to monitor the implementation of the Dover District Core Strategy (2010) and the Land Allocations Local Plan (2015). The Core Strategy (2010) details a number of objectives covering social issues, the economy, the environment, as well as housing and infrastructure delivery. The key findings from the AMR for each of these indicators are summarised as follows:

#### Social

1.6 The total population of the District now stands at 113,100 people (ONS 2014 SNPP), exceeding the Core Strategy target for 2026 of 111,500 people. The working age population of the District is still someway under the Core Strategy target of 72,100 and is currently at 67,700 (ONS 2014 SNPP). By 2037, the population of the District

is forecast to increase to 127,200, predominantly due to domestic migration. The age profile of the population is also set to increase; demonstrating a need to plan for an ageing population across the district.

- 1.7 The Dover District is in England's most deprived half of local authorities with 4 Lower-Layer Super Output Areas (LSOAs) falling within the most deprived 10% of LSOAs nationally and 1 LSOA in the top 5% most deprived areas in the country. The District's position in the national ranking has worsened over the Plan period (2006-2026) and is now considered to be more deprived than in 2007. This signifies that the Council is behind its Core Strategy target of improving social disadvantage in the most deprived wards and clearly demonstrates a need to work better with a range of delivery partners in order to help address this important issue.
- 1.8 The health profile of people in the Dover District is varied compared with the England average. Life expectancy for both men and women is slightly lower than the England average. In the most deprived areas of Dover, life expectancy is 7.7 years and 2.7 years lower for men and women respectively, compared to those in the least deprived areas. This situation has worsened since the start of the Plan period (2006).

#### The Economy

- 1.9 The District represents a reasonably small but productive economy in East Kent. Employment floorspace within the district is dominated by industrial uses (B2 and B8 uses) and the Dover District has the second largest stock of industrial space and the second smallest stock of offices in East Kent.
- 1.10 Over the monitoring period (2016/17) a total of 4,650 sqm of employment floorspace (B1, B2 and B8 uses) was permitted in the District (this is a net overall figure taking into account gains and losses). Of this, the main gains in employment floorspace were seen in B1c and B2 uses and can be largely attributed to 2 applications at Discovery Park Sandwich. The main losses in employment floorspace were seen in B1a office space, with losses from Protea House, Market Square and Castle Street in Dover. This echoes longer term trends in employment floorspace in the District, which has principally seen gains in industrial uses (B1c and B2) and losses in B1a office space.
- 1.11 Discovery Park continues to attract high levels of investment and is now one of the UK's top performing Enterprise Zones and is home to over 150 companies and 3,346 employees from established organisations to emerging start-ups in the fields of life science, pharmaceuticals, biotechnology, science and technology. However, while the high level of investment at Discovery Park is extremely positive for the District, the low level of investment across other employment areas is a concern and illustrates that more needs to be done to promote other sites such as the White Cliffs Business Park.
- 1.12 The Dover District has recorded a loss of 4,700 jobs during the first 10 years of the Core Strategy Plan period from 2006 to 2016 across most sectors, with only education, hospitality and recreation, finance and insurance, and information and

communication showing an increase in employment. The Core Strategy objective was to deliver 6,500 jobs over the Plan period, the opposite has occurred and the economy has contracted, with future growth forecast at 2,700 jobs over the period to 2037.

- 1.13 Furthermore, the latest job density figures published by NOMIS in 2015 show that the number of jobs in the District has declined from 41,000 in 2014 to 40,000 jobs in 2015 which equates to a jobs density of 0.59, significantly below the Kent average. Looking at these figures more closely the Business Register & Employment Survey (BRES) shows that the District has lost 700 employee jobs (net figure) over the monitoring year although there are gains and losses across a number of sectors. The sector with the largest loss over the monitoring period is 'human health and social work activities' with 800 losses but it should be noted that in fact the same sector shows an 800 increase in the previous period 2014/15. KCC who published this bulletin have highlighted this figure as being potentially unreliable and if the number of employee jobs in the District is considered without this sector being included there is no overall change in the monitoring year.
- 1.14 Positively, skill attainment levels in the District have improved over the Plan period. The percentage of residents of working age without qualifications has decreased and is now lower than the Kent average. The percentage of working age residents with NVQ 4 qualification or higher has increased and the gap between the District and the Kent average is decreasing, which is very positive news.
- 1.15 With regard to development in the retail and leisure sector in the District, work is continuing on the St James' development site (also known as the Dover Town Investment Zone (DTIZ)) in the Dover Town Centre, which is an extremely positive step for the regeneration of Dover and for the District holistically, as the development will bring new shops, cafés, restaurants and a cinema into the heart of the Dover Town Centre. Work has also commenced on the Area Action Plan (AAP) for Dover Waterfront area and a Public Realm Strategy for the Town Centre. This work will build on the momentum created through the St James' development and seek to deliver new retail, leisure, housing and employment to re-invigorate Dover's sea front. In addition to this, the development of a new Lidl foodstore (use class A1) at Whitfield was granted permission over the monitoring period and is currently under construction.
- 1.16 Across the remainder of the District there has only been a limited amount of activity in the retail and leisure sector. Since the last monitoring period there has been a decrease in retail floorspace built from 298 sq m during 2015/16 to -715 in 2016/17. There has also been a decrease in leisure floorpsace with 259 sq m and 108 sq m built in 2015/16 and 2016/17 respectively. Recent shopping surveys of shopping frontages in the District show that Dover has a vacancy rate of 15.28%, Deal 2.83% and Sandwich 7.0%. Over the monitoring year, the vacancy rate in Dover has increased from 14% (2015/16) to 15.28% (2016/17), this rate is above the national average of 11.1%. Clearly the rise in vacancy rates in Dover is of key concern and needs to be very closely monitored in relation to the opening of the St James' development and how the Local Plan can be used to support the existing town centre. <sup>28</sup>

- 1.17 In Deal the vacancy rate has increased slightly over the monitoring year from 2% to 2.83% although this centre still has the lowest overall percentage. Sandwich has seen some losses in the secondary shopping frontages although this has been offset by some gains and therefore the overall vacancy rate remains unchanged from last monitoring period at 7%.
- 1.18 In 2015/16, the number of passengers entering and exiting Dover Priory fell from 961,174 to 883,394 (Office of Rail and Road, Estimates of Station Usage). This may be explained by the fact that the line between Dover Priory and Folkestone West was closed for a number of months in 2016 whilst emergency repair works were carried out on the sea wall adjacent to the railway line. The decline in passenger numbers in 2015/16 is concerning and will need to be monitored, especially as passenger volumes at Dover Priory are still relatively modest compared to other stops on the High Speed line. Efforts need to be made to capitalise more on the High Speed line in the District through the construction of additional car parking facility, adjacent to the railway station.

#### **Environment**

- 1.19 Measures have been taken over the monitoring year to improve the environment in the District. The Council completed the St Radigunds play area project during the monitoring period at Triangles Community Centre in Coombe Valley, Dover. In addition, other play are providers have also been actively increasing capacity of their facilities such as Wingham Parish Council replaced a local play area to provide a Multi-Use Games Area, opened in March 2017.
- 1.20 The Council's adopted Parks and Amenity Open Spaces Strategy placed a very high priority on raising standards and capacity at the District's most popular park, Kearsney Abbey. The project to restore Kearsney Abbey and Russell Gardens secured a £3million grant in July 2016, the project will run until June 2020.
- 1.21 The District has a rich and varied historical landscape and over the monitoring period there has been one new heritage designation in the District, namely a pair of acoustic mirrors in the Fan Bay as a scheduled monument. Furthermore, the Heritage Strategy identified the need for a programme of Conservation Area appraisals in order to facilitate understanding of the special interest of the Conservation Areas, and to enable management and monitoring of the areas through the development of guidance and advice, and the widening of Article 4(2) Directives. In the monitoring period the Heritage team have progressed with:
- Nelson Street Deal Conservation Area Appraisal the Appraisal drafted by the Deal Society was adopted in January 2017 and work has progressed on implementing an Article 4 Direction on the newly defined conservation area to manage changes; and
- Waterloo Crescent Conservation Area Appraisal the draft appraisal was prepared by the Regeneration Delivery Section in the early autumn of 2016 and consultation is to be held during the next monitoring period.

- 1.22 A review of the District's historic parks and gardens is also underway and reports are expected to be available from spring 2018.
- 1.23 Additionally, KCC is continuing to develop an Urban Archaeological Database for Dover to help planners and developers prepare and assess development proposals to help conserve Dover's remarkable heritage. The first phase of this work is expected to be completed by autumn 2017.

#### **Housing and Infrastructure Delivery**

- 1.24 Whilst the Council experienced the highest housing completion figure since 1989 of 726 dwellings during the last monitoring period, a total 406 net completions were recorded during 2016/17; Currently, there are 4,196 units which have planning permission, however are not started and 387 units which are under construction in the District, which should help to maintain the rate of housing completions in the District over the coming years. Using the Objectively Assessed Need for housing, identified in the Council's Strategic Housing Market Assessment (SHMA, 2017) the Council is able to demonstrate that the District has a 5 year Housing Land Supply of 5.80 years.
- 1.25 Although there has been a decline in housing completions this monitoring period, there are very encouraging signs that a range of allocated housing sites across the District are continuing to come forward for development, as 63% of total completions have come from housing allocations. The Development Plan allocates sites to deliver approximately 10,273 homes across the district.
- 1.26 To date, 4,211 homes have been granted planning permission on allocated sites (221 within this monitoring period) and 1,023 of these homes are now completed (248 within the monitoring period). Total housing allocations granted planning permission is lower than that granted in 2015/16. Whilst it is encouraging that the Council's housing allocations are starting to come forward, completions are still behind schedule and a large amount of development in the District still comes from windfall sites (37%), indicating that it is not Plan-led development. The majority of development over the monitoring period occurred in Deal (179 units), followed by Dover 87 units) and Aylesham (78 units). The Strategic allocation at Whitfield (where the majority of the development is planned for Dover) being significantly behind target having only delivered 91 homes to date (out of 5,750 planned), although work on the construction of a new roundabout on the A256 is now complete.
- 1.27 Of the 1,006 dwellings granted permission during the monitoring year, 775 were houses,196 flats, 28 bungalows and 7 maisonettes. Approximately, 6% of dwellings granted planning permission over the monitoring period had 1 bedroom; 28% had 2 bedrooms; 44% had 3 bedrooms and 22% had 4 bedrooms plus. Comparing these figures with requirements under Policy CP4 on housing mix shows that we are under delivering on 1 and 2 bedrooms units, on target for 3 bedroom units and over the policy target on 4 bedroom units.

- 1.28 Over the monitoring period, 91 affordable houses were granted permission in the District on 5 sites. However, the Council only achieved its target of 30% affordable housing on two sites: The Old Sorting Office, Charlton Green, Dover and land adjacent to allotments, Folkestone Road, Dover. Further to this, during the monitoring period, 78 affordable homes were completed in the District on two sites: Aylesham and Timperly Place Sholden (Deal). This equates to 19.2% of all housing completions. This is lower than that achieved during 2015/16 where 185 affordable homes were delivered equating to 25.48% of total completions.
- 1.29 Whilst progress is being made with the delivery of affordable housing within the Dover District, the SHMA (2017) advised that in order to meet housing need, 167 affordable homes should be delivered in the district per annum. It is clear that the level of affordable housing delivery in the District is below this level (with the exception of 15/16) and indicates the need to review the Council's strategy to affordable housing provision as part of the preparation of the new District Local Plan. Whilst accepting that delivery of 167 affordable homes per year is unlikely to be achieved.
- 1.30 During 2016/17, 23 residential units have been gained through permitted development rights, the largest number since the right was introduced in 2015. This clearly shows that the Government's policy of allowing residential properties in the countryside is having a noticeable impact on the District.
- 1.31 With regard to infrastructure delivery, since the last monitoring period the Council received £744,518 in S106 contributions from developments across the district. Of this figure, DDC received £543,703 to assist in the delivery of: affordable housing, children's play space, community space, the Thanet Coast Mitigation Strategy, a community development officer for Aylesham Garden Village, and school playing pitches. The remainder of the contributions were passed to Kent County Council (KCC) for the delivery of transport projects, libraries, social facilities and education.
- 1.32 Contributions secured through S106 agreements in this monitoring period are £379,875 less than that received during 2015/16. This can be explained in part by the fall in the number of housing completions as S106 payments are often triggered on commencement of development or by a certain number of occupations and as a result there is a correlation between housing activity/completions and S106 collections.
- 1.33 During this monitoring period the Council submitted a planning application for the relocation of a new £26m Dover District Leisure Centre based in Whitfield; meeting recommendations and objectives set out in the Land Allocations Local Plan (2015) and Indoor Sports Facilities Strategy. Work is now well underway on site.

#### 1.2 Direction of Travel

1.34 Table 1.1 below sets out the direction of travel of the key matters raised in the key findings from the last monitoring period (2015/16) to this monitoring period (2016/17).

Table 1.1 Direction of Travel from 2015/16 to 2016/17

Social	
Population	<b>4&gt;</b>
Ageing population	<b>4</b> >
Deprivation levels	<b>4</b> >
Economy	
Net employment floorspace	▼
Number of jobs	<b>4</b> >
Job density	▼
Skill attainment levels	<b>A</b>
Retail floorspace built	<b>A</b>
Leisure floorspace built	▼
Vacancy rates	
Dover	<b>A</b>
Deal	<b>A</b>
Sandwich	<b>4</b> >
Passenger numbers from Dover Priory Station	▼
Environment	
Play areas/ open space	<b>A</b>
Historic Environment	<b>A</b>
Housing and Infrastructure Delivery	
Housing completions	▼
5 year Housing Land Supply	▼
Allocated sites granted permission	▼
Allocated sites completions	▼
Housing mix	
1-bed homes	<b>A</b>

#### 11

# one Overview

2-bed homes	▼
3-bed homes	<b>◆▶</b>
4-bed homes	▼
Affordable housing	▼
S106 contributions	▼

Table 1.2

# Key

▲ Value Increased

▼ Value Decreased

**◄▶** Value Unchanged

### 12

# Introduction

# two Introduction

#### 2 Introduction

#### What is the Authority Monitoring Report?

- 2.1 This is the thirteenth AMR produced by DDC and covers a period from 1st April 2016 to 31st March 2017 (the monitoring period).
- 2.2 The AMR serves a number of purposes:
- to assess the performance of the Council's current planning policies and to monitor the delivery of the Council's adopted Development Plan;
- to assess changes in the structure and health of the population in the District;
- to record of the amount of development which has taken place in the District during the monitoring period;
- to look at the health of the District's centres and capture changes in retail floorpsace;
- to capture the level of housebuilding that has been taking place in the District and review the distribution of housebuilding and the type of housing that is being delivered:
- to look at changes in the economy and employment floorspace in the District;
- to monitor the impact of development on the environment;
- to capture progress of the delivery of the Council's strategic land allocations;
- to set out projections and expectations for future development in the District, and assess where policies and approaches may need to change; and
- to set out the Council's progress against its 'Local Development Scheme', a high-level project plan for the production of new planning documents and policies.
- 2.3 Copies of previous AMRs are available and can be downloaded via the District C o u n c i l ' s w e b s i t e : <a href="https://www.dover.gov.uk/Panning/Panning-Policy-and-Regeneration/Plan-Monitoring/Authority-Monitoring-Report.aspx">https://www.dover.gov.uk/Planning/Planning-Policy-and-Regeneration/Plan-Monitoring/Authority-Monitoring-Policy-and-Regeneration/Plan-Monitoring/Authority-Monitoring-Policy-and-Regeneration/Plan-Monitoring/Authority-Monitoring-Report.aspx</a>

#### What are the key components of the Authority Monitoring Report?

- 2.4 The Council has a set of its own contextual indicators and local indicators in the adopted Core Strategy. The Government's Planning Practice Guidance (PPG) details various pieces of information which Local Planning Authorities (LPAs) should report annually, but is otherwise not prescriptive on what an AMR should contain.
- 2.5 The PPG states that local planning authorities must publish information at least annually that shows progress with Local Plan preparation; report any activity relating to the duty to cooperate; and show how the implementation of policies in the Local Plan is progressing. Furthermore, LPAs are encouraged to report as frequently as possible on planning matters to communities. This is important to enable communities and interested parties to be aware of progress.
- **2.6** LPAs can also use the AMR to provide up-to-date information on the implementation of any neighbourhood plans that have been made, and to determine whether there is a need to undertake a partial or full review of the Local Plan.

# two Introduction

- 2.7 Regulation 34 of the Town and Country Planning (Local Planning) (England) Regulations 2012 sets out what information the reports must contain, although there is other useful information that can be set out. In particular, the reports can highlight the contributions made by development, including section 106 planning obligations, Community Infrastructure Levy and New Homes Bonus payments, and how these have been used.
- 2.8 The AMR should be made publicly available.

#### Structure of the Authority Monitoring Report

- 2.9 In light of the above, the structure of the AMR is as follows:
  - **Chapter 3 The District and its People** providing a spatial portrait of the District and an overview of the population and health profile of the area.
  - **Chapter 4 Planning for the Future** summarising the work undertaken to plan for the future of the District, as well as progress against the Local Development Scheme (LDS), neighbourhood planning and meeting the requirements of the duty to co-operate.
  - **Chapter 5 Monitoring of Current Policies** reviewing the effectiveness of development management policies and the implications of the introduction of permitted development rights.
  - **Chapter 6 Retail, Services and Facilities** looking at the health of the District centres, including the amount of new retail, service and facility floorspace built during the monitoring year.
  - **Chapter 7 Housing** detailing the Council's progress regarding housing delivery, looking at affordable housing provision, Gypsy and Traveller accommodation and future housing land supply.
  - **Chatper 8 The Economy** identifying changes in employment floorspace, jobs, unemployment levels and skills in the District over the monitoring period.
  - **Chapter 9 Environment and Sustainability** assessing the District's environment and the sustainability of new development; across a range of top including the historic environment, open space, energy and transport.
  - **Chapter 10 Infrastructure** reviewing the Council's performance regarding the delivery of infrastructure required to support development and the Council's position in relation to funding mechanisms such as the Community Infrastructure Levy (CIL) and developer contributions.
  - **Chapter 11 Strategic Sites** detailing an update on the progress of the Council's strategic sites set out in the adopted Development Plan.

# The District and its People

### 3 The District and its People

3.1 This chapter provides a spatial portrait of the District and looks at the population and health profile of the area.

### 3.1 Geography

- 3.2 The Dover District is situated on the East Kent peninsula and covers an area of 31,982 hectares (ha). The District is bordered by Thanet to the north, Shepway to the south west and Canterbury to the north west. To the south/south east of the District is the English Channel; putting Dover at both the centre of surface travel to and from continental Europe and on the edge of domestic economic activity. See Figure 3.1: Map of the District.
- 3.3 The District contains three main towns: Dover, Deal and Sandwich, and has a large rural area with a variety of villages and smaller settlements. The total population of the district is 113,100 <sup>(1)</sup>.



Figure 3.1 Map of the District

#### Dover

Dover is the District's principal town and has a population of 44,390<sup>(2)</sup>. The town provides the main convenience and comparison retail offer for the District, and White Cliffs Business Park is one of the key sources of employment in the area. The town is also home to the Port of Dover which is Europe's busiest ferry port and a vital international gateway for the movement of passengers and trade. The Port of Dover is an award-winning cruise port, the second busiest in the UK, hosting some of the world's most prestigious cruise-liners and is an important source of employment in the district. <sup>(3)</sup>.

#### Deal

3.5 Deal, the second largest town in the District, with a population of 30,100 <sup>(4)</sup>, is a seaside town, predominantly residential in nature, with an attractive town centre and good retail offer. Commercial activity tends to be small scale, locally based, and dominated by town centre businesses. The northern part of Deal and the countryside between Deal and Sandwich, is subject to the risk of tidal flooding which is a constraint to development.

#### Sandwich

**3.6** Sandwich, the third largest town, with a population of 7,040 <sup>(5)</sup>, is a historic Cinque Port market town, renowned for its medieval street pattern and high concentration of listed buildings. The Discovery Park Enterprise Zone to the north of Sandwich is also a major employment centre, with over 150 resident companies, generating 3,346 jobs. An international golf course lies to the immediate east of the town, and a second golf course of national importance lies to the north east of the town, both of which are important contributors to the local economy and profile of the area.

#### **Rest of the District**

- 3.7 The District is connected to the main highways network by the M20/A20 and M2/A2 corridors, which provide a direct connection to London. High speed rail links also connect Dover, Deal, Sandwich and Martin Mill to London and the wider rail network.
- 3.8 The Dover District is a diverse maritime area characterised by contrasting landscapes and a rich heritage. Key features of the district include:
- a variety of natural assets including, 20 miles of coastline, 2,000 hectares (ha) of broad leaved woodland, 2,211 ha of land is designated as Sites of Special Scientific Interest, 28,110 hectares of agricultural land, two main rivers The River Dour and The River Stour; and 391 miles of public rights of way;
- about 6,900 ha (21%) of the District is designated as part of the Kent Downs Area of Outstanding Natural Beauty (AONB) and of this 876 ha (3%) is designated as Heritage Coast;
- the District contains the spectacular Norman Castle at Dover, the Tudor castles
  of Deal and Walmer and the Roman castle at Richborough, as well as around
  46 scheduled monuments, approximately 2,800 listed buildings and 57
  conservation areas; and
- there are a range of sports and leisure facilities on offer in the district including leisure centres, swimming pools, country parks, off road cycle track, gardens, play areas, cinemas, theatres and museums. The district is also famous for its golf courses including the Royal St. George's in Sandwich, which has hosted the Open Championship.

- 3.9 However, despite its character and location in the prosperous South East Region, the District suffers a number of problems:
- Dover Town has some of the most deprived wards in the country;
- unemployment levels are above the national average;
- parts of the District are at risk from flooding from both fluvial and tidal sources;
- Dover Town Centre is struggling to compete with neighbouring shopping areas, such as Canterbury, which is drawing trade out from Dover;
- traffic congestion associated with the Port of Dover, which also leads to poor air quality; and
- the health of people in Dover is varied compared with the England average. Life expectancy for both men and women is slightly below the England average.

### 3.2 Population

3.10 This section sets out the population profile of the District, looking at how the population has changed since 2001, comparing the latest population projections for the District to the Core Strategy Indicators for population growth, and how the profile of the District's population is forecast to change in the future.

#### Changes in Population 2001 - 2014

- 3.11 The Adopted Core Strategy (2010) identifies the importance of population growth in the District, particularly within working age families to support growth in the local economy.
- 3.12 The 2014 Sub-National Population Projections (SNPP) published by the Office of National Statistics (ONS) in June 2016 show that the total population of the District is 113,100 and that the working age population (16-64 years) is 67,700, the non-working age population is 45,400. (6)
- 3.13 Table 3.1 compares the 2014 SNPP with Core Strategy Indicator 1 (population and labour supply growth):

Table 3.1: Dover Population Comparison Figures

Dover Population Comparison Figures				
	Baseline Figure	Core Strategy Target for 2026	Total Population (2014 SNPP)	Difference between 2026 target and 2014 SNPP
Total Population	104,800 (2007)	111,500	113,100	1,600

Dover Population	Dover Population Comparison Figures				
Working Age Population (16-64 years)	73,800 (2001)	72,100	67,700	-4,400	

- Table 3.1 shows that whilst the total population of the District has already exceeded the Core Strategy target of 111,500 people by 2026, the proportion of working age population has declined and is lower than the level forecast in the Core Strategy (2010). It is clear that the Core Strategy objective in relation to the percentage of working age population in the district has not been met. Additionally, over the same period the District has seen a decline workforce jobs which is an important factor in attracting and retaining working age families to the district. Reasons for a decrease in working age population could also be a result of an overall ageing population across the district. The reasons for the increase in total population in the district are explored below.
- Between mid-2001 and mid-2014<sup>(7)</sup> the population of the Dover District has risen by approximately 8,400 to reach 113,100. This increase is made up of natural change -800 (with deaths outnumbering births) and an increase from net migration and other changes of 9,200 persons.
- 3.16 Key trends over the 13 year period include:
- whilst annual births have increased and deaths have varied little, natural change is negative and has switched from an annual loss of around 200 between 2001 and 2004, to gains or very modest losses after 2005/06;
- net migration from within the UK has been the main driver of population increase but has varied between gains of over 800 in 2003/04 to a loss of nearly 200 in 2008/09;
- net overseas migration has been positive in most years with a maximum of over 200 in 2009/10;
- regarding the profile of migration into the district, the District loses younger age adults, most likely migrating for university or other 'bright lights'. However, this rebounds in the early 20s and subsequent inward migration is spread though middle ages. There is also some evidence of retirement-related migration at the older ages but this is much less than may be observed elsewhere along the coast. The migration profile is more balanced than would be observed in a true 'retirement' destination district;
- the net result is that the population has risen in all years since 2001 but at very different annual levels varying between less than 50 and over 1,100; and
- the population has aged as the resident population has aged and also due to older in-migration.

#### **Future Population Projections**

- 3.17 In the future, for the period 2014 2037 population projections show that the population of the Dover District will increase from 113,100 to 127,200 people (12.4% increase). This is predominantly due to domestic migration flows, as natural change remains negative (i.e. there are more deaths than births each year).
- 3.18 The ONS 2014 SNPP shows that the Dover District will attract nearly 18,500 new residents via migration over the period 2014 2037. It is anticipated that the majority of this will be 'domestic' migration flowing from elsewhere in the UK. By 2036 (the end of the projection period) domestic migration runs at 900 persons per year are anticipated compared to 100 international migrants.
- 3.19 Natural change will however continue to be negative as the ONS 2014 SNPP projections foresee an increase of approximately 550 deaths compared to 480 births per annum between 2014 and 2037.
- 3.20 Figure 3.2 shows the affect of the changed components on the age structure at 2037. The most significant change is the reduction in the projection of persons aged over 90 years. This reduction has a knock-on effect on the household projections, as the elderly living in private households have the highest overall household representative rates. This group also has a high likelihood of requiring residential care. In general, the projection is higher at all other ages.




Figure 3.2 Dover District Age Structure at 2037. ONS 2012 SNPP and ONS

#### **Changes in Households**

3.21 The 2011 Census revealed that since 2001 the number of households in the Dover District has increased by 9.0%, reaching 48,310 households in total. This compares to the regional average of 8.2% and the national figure of 7.9%. In the District the number of households has risen at a faster rate than the population in

households between 2001 and 2011; implying a decline in the average size of households across Dover District (as is illustrated in Table 3.2), which reflects regional and national trends.

Table 3.2 Change in Average Household Size between 2001 and 2011

Location	Average Household Size in 2001	Average Household Size in 2011
Dover	2.29	2.27
South East Region	2.37	2.34
England	2.38	2.36

3.22 The 2011 Census also indicates that there are more single person households and fewer couple households with dependent children in the District than are recorded regionally and nationally. Furthermore, over the period 2001 to 2011 the main change in household types has been a growth in 'other' households, followed by lone parent households with no dependent children. It is interesting to note however that households with only non-dependent children have increased notably whilst the number of households with dependent children has decreased. This suggests that household formation rates amongst young adults may have reduced.

### 3.3 Health and Social Wellbeing

3.23 This section provides a health profile of the District, looking at areas of deprivation, life expectancy levels, the general health of the population and what the District's health priorities are.

#### **Indices of Multiple Deprivation**

- 3.24 Deprivation is most comprehensively measured by the ONS Index of Multiple Deprivation (IMD) which ranks each of England's LSOAs small areas with populations of around 1,500 people from 1 (most deprived) to 32,844 (least deprived). The IMD combines seven topics to give a broad coverage of ways by which people can be 'deprived', along with more obvious means of deprivation such as income and employment; it encompasses health, education, skills and training, barriers to housing, and living environment and crime.
- 3.25 The English Indices of Deprivation 2015 <sup>(8)</sup> reinforce previously identified patterns of deprivation across the District. See Figure 3.3 below.




Figure 3.3 Indices of Multiple Deprivation 2015

- 3.26 The District continues to have deprivation 'hot spots' that are amongst some of the most deprived small areas in the country yet are geographically close to some of the least deprived areas in the country. The 4 Lower-layer Super Output Areas (LSOAs) that fall within the most deprived 10% of LSOAs nationally are within the wards of St. Radigunds; Castle; Maxton, Elms Vale and Priory; and Buckland (all within Dover Town), with the LSOA in the St. Radigund's ward also in the top 5% most deprived areas in the country.
- 3.27 From a national perspective, the Dover District is in the most deprived half of local authorities in England.

National rank: 126 (out of 326 English local authority districts) \*

Kent rank: 5 (out of 12 Kent local authority districts) \*

Number of LSOAs in the most deprived 10% nationally: 04 (out of 67 LSOAs

in the district) \*\*

Number of LSOAs in the most deprived 20% nationally: 11 (out of 67 LSOAs

in the district) \*\*

Number of LSOAs in the least deprived 10% nationally: 01 (out of 67 LSOAs

in the district) \*\*

The highest levels of multiple deprivation are found in the urban areas of Dover

\* Where 1 is the most deprived; using the Rank of Average Score

- \*\* LSOAs (or Lower-layer Super Output Areas) are small geographical areas with approximately 1,500 residents or 650 households
- 3.28 The Core Strategy (2010) Indicator 6 is set to measure social disadvantage. In 2007, the District's national ranking was 142 out of 326 authorities (IMD, 2007), showing that the District's national ranking has fallen over the Plan period (2006-2026) and the District is now considered to be more deprived than in 2007. At County level, the District's ranking has however remained the same, and continues to rank fifth out of the 12 Kent local authority districts/boroughs.
- 3.29 Core Strategy Indicator 6 aims to have 6 LSOAs in the most deprived 20% nationally by 2016 and 0 LSOAs in the most deprived 20% nationally by 2026. This target has not been achieved, as at 2016, there are still 11 LSOAs in the most deprived 20% nationally (out of 67 LSOAs in the District).
- 3.30 This illustrates that the Core Strategy objective has not been met and there has instead been a decline in social disadvantage in the District. From this, it is evident that DDC needs to continue to work closely with other partners for example Kent County Council (KCC) and the NHS to address deprivation in the District. A multi agency approach to this important issue is essential as the Planning Department alone cannot influence all of the required strands of deprivation.

#### **Health Profile**

- **3.31** Table 3.3 shows how the health of people in this area compares with the rest of England.
- 3.32 It should be noted that:
- Red value indicates a value significantly worse than the England Value

- Amber value indicates a value that is not significantly different from the England Value
- Green value indicates a value that is significantly better than the England Value but may still be an important public health problem.

Table 3.3 Source Public Health England 2017

Health Summ	ary for Dover 2010	6					
Domain	Indicator	Period	Local No total count	Dover District Value	England Value	England Worst	England Best
Our Communities	1 Deprivation score (IMD 2015)	2015	n/a	21.6	21.8	42.0	5.0
	2 Children in low income families (under 16s)	2014	4,380	22.9	20.1	39.2	6.6
	3 Statutory homelessness	2015/16	15	0.3	0.9		
	4 GCSEs achieved	2015/16	617	53.7	57.8	44.8	78.7
	5 Violent crime (violence offences)	2015/16	2,155	19.1	17.2	36.7	4.5
	6 Long term unemployment	2016	285	4.2	3.7	13.8	0.4
Children's and young people's health	7 Smoking status at time of delivery	2015/16	181	16.3	10.6	26.0	1.8
	8 Breastfeeding initiation	2015/16	731	x	74.3	47.2	92.9
	9 Obese children (Year 6)	2015/16	232	21.5	19.8	28.5	9.4
	10 Alcohol-specific hospital stays (under 18)	2013/14 - 15/16	15	21.9	37.4	121.3	10.5
	11 Under 18 conceptions	2015	53	26.3	20.8	43.8	5.4
Adults' health and lifestyle	12 Smoking prevalence in adults	2016	n/a	17.7	15.5	25.7	4.9

Health Summ	Health Summary for Dover 2016						
Domain	Indicator	Period	Local No total count	Dover District Value	England Value	England Worst	England Best
	13 Percentage of physically active adults	2015	n/a	56.4	57.0	44.8	69.8
	14 Excess weight in adults	2013 - 15	n/a	67.6	64.8	76.2	46.5
Disease and poor health	15 Cancer diagnosed at early stage	2015	275	48.2	52.4	39.0	63.1
	16 Hospital stays for self-harm	2015/16	202	192.9	196.5	635.3	55.7
	17 Hospital stays for alcohol-related harm	2015/16	617	531.5	647	1163	374
	18 Recorded diabetes	2014/15	6,251	7.1	6.4	9.2	3.3
	19 Incidence of TB	2013 - 15	12	3.5	12.0	85.6	0.0
	20 New sexually transmitted infections (STI)	2016	309	448.7	795	3288	223
	21 Hip fractures in people aged 65 and over	2015/16	151	606.8	589	820	312
Life expectancy and causes of death	22 Life expectancy at birth (Male)	2013 - 15	n/a	79.3	79.5	74.3	83.4
	23 Life expectancy at birth (Female)	2013 - 15	n/a	82.6	83.1	79.4	86.7
	24 Infant mortality	2013 - 15	15	4.3	3.9	8.2	0.8
	25 Killed and seriously injured on roads	2013 - 15	123	36.3	38.5	103.7	10.4

Health Summ	Health Summary for Dover 2016						
Domain	Indicator	Period	Local No total count	Dover District Value	England Value	England Worst	England Best
	26 Suicide rate	2013 - 15	27	8.9	10.1	17.4	5.6
	27 Smoking related deaths	2013 - 15	N/a	N/a	283.5		
	28 Under 75 mortality rate: cardiovascular	2013 - 15	238	70.9	74.6	137.6	43.1
	29 Under 75 mortality rate: cancer	2013 - 15	486	142.6	138.8	194.8	98.6
	30 Excess winter deaths	Aug 2012 - Jul 2015	208	17.7	19.6	36.0	6.9

- 3.33 The above table illustrates that the health of people in the Dover District is varied compared with the England average, with more red and amber lights, than green. Key areas of concern include:
- 23% (4,400) of children live in low income families;
- in Year 6, 21.5% (232) of children are classified as obese;
- low levels of GCSE attainment worse than the national average;
- estimated levels of adult excess weight are worse than the England average;
- high levels of smoking related deaths worse than the average for England.
   Estimated levels of adult smoking are also worse than the England average;
- the rate of violent crime is worse than average:
- levels of teenage pregnancy are worse than the England average; and
- life expectancy for both men and women is slightly lower than the England average. However, life expectancy is 7.7 years lower for men and 2.7 years lower for women in the most deprived areas of Dover than in the least deprived areas.
- 3.34 Given this, the health priorities in Dover include improving life expectancy by preventing suicide and heart disease and reducing smoking prevalence, improving teenage pregnancy rates, and improving physical activity in children and adults. The majority of these issues fall outside the remit of town planning but clearly there is a need to work closely with relevant health partners to establish ways in facilitating healthier lifestyles across the district.

### 4 Planning for the Future

4.1 This chapter summarises the work that the Council is undertaking to plan for the future of the District and sets out progress with the preparation of the new District Local Plan. Furthermore, the chapter also summarises progress made against the LDS, how the Council is working with parish councils to deliver neighbourhood plans and how the Council is meeting its obligation under the duty to co-operate.

### 4.1 Current Planning Policies

- **4.2** Decisions on planning applications are taken in accordance with adopted planning policies, unless material considerations indicate otherwise. The Development Plan for the District comprises:
- KCC Minerals and Waste Local Plan 2013 2030 (2016);
- The Adopted Core Strategy (2010);
- The Land Allocations Local Plan (2015);
- Worth Neighbourhood Plan (2015);
- Saved Local Plan Policies (2002); and
- Policies Map.
- 4.3 The Council has also produced a number of Supplementary Planning Documents (SPDs) and guidance, which expand on policies in the Development Plan or cover specific areas of the District. The adopted SPDs and Guidance include:
- Whitfield Masterplan;
- Affordable Housing SPD and Addendum;
- The Kent Design Guide 05/06;
- Dover Western Heights Masterplan;
- Kingsdown Conservation Area Character Appraisal:
- Dover District Heritage Strategy;
- Affordable Housing Rural Exception Schemes;
- Aylesham Masterplan;
- Buckland Mill Planning Brief;
- Dover Town Centre Conservation Area Character Appraisal;
- St James's Area Dover Planning Brief;
- Security Measures for Retail and Commercial Premises;
- York Street Site Dover Planning Brief;
- Flat Conversion Guidelines:
- Walmer Design Statement; and
- Preston Village Design Statement.

#### 4.2 Local Plan Review

4.4 The Council is starting work on a new District Local Plan which will guide the future growth and development of the District to 2037.

#### What is the Local Plan?

- 4.5 The new District Local Plan is an extremely important document for the future of the Dover District. It will be the blueprint for growth in the District; contain the over-arching planning strategy for the District; identify sites where development will happen over the next 20 years; and will guide decisions on planning applications. The new District Local Plan will comprise:
- a vision for the future of the District;
- the amount of housing, employment and retail development needed in the District;
- strategic policies;
- development management policies;
- site allocations; and
- policies map.
- 4.6 The new District Local Plan must comply with government policy and be justified by evidence. Once adopted, it will replace the Dover District Core Strategy (2010), Saved Policies from the 2002 Local Plan and the Land Allocations Local Plan (2015) (together known as the Development Plan) and will cover the period from 2014 to 2037.

#### What is the process of preparing a District Local Plan

4.7 The process of producing a Local Plan involves the following stages:

#### **Local Plan Preparation Process**

#### 1. Evidence gathering (ongoing)

The Council is in the process of preparing a number of studies to support the new District Local Plan, see table 4.2. The Council will carry out both formal and informal engagement with a range of stakeholders as the preparation of the new District Local Plan and evidence base documents advances.

#### 2. Call for Sites (completed summer 2017)

As part of the preparation of the Housing and Employment Land Availability Assessment (HELAA) the Council undertook a 'call for sites' exercise in the summer of 2017 inviting developers, land owners, agents and the local community to submit sites to the Council for assessment in order to ascertain whether they are suitable for inclusion within the Local Plan. Any sites that have been submitted will be assessed by the Council in the new year in order to determine their suitability, availability, achievability and deliverability. Such sites will also be subject to a SA/HRA.

# 3. Regulation 18 - Issues and Options consultation (October/November 2018)

The Council will consult on the scope of the issues that the new District Local Plan will need to address and the potential strategy for responding to such issues, in accordance with Regulation 18 of the Town and Country Planning (Local Planning) (England) Regulations 2012.

Responses received as part of this consultation will then be reviewed and be used to help inform the development of a draft District Local Plan.

#### 4. Preparation of the Local Plan (December 2018 - August 2019)

Following on from the issues and options consultation the Council will start to prepare a draft Local Plan. The District Local Plan will be prepared in consultation with key stakeholders and will incorporate key findings from the Council's evidence base.

# 5. Regulation 19 - Publication version of the Local Plan (September/October 2019)

In accordance with Regulation 19 of the Town and Country Planning (Local Planning) (England) Regulations 2012, the Council will publicise the version of the Local Plan to be submitted to the Planning Inspectorate for examination. The publication version of the District Local Plan, will include a vision for the future of the Dover District; a set of strategic policies allocating land for future housing, employment, retail development, as well as green infrastructure and open space;

and development management policies. Any representations submitted at this stage of the process will be forwarded to an independent Inspector who will be appointed to examine the Local Plan.

# 6. Submission of Local Plan to the Secretary of State for examination (January 2020)

Having received any representations on the publication version of the Local Plan, the Council will submit the Plan and any proposed changes it considers appropriate along with supporting documents to the Planning Inspectorate for examination on behalf of the Secretary of State.

#### 7. Examination of the Local Plan by a Planning Inspector (April/May 2020)

The examination commences upon submission of the Local Plan to the Planning Inspectorate and concludes when the Inspector's Report is issued to the LPA. During the formal examination process, a Planning Inspector will assess whether the Local Plan has been prepared in line with the relevant legal requirements (including the duty to cooperate) and whether it meets the tests of 'soundness' contained in the NPPF (2012). The Inspector will consider the representations received during the Regulation 19 consultation, and where appropriate, will invite individuals or organisations who submitted representations to appear at examination hearings. Following the examination, the Inspector will produce a report in order to determine whether or not the plan can be considered to be 'sound'. This report may include 'main modifications' to the District Local Plan where the Inspector feels that these are necessary to ensure that the Plan is sound.

#### 8. Adoption of the Local Plan (July 2020)

The final stage in the plan making process is the formal adoption of a Plan. In accordance with the Council's constitution, the adoption of the District Local Plan must take place at a meeting of Full Council. Following adoption, the District Local Plan will become the main document against which decisions on planning applications will be made.

4.8 The timetable for the preparation of the new District Local Plan is set out in the Council's LDS (September 2017) and can be downloaded via the following w e b s i t e : <a href="https://www.dover.gov.uk/Planning/Panning-Policyand-Regeneration/Plan-Monitoring/Local-Development-Schemeaspx">https://www.dover.gov.uk/Planning/Planning-Policyand-Regeneration/Plan-Monitoring/Local-Development-Schemeaspx</a>

#### **Key Challenges for the Local Plan**

- **4.9** Looking to the future there are a number of key challenges that the District Local Plan must address:
- to provide 12,167 new homes by 2037 to meet the Objectively Assessed Need for housing identified in the SHMA (2017);

- identify sufficient land to meet future development needs over the next 20 years;
- identify and deliver key infrastructure to support future growth;
- to promote good transport links both within the district, and beyond;
- to tackle congestion, air quality and provide more sustainable transport alternatives in the district;
- provide sufficient employment land to deliver the projected 2,700 jobs forecast to be delivered in the district over the period to 2037 to strengthen the District's economic position in East Kent;
- provide improved education and training facilities to ensure that local people are better equipped to join the workforce;
- strengthen Dover town centre building on the momentum that is being created by the DTIZ development;
- the need to plan for an ageing population;
- tackle deprivation in the district and address health inequalities;
- meet the challenge of climate change by considering setting targets for renewables and low carbon energy; and
- to deliver growth in the district whilst preserving and enhancing the District's key natural and historical assets.

#### What the Local Plan will Cover?

- 4.10 It is proposed that the Local Plan will comprise the following sections:
- an introduction to Local Plans, a description of the district in 2017 and the challenges it faces;
- the overarching spatial strategy for the district, including the key diagram, vision, targets for growth, growth delivery strategy and approach to delivering healthy and sustainable communities;
- topic specific policies, including development management policies;
- settlement and site specific policies; and
- implementation and monitoring.

#### 4.3 Planning Documents Under Preparation

**4.11** The Council is currently in the process of producing a number of new planning documents (see Table 4.1); updating the evidence base that supports the Local Plan; and proactively working with parish councils to bring forward Neighbourhood Plans in the District. This section provides an update on the Council's progress with bringing forward these documents:

### **Progress Against the Local Development Scheme**

4.12 In March 2017 the Council's Cabinet made the decision to proceed with a review of the current Core Strategy (2010) and Land Allocations Local Plan (2015), and produce a new NPPF compliant District Local Plan.

- 4.13 Since the LDS was adopted in March 2017, the Council has had legal advice regarding the preparation of a Dover Waterfront Masterplan. It was advised that the Masterplan cannot be prepared as a SPD and must instead be a standalone Development Plan Document. As a result, the Council adopted a revised LDS in September 2017, which includes a revised timetable for the production of the Dover Waterfront Area Action Plan (AAP), as well as the District Local Plan and therefore supersedes the LDS dated March 2017.
- 4.14 The current and previous LDSs are available to view on the Council's website: <a href="https://www.dover.gov.uk/Planning/Panning/
- 4.15 Table 4.1 sets out the timetable for the preparation of the documents in the current LDS (September 2017) and notes the Council's progress against meeting key milestones.

Table 4.1 Progress Against the LDS

Planning Document	Timetable	Progress Against Meeting Timetable
District Local Plan (including SA and HRA)	Reg 18 Consultation: Oct/Nov 2018  Reg 19 Consultation (publication): Sept/Oct 2019  Submission: Jan 2020  Examination: Apr/May 2020  Adoption: Jul 2020	Work is underway on the preparation of the District Local Plan.  The Council has commissioned a number of studies to support the preparation of the Local Plan (see below) and also undertook a 'call for sites' consultation from June to August 2017 inviting landowners and developers to put forward land for development for the Plan period (2014-2037).  A Local Plan Engagement Strategy has been produced which sets out how the Council will engage residents, businesses and key stakeholders in the preparation of the Local Plan.  The Council has also set up a Planning Advisory Group to steer the production of the Local Plan, the agenda and minutes of which are available to view online.

Planning Document	Timetable	Progress Against Meeting Timetable
Dover Waterfront AAP	Reg 18 Consultation: Jan/Feb 2018  Reg 19 Consultation(publication): Jun/Jul 2018  Submission: Oct 2018  Examination: Jan 2019  Adoption: Jun 2019	The previous version of the LDS identified the Dover Waterfront AAP as being progressed as either a SPD or a residual Local Development Document (LDD). As a result of a recent High Court case, it has become clear that work on the Dover Waterfront AAP and the associated public realm works cannot be prepared as a SPD or as a residual LDD because the emerging proposals involve land beyond that allocated under Policy CP8 to accommodate a cable car connection from the town centre to Dover Castle and proposals for new development along the new Marina Curve. Without the inclusion of these it would not have the added advantage of enabling the scheme to make a really positive contribution to the regeneration of the town.  As a result of this, the proposals need to be prepared as a Development Plan Document and examined by an independent Inspector on behalf of the Secretary of State before it can be adopted by the Council. Once it has been adopted by the Council it will have the same planning status as the District Local Plan and will form part of the Council's new Development Plan.
Statement of Community Involvement	Consultation: Jun/Jul 2017 Adoption: Sept 2017	The Statement of Community Involvement (SCI) was agreed by the Council on the 9th May 2016. The SCI will be updated to reflect the changes introduced by the Neighbourhood Planning Act 2017.
Waterloo Crescent Conservation	Consultation: Mar 2017 Adoption: May 2017	Following consultation in early 2017, the Waterloo Crescent Conservation

Planning Document	Timetable	Progress Against Meeting Timetable
Area Character Appraisal		Area Character Appraisal was adopted in May 2017.
South Barracks Conservation Area Character Appraisal	Consultation: May/Jun 2017 Adoption: Nov 2017	A consultation on the South Barracks Conservation Area Character Appraisal was held between 15th August and 25th September 2017. It is anticipated that the South Barracks Conservation Area Character Appraisal will be adopted in November 2017.

**4.16** Whilst the Council is committed to bringing forward all the documents set out in the LDS, some milestones have been missed, due to the need for a change in the approach towards the work on the Dover Waterfront AAP, resource constraints and competing priorities.

### **Evidence Base Update**

- **4.17** The NPPF (2012) places responsibility on each LPA to "ensure that the Local Plan is based on adequate, up-to-date and relevant evidence about the economic, social and environmental characteristics and prospects of the area".
- 4.18 The Council is in the process of updating the following evidence base studies to support the preparation of the new District Local Plan:

Table 4.2 Completed evidence base studies

Evidence Base Study		Description		
Completed evidence base studies				
Indoor Sports Facilities Study	The Sports Consultancy Jul 2016	This study sets out an audit and assessment of indoor sports facilities, providing an understanding of current demand and future supply of indoor sporting facilities, as well as recommendations in delivering sporting outcomes for the Dover District.		

Evidence Base Study		Description
Strategic Housing Marking Assessment (SHMA)	Peter Brett Associates Feb 2017	The Council, working jointly with Shepway District Council, commissioned Peter Bretts Associates to undertake a SHMA to identify the OAN for the Dover District for the period 2014-2037, in accordance with the NPPF (2012). This study will be used to underpin the preparation of the new District Local Plan.
Economic Development Needs Assessment (EDNA)	Nathaniel Lichfield & Partners Mar 2017	This study assesses and evidences the need for economic development in the District and identifies the amount of employment land required in the district to support housing growth.
Water for Sustainable Growth Study	Aecom Jul 2017	KCC, along with the Districts commissioned Aecom to identify the water related constraints to growth across the region and to assess whether growth can be delivered within these constraints. The study also looked at the ability of lowering the cost of water related infrastructure.
Dover Air Quality Study	Bureau Veritas Sept 2017	This study assesses the potential air quality impacts on the future development proposals in Dover and sets out an understanding of the potential effect of local pollution concentrations of NO2 and PM10 both on and around site allocations in the adopted Development Plan. This work will also be used to inform the preparation of the Dover Waterfront AAP.
East Kent Growth Framework	Nathaniel Lichfield & Partners Aug 2017	This document is an update of the East Kent Growth Plan (2013) and identifies the opportunities and challenges for East Kent, defines the strategic objectives underpinning the future strategy for growth for East Kent, as well as investment priorities required to deliver such strategic objectives.
Ongoing evidenc	e base studies	s
Dover Transport Study	WSP & Peter Brett Associates	WSP/PB have been appointed by DDC, KCC Highways, Dover Harbour Board (DHB) and Highways England to update the existing transport modellings (e.g. 2007 VISSUM

Evidence Base Study		Description
		transport model) by re-validating existing data and any development that has already happened/is in the pipeline since 2007. This updated model has now been agreed and signed off by Highways England and KCC Highways in conjunction with DDC, to give a Present Year Validated Model that can be used for a range of issues such as identifying highway improvements to Dover Town Centre and assessing the impact of development proposals on the road network. Work on this commission has been put on hold until the distribution of proposed development is known.
Deal Transportation Model	WSP & Peter Brett Associates	DDC in partnership with KCC and Highways England has commissioned WSP/PB to develop a transport model of Deal. The model will be developed by extending the existing Dover Transport Model to cover all the key roads, in and around Deal. As part of the model development, WSP will survey traffic flows to help identify issues such as 'pinch points' and 'rat running'. This information will help to assess the need for new transport infrastructure including possible improved connectivity between Dover and Deal. The model will also be used to assess the suitability of sites put forward by landowners.
		Alongside the modelling work, WSP in partnership with LDA Design will undertake a detailed analysis of the North Deal area. This is a key commitment in the Council's dopted Core Strategy (2010) and will investigate whether place-making and infrastructure solutions can be found to benefit existing residents and identify opportunities to create further development.
Housing and Economic Land Availability Assessment (HELAA)	DDC	The Council is currently undertaking a HELAA to identify sites for housing, employment and retail uses in the District in accordance with the methodology set out in the Planning Practice Guidance. As part of this study, a 'call for sites' exercise was undertaken from June to August

Evidence Base Study		Description
		2017. In the new year officers will assess the suitability, deliverability, availability and acheivability of each site. This work will help inform the scale and distribution of growth across the District required to meet its requirements.
Retail and Town Centre Needs Assessment	Carter Jonas	Carter Jonas has been appointed to undertake an assessment of the retail and town centre needs of the District. This study is currently ongoing and will review the existing retail hierarchy, assess the health of the District's town centres and identify the need for retail and leisure floorspace in the District.
Strategic Flood Risk Assessment	Herringtons	The Council has commissioned Herringtons to undertake a SFRA in accordance with the NPPF (2012) and PPG. This study is ongoing and will update the 2007 SFRA and will assess the flood risk from all types of flooding, taking into account the existing climate and predicted changes in climate, and will allow the Council to identify sustainable locations for development away from flood risk areas. It will also review Coastal Change Management Areas.
Sustainability Appraisal and Habitats Regulations Assessment	Land Use Consultants	Land Use Consultants have been commissioned to to undertake a Sustainability and Habitats Regulations Assessment in accordance with the NPPF (2012) and PPG to support the preparation of the Local Plan. This study is ongoing and will consider and identify the likely effects of the District Local Plan, and assess the extent to which the District Local Plan, when judged against alternatives, will help to achieve environmental, economic and social objectives.
Green Infrastructure Strategy	DDC	The Council is in the process of updating the Green Infrastructure Strategy to support the Local Plan. The Green Infrastructure Strategy will review existing GI provision in the District and identify where new GI assets are required to support growth.

Evidence Base Study		Description
Landscape Character Assessment (LCA)	DDC	The Council is currently undertaking a LCA of the Dover District. This work will look at the different landscape character areas across the District and will be used to inform the preparation of the District Local Plan.
Gypsy, Travellers and Travelling Showpeople Accommodation Needs Assessment	Arc4	The Council has commissioned Arc4 to undertake a Gypsy, Traveller and Travelling Showpeople Accommodation Needs Assessment to identify the number of new Gypsy and Traveller pitches required in the District over the Plan period. This study is ongoing and forms part of a Kent wide study that will identify the need for Gypsy and Traveller accommodation across the county.

### **Community Consultation**

- **4.19** The NPPF (2012) emphasises the need to involve all sections of the community in plan-making. The Council also has a legal duty to consult residents and businesses when appropriate and legislation prescribes who must be consulted at different stages of document preparation.
- **4.20** The Dover District SCI is the means by which the Council aims to facilitate this. The Council's SCI was adopted in May 2016, and identifies who the Council will consult and how they will be consulted as part of the plan making process to ensure plans are as easy to access and understand as possible.
- **4.21** The Council has held the following consultations on key planning documents during the monitoring period:
- Nelson Street Conservation Area Character Appraisal: Consultation on the Nelson Street Conservation Area Character Appraisal has held between 7th October 2016 and 18th November 2016. Four representations were received. The Nelson Street Area Character Appraisal was formally adopted by the Council as a LDD in January 2017.
- Waterloo Crescent Conservation Area Character Appraisal: Consultation on the Waterloo Crescent Conservation Area Character Appraisal was held between 26th January 2017 and 9th March 2017. A total 26 representations were received. The Waterloo Crescent Conservation Area Character Appraisal was formally adopted by the Council in May 2017.

### **Neighbourhood Planning**

- 4.22 The Localism Act 2011 enables local communities to produce Neighbourhood Plans to support development in their area. Upon adoption by the Council, such plans will hold the same weight as other Development Plan documents for the District.
- 4.23 The first stage in producing a Neighbourhood Plan is to designate a Neighbourhood Area. As it stands, there are currently five parish councils in the district with Neighbourhood Area designations who are at different stages of the planning process:
- Worth the Worth Neighbourhood Plan was adopted in January 2015 and now forms part of the Development Plan for the District.
- **Ash** the Parish Council is currently in the process of preparing a Neighbourhood Plan for the area.
- Sandwich Neighbourhood Area designated.
- St Margaret's at Cliffe Neighbourhood Area designated.
- Shepherdswell with Coldred the Parish Council has taken the decision not to proceed with preparing a Neighbourhood Plan.
- **4.24** The Local Authority has a duty to support groups with the preparation of their Neighbourhood Plans and officers will continue to support parishes with the Neighbourhood Planning process.
- 4.25 Neighbourhood plan policies remain in force until the plan policy is replaced.

#### Worth

4.26 Whilst there is no requirement to review or update an adopted neighbourhood plan, PPG highlights that communities in areas where policies in an adopted neighbourhood plan have become out of date may decide to update their plan, or part of it. The Worth Neighbourhood Plan was adopted in January 2015. To date, there has been no indication of the intention to review the policies in this plan and therefore, this settlement will be considered as part of the Local Plan review.

#### Ash

4.27 In the case of Ash, the local community has started work on the preparation of a Neighbourhood Plan for the designated area. Depending on the stage that they reach in the process, a decision will need to be made as to whether to include this particular settlement in the Local Plan review.

#### Sandwich and St Margaret's at Cliffe

**4.28** With regard to Sandwich and St Margaret's at Cliffe, whilst neighbourhood areas have been designated, the preparation of neighbourhood plans have not yet commenced and therefore as it stands both settlements will be included in the Local Plan review.

#### **Shepherdswell and Coldred**

**4.29** As the Parish Council has taken the decision not to progress with the preparation of a neighbourhood plan, this settlement will be considered as part of the Local Plan review.

### 4.4 Duty to Co-operate

- **4.30** The duty to co-operate was introduced in the Localism Act 2011 and places a legal duty on LPAs to engage constructively, actively and on an on-going basis to maximise the effectiveness of local plan preparation relating to strategic cross-boundary matters.
- **4.31** Paragraph 156 of the NPPF identifies the following as strategic issues requiring cooperation:
- the need for and provision of homes and jobs in an area;
- the provision of retail, leisure and other commercial development;
- the provision of infrastructure for transport, telecommunications, waste management, water supply and waste water treatment, flood risk management, the provision of minerals, and energy supply;
- the provision of infrastructure for health, security, community wellbeing and culture;
- Climate Change mitigation and adaption; and
- the conservation and enhancement of the natural and historic environment.
- 4.32 A full list of 'duty to cooperate bodies' is set out in Part 2 of the Local Plan Regulations 2012, and DDC's main duty to cooperate bodies are listed below. However, the nature of the duty means that it would never be possible to produce an exhaustive list:
- Kent and Medway Planning Authorities
- Civil Aviation Authority
- Environment Agency
- Greater London Authority
- Highways England
- Historic England
- Homes and Communities Agency
- South East Clinical Commissioning Group
- Canterbury and Coastal Clinical Commissioning Group
- Natural England
- Office of Rail and Road
- Transport for London

- 4.33 The Council is also required to 'have regard to' the Local Enterprise Partnership (LEP) <sup>(9)</sup> and Local Nature Partnership (LNP) <sup>(10)</sup> for Kent and Essex when drawing up policies and plans. Both now have an important role in strategic planning and a close working relationship is therefore crucial.
- 4.34 The Council also consults a number of other organisations on planning matters examples include the District's town and parish councils, and bodies such as Thames Water and Sport England. Whilst not a part of the duty to cooperate, ongoing engagement with these bodies is integral to delivering high quality development in the area.

### Memorandum of Understanding

- **4.35** In February 2016, the Council adopted a Memorandum of Understanding (MOU) in respect of the duty to cooperate between the East Kent Regeneration Board members. This includes:
- Ashford Borough Council (ABC)
- Canterbury City Council (CCC)
- Shepway District Council (SDC)
- Thanet District Council (TDC)
- Dover District Council; and
- Kent County Council (KCC)
- 4.36 The MOU does not override the statutory duties and powers of the identified parties. It is not legally binding nor is it intended to cover every detailed aspect of their relationships; rather it is a statement of principles to guide relations between the parties and provide a set of workable ground rules for early discussion and co-operation in addressing strategic and cross-boundary issues.

### The Duty to Cooperate in Practice

- 4.37 The Council has continued to co-operate with other LPAs in Kent and key stakeholders in planning for the District's future. This has involved a number of meetings over the monitoring period which are shown in the table 4.2.
- 4.38 The Richborough Connection National Significant Infrastructure Project (NSIP) continued in this AMR monitoring period with a series of joint meetings between National Grid, DDC,TDC, CCC and KCC. The NSIP was granted consent by the Secretary of State for Business, Energy and Industrial Strategy in August 2017 which falls outside the monitoring period.

<sup>9</sup> The LEP is responsible for bidding for and prioritising infrastructure investment

<sup>10</sup> LNP are partnerships of a broad range of local organisations, businesses and people who aim to help bring about improvements in their local natural environment

Table 4.3 Evidence of the Duty to Cooperate

Date	Meeting	Attendees	Relevant Local Plan Documents	Key Outcomes
05/04/2016	SHMA Inception Meeting with PBA	PBA/DDC/SDC	Local Plan Review	Meeting between DDC/SDC and PBA Consultants to discuss and agree the way forward with the commission and what issues need to be addressed in the SHMA.
27/04/2016	Richborough ConnectionPproject	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
18/05/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
08/06/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
13/06/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
15/06/2016	SHMA Duty to Co-operate Workshop	DDC/CCC/TDC/SDC and Ashford Borough Council	Local Plan Review	Information shared with neighbouring local planning authorities on the initial findings of the SHMA.
20/06/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project

Date	Meeting	Attendees	Relevant Local Plan Documents	Key Outcomes
22/06/2016	Duke of York's Roundabout LEP bid	DDC/KCC	Core Strategy	Meeting to discuss and agree a bid to LEP on improvements that are needed to the Duke of York's Roundabout which is an important component of the Dover Transportation Study.
22/06/2016	SHMA meeting	PBA/DDC/SDC/KCC	Local Plan Review	Meeting to discuss the Objectively Assessed Need figure for affordable housing.
11/07/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
13/07/2016	SHMA meeting	DDC/TDC and GVA	Local Plan Review	Meeting to discuss the initial findings from the SHMA and to discuss the initial recommendations from PBA Consultants that Dover district is best placed in a Shepway and Dover Housing Market Area (HMA) rather than a Thanet, Canterbury and Dover HMA.
25/07/2016	Dover Transport Strategy	DDC/KCC	Local Plan Review	Meeting to update KCC on various development proposals that are happening in the District and implications for KCC highways.
27/07/2016	Richborough Connection Project Examination	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project

Date	Meeting	Attendees	Relevant Local Plan Documents	Key Outcomes
28/07/2016	Richborough Connection Project Examination	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
29/07/2016	Richborough Connection Project Examination	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
11/08/2016	East Kent Duty to Co-operate Meeting	DDC/CCC/TDC/SDC and ABC	Core Strategy, Land Allocations Local Plan and Local Plan Review	Regular Duty to co-operate meeting with neighbouring local planning authorities to discuss and agree a range of cross boundary issues.
18/08/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
08/09/2016	East Kent Growth Framework	DDC/SDC/TDC/CCC and Lichfields	Local Plan Review	Meeting to update East Kent local authorities on the emerging findings from the Lichfield East Kent Growth Plan

Date	Meeting	Attendees	Relevant Local Plan Documents	Key Outcomes
27/09/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
29/09/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
05/10/2016	EDNA - Duty to Co-operate Workshop	DDC/CCC/SDC/TDC/ABC and Lichfields	Local Plan Review	A Duty to co-operate meeting with neighbouring local planning authorities to discuss the initial findings from the EDNA
10/10/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
12/10/2016	Dover Transportation Study Meeting	DDC/KCC/WSP, Highways England and Dover Harbour Board	Local Plan Review	Steering Group meeting with WSP to discuss progress on the Dover Transportation Study and to agree the next steps.
17/10/2016	East Kent Growth Framework	DDC/SDC/TDC/CCC and Lichfields	Local Plan Review	Meeting to update East Kent local authorities on the emerging findings from the Lichfield East Kent Growth Plan

Date	Meeting	Attendees	Relevant Local Plan Documents	Key Outcomes
09/11/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
10/11/2016	Richborough Connection Project	National Grid, DDC/CCC/TDC and KCC	NSIP	Regular meeting with National Grid to discuss the Nationally Significant Infrastructure Project
16/11/2016	East Kent Growth Framework	DDC/SDC/TDC/CCC and Lichfields	Local Plan Review	Meeting to update East Kent local authorities on the merging findings from the Lichfield East Kent Growth Plan
12/12/2016	Kent Water Study	DDC/KCC/SDC/TDC and CCC	Local Plan Review	Meeting to discuss the emerging findings from the Kent Water Study and the implications for the District.
02/02/2017	SFRA	DDC and Environment Agency	Local Plan Review	Meeting with the EA to discuss and agree the draft brief for the Strategic Flood Risk Assessment that will be used to inform the Local Plan Review.
22/02/2017	East Kent Duty to Co-operate Meeting	DDC/CCC/TDC/SDC and ABC	Core Strategy, Land Allocations Local Plan and Local Plan Review	Regular Duty to co-operate meeting with neighbouring local planning authorities to discuss and agree a range of cross boundary issues.

Date	Meeting	Attendees	Relevant Local Plan Documents	Key Outcomes
24/02/2017	Thanet Local Plan Meeting	DDC/TDC	Thanet Local Plan	Meeting between DDC and TDC to discuss the representations submitted to the TDC Local Plan
21/03/2017	Presentation to Health and Wellbeing Board	DDC	Local Plan Review	Presentation to the health and well being board.

### **Update on Neighbouring Local Plans**

### **Ashford Borough Council**

4.39 The Borough Council consulted on a draft version of its Local Plan 2030 between the 15 June and 10 August 2016. Additionally, the Borough Council consulted on the proposed main changes to the Local Plan 2030 in July 2017 and has recently consulted on a number of new housing allocations in order to meet an updated OAN figure.

#### **Canterbury City Council**

- 4.40 The Council submitted a number of representations during the preparation of the City Council's Local Plan. The most notable concern related to the impact of CCC's proposals for additional retail development at Wincheap and the need for CCC to undertake an impact assessment at the Plan-making stage in order to fully assess and understand the potential implications of the proposed additional retail floorspace at Wincheap on the District. The City Council submitted is Local Plan for examination in November 2014. Representations were considered and recognised by the Inspector who was conducting the Local Plan Examination and they were dealt with in a slightly different way to DDC's representation as the impact of additional retail development at Wincheap will now be assessed at the planning applications stage.
- 4.41 The Adoption of the Canterbury Local Plan is now at the High Court as a challenge has been submitted on air quality grounds.

#### **Shepway District Council**

- 4.42 The District Council's Core Strategy was adopted in 2013. SDC is now in the process of producing a follow-on Places and Policies Local Plan and has commenced a partial review of its Core Strategy. SDC consulted on its Places and Policies Local Plan 'Preferred Options' document on 7<sup>th</sup> October 2016 for a six week period that closed on the 18<sup>th</sup> November. The Places and Policies Local Plan identifies sites for future development to meet the requirements in the adopted Core Strategy (2013) and also set out development management policies to guide this development.
- 4.43 SDC has announced its intention to build a garden town at Otterpool Park which could accommodate up to 12,000 new homes. The Government has awarded £155,000 of funding to support the preparation of a masterplan for the site that will guide its development over the coming 30 years.

#### **Thanet District Council**

4.44 The District Council consulted on a number of specific changes to their Local Plan; most notably the allocation of residential development at Manston airport. The Council has raised a a number of cross-boundary issues as part of this public consultation relating to the allocation of housing at Manston airport and that evidence from DDC's SHMA has concluded that Dover District is best placed in a Shepway and Dover Housing Market Area (HMA) rather than a Thanet, Canterbury and Dover HMA, as identified in Thanet District Council's SHMA. It is envisaged that TDC will consult on their Local Plan early in early 2018, providing DDC with the opportunity to submit further representations.

#### **London Plan**

4.45 The Mayor of London has commenced a full review of the London Plan. A major cross-boundary issue is whether London can accommodate sufficient new housing to meet its objective needs. The Council needs to continue to be fully engaged as the preparation of the London Plan advances and to monitor progress in order to assess the implications of this for the preparation of the new District Local Plan.

### 51

# Monitoring of Current Policies

### **5 Monitoring of Current Policies**

5.1 This chapter looks at the use of policies in the Core Strategy (2010) and Land Allocations Local Plan (2015), including where decisions are appealed. It also examines the impact of permitted development rights which circumvent those policies.

### 5.1 Effectiveness of Development Management Policies

- 5.2 One way to assess the effectiveness of policies is to examine how often each policy is referred to as a 'reason for refusal' within decision notices sent to unsuccessful applicants for planning permission. If a policy can confidently be used to refuse a proposal knowing that it may be challenged by an appeal it indicates that it remains useful. However, it should be noted that some policies relate to very specific uses or individual sites these are unlikely to be used often, but that does not in itself mean that they are ineffective.
- 5.3 During the monitoring year 1, 229 planning applications were determined (11). Of these, 87% (or 1073 planning applications) were approved and 13% of applications (or 145 planning applications) were refused.
- 5.4 The planning application refusals over the monitoring period have been assessed to determine which development management policies have been the most influential and relevant in determining planning applications. Table 5.1 illustrates the most frequently used development management policies out of the total of planning refusals:

Table 5.1

Use of Core Strategy Policies in Planning Application Refusals				
Rank	Policy Reference	Description	Percentage of times used in refusals	
1	DM 15	Protection of the Countryside	4.5%	
2	DM 1	Settlement Boundaries	4.2%	
3	DM 16	Landscape Character	2.7%	
4	DM 11	Location of Development and Managing Travel Demand	2.3%	
5	CP 1	Settlement Hierarchy	1%	
6	CP 6	Infrastructure	0.5	
7	CP 7	Green Infrastructure Network	0.3%	

Use of	Core Strategy Po	licies in Planning Application Refus	sals
Rank	Policy Reference	Description	Percentage of times used in refusals
	CO 5	Heritage Coast	0.3%
	CO 8	Protection of Hedgerow	0.3%
10	DM 2	Protection of Employment Land and Buildings	0.2%
	DM 3	Commercial Buildings in the Rural Area	0.2%
	DM 8 Replacement Dwellings in the Countryside		0.2%
	DM 9	Accommodation for Dependent Relatives	0.2%
	DM12	Road Hierarchy and Development	0.2%
	DM18	River Dour	0.2%
	DM 25	Open Space	0.2%
	TR4	A2 & A256 Safeguarding	0.2%
	LA23 (LALP)	Residential Development at Ash	0.2%
	LA25 (LALP)	Land to the north of the junction of Capel Street and Winehouse Lane Capel-le-Ferne	0.2%
	LA43 (LALP)	The Paddock, Townsend Farm Road, St Margarets at Cliffe	0.2%

- 5.5 It can be seen that the most commonly used policies cited in refusals relate to the protection of the countryside and the supply and location of housing. Historically, the Council has not had a five year deliverable supply of housing land. Which has encouraged the submission of planning applications for development in locations contrary to the Council's policies on housing supply.
- 5.6 In conjunction with this the NPPF is also increasingly cited by officers in reasons for refusal, with 85 refusals relying solely on the NPPF, rather than adopted policy. The most frequently cited paragraphs of the NPPF include:

Table 5.2

Use of	Use of the NPPF in Planning Application Refusals				
Rank	Paragraph from NPPF <sup>(1)</sup>	Description	Percentage of times paragraph cited in refusals		
1	17	Core Planning Principles	11.3%		
2	56	Good design is a key aspect of sustainable development, is indivisible from good planning	10.5%		
3	64	Permission should be refused for development of poor design	10%		
4	58	Local and neighbourhood plans should develop robust and comprehensive policies that set out the quality of development	6%		
5	57	It is important to plan positively for the achievement of high quality and inclusive design for all development	5%		

- For information on the NPPF or to read the paragraphs in full please click on the following link; https://www.gov.uk/government/uploads/system/uploads/attachment\_data/file/6077/2116950.pdf
- 5.7 Table 5.2 demonstrates that the NPPF is being frequently used in policy refusals. The most frequently cited paragraph of the NPPF (para 17) relates to the 12 Core Planning Principles and contains overarching principles to be applied to all planning applications. Further to this, paragraphs 56, 57, 58 & 64 in the NPPF all relate to design. As the Core Strategy (2010) does not have any design-led policies, it is to be anticipated that the NPPF is being used prevalently in this way.
- 5.8 Overall, it can be considered that the Council's policies are being used effectively to refuse inappropriate development in the District. It is clear that the most used policies in the Development Plan relate to the protection of the countryside and the supply of housing, which is not surprising considering the previous lack of a 5 year supply of deliverable land. Moving forward the Council has a five year supply of housing (5YHLS) during the monitoring period and the effect of this on planning application refusals will be monitored.
- 5.9 The frequency of use of other Development Plan policies is small, with officers instead relying on the NPPF in decision taking. Here, it can be noted that the NPPF is being extensively used when dealing with design aspects of applications and in the absence of any local design policies this is not surprising. The use of these principles seems to be successful and effective in determining planning applications, however it is recommended that consideration be given to creating some local distinctive design policies as part of the local plan review. Some locally distinctive design policies may well prove to be influential on the Council's success in planning appeals. See table 5.3 for most cited policies in planning appeals.

76

### 5.2 Number of Decisions Allowed on Appeal

- 5.10 The extent to which Inspectors cite the Council's Development Plan policies is another indicator of the effectiveness of policies, as well as the extent to which the Council's decisions are rigorous and can be trusted.
- **5.11** During the 2016/17 monitoring year 43 of the Council's decisions were appealed, which marks a 39% increase from the previous monitoring year.

Table 5.3

	2015/2016		2016/2017	
Decision	No of Decisions	Percentage	No of Decisions	Percentage
Allowed	4	13%	17	40%
Dismissed	27	87%	26	60%
Total	31	100%	43	100%

- 5.12 The Council's success at appeal has declined during the monitoring year and is significantly over the 15% annual target. However, there is no obvious pattern for this. Previous performance prior to 2016/17 met national targets. An independent report has similarly found no obvious reason for this trend. It should be noted that the reasons for allowing appeals during 2016/17 concerned specific detailed matter (e.g. Impact on amenities etc) rather than policies regarding matters of principle.
- 5.13 In 2018 the Government intends to use appeal decisions as an indicator to determine whether an authority will be designated as poor performing. This will take effect from 2018 but will be based on analysis of decisions taken between April 2015 and March 2017. The indicator is no more than 10% of total decisions taken during that period (not appeals lodged) being overturned on Appeal. Table 5.4 illustrates what the Council's performance will look like against this performance indicator:

Table 5.4

Monitoring Year	Total Number of Planning Decisions	Number of Decisions overturned on Appeal	Percentage of Total Decisions
2015/2016	1015	4	0.39%
2016/2017	1226	17	1.38%

5.14 Table 5.5 shows which policies or paragraphs of the NPPF were the most commonly cited in the appeals that were allowed by the Planning Inspector during the monitoring year:

Table 5.5

Rank	Percentage of use	Policy/NPPF	Description
1	78%	Various paragraphs of the NPPF	Relating to core planning principles, design and quality of development, protection of heritage assets and conservation of landscape & scenic beauty.
2	4.5%	DM 15	Protection of the Countryside
3	3%	DM 1	Settlement Boundaries
4	1.5%	DM 13	Parking Provision
	1.5%	DM 24	Retention of Rural Shops and Pubs
	1.5%	GPDO	General Permitted Development (England) Order 2015
	1.5%	Kent Design Guide	Kent Design Guide
	1.5%	LB & CA Act 1990	(Listed Building and Conservation Area) Act 1990
9	0.75%	DM 4	Re-use or Conversion of Rural Buildings
	0.75%	DM 5	Provision of Affordable Housing
	0.75%	DM 12	Road Hierarchy and Development
	0.75%	DM 16	Landscape Character
	0.75%	DM 22	Shopping Frontages
	0.75%	CP 1	Settlement Hierarchy
	0.75%	CO5	Heritage Coast
	0.75%	LA 24	Land to the south of New Dover Road, between Capel Court Caravan Park and Helena Road, Capel-le-Ferne
	0.75%	Kent Downs AONB Management Plan	Kent Downs Area of Outstanding Natural Beauty Management Plan 2014 - 2019

5.15 The paragraphs in the NPPF relating to planning principles and design are the most commonly referred to by Inspectors in determining appeal cases. As the Council does not have adopted policies relating to design in their adopted Development Plan, this perhaps is to be expected.

### 5.3 Changes to Permitted Development Rights

- 5.16 Permitted Development Rights allow people to carry out certain types of work without needing to apply for planning permission. They were originally intended to remove the need for local authorities to deal with small and non-contentious schemes such as fences and porches, but are increasingly being used by the government to allow more significant construction and changes of use. This means that some types of development which would potentially be contrary to existing policies in the Development Plan are now nevertheless able to take place, with only minimal involvement of the Council.
- 5.17 It is important to monitor changes under Permitted Development Rights so it can be seen what effect they are having on policy objectives highlighted in the Council's Development Plan.
- 5.18 During the monitoring year the Council recorded 50 notifications under Permitted Development Rights. Out of the notifications received prior approval was refused for 13 of the notifications as they did not fall within the criteria allowed for permitted development as laid out in the General Permitted Development (England) Order 2015 (GPDO).
- 5.19 In 2013 the government introduced a number of temporary permitted development rights in an attempt to boost the economy. Three of these are particularly relevant to the District and their impacts are explored below.
- 5.20 The first is the temporary right to convert offices to a residential use. Since the right was introduced a loss of 1,232 sq m of B1a floorspace has been granted through prior approvals. Although no loss of office floorspace has been granted this monitoring year as illustrated in table 5.5. This right has significant implications for the District's supply of employment land whilst it was originally set to expire in 2016, the government has now announced that the right will be made permanent. Continued impacts on employment land are therefore a serious concern and ongoing monitoring will be required to assess the long term impacts that this may have on the District's employment aspirations.

Table 5.6

	Office to Residential Permitted Development 2013-2016				
Year	Total Number of Prior Approvals Received	Total Number of Prior Approvals Refused	Loss in B1a Floorspace sq m	Gain in Residential Units	
2013/14	1	0	140	1	
2014/15	2	0	229	3	
2015/16	5	0	863	6	
2016/17	3	3	0	0	
Total	11	3	1232	10	

5.21 The second is the temporary right to convert agricultural buildings to a residential use. There has been a loss of 5,737 sq m of agricultural floorspace which has been permitted through prior approvals as illustrated in table 5.6 It can also be seen that over the last monitoring year 23 residential units have been gained through permitted development rights this is the largest number since the right was introduced. Whilst it was originally set to expire in 2016, the government has now announced that this will be made permanent. Given this, it will be important to continue to monitor the changes occurring in our rural settlements to assess any long term effects.

Table 5.7

	Agricultural to Residential Permitted Development 2013-2016				
Year	Total Number of Prior Approvals Received	Total Number of Prior Approvals Refused	Loss in Agricultural Floorspace Sq m	Residential Units gained	
2013/14	0	0	0	0	
2014/15	9	5	1,168	5	
2015/16	10	8	375	2	
2016/17	23	8	4,194	23	
Total	42	21	5,737	30	

5.22 The third is the temporary right to convert retail to a residential use. Since the right was introduced a loss of 111 sq m retail floorspace has been permitted through prior approvals as illustrated in table 5.7. Over this monitoring year a loss of 74 sq m of retail floorspace was permitted across two sites neither of which were <sup>80</sup>

located in the primary or secondary shopping frontages. Whilst this was originally set to expire in 2016, the government has now announced that it will be made permanent. It can be seen that since this right was introduced only a modest amount of retail space has been lost in the District under Permitted Development rights. However, it is important to continue to monitor any losses to assess the changes to retail floorspace.

Table 5.8

	Retail to Residential Permitted Development 2013-2016				
Year	Total Number of Prior Approvals Received	Total Number of Prior Approvals Refused	Loss in Retail Floorspace Sq m	Gain in Residential Units	
2013/14	0	0	0	0	
2014/15	0	0	0	0	
2015/16	1	0	37	1	
2016/17	3	1	74	2	
Total	4	1	111	3	

- 5.23 Other temporary rights exist under Permitted Development to allow the conversion of storage or distribution floorspace (Use Class B8) to a residential use. The Council received 1 notification under this class of the GPDO but prior approval was refused.
- **5.24** Finally, with effect from the 1/10/2017 there will be a temporary right to convert light industrial floorspace to residential use until 30/09/2020.
- 5.25 The Council will continue to monitor recorded notifications received under Permitted Development Rights. To assess the effect these rights may be having on the Council's policy objectives and aspirations and report findings in the AMR. For further details on Permitted Development Rights can be accessed via the following link: Permitted Development Rights

#### 60

# Retail, Services and Facilities

### 6 Retail, Services and Facilities

6.1 This chapter looks at the health of the District's centres, including the amount of new retail, service and facility floorspace built during the year.

#### 6.1 Health of the District's Centres

- 6.2 The District contains two urban areas (Dover and Deal), a market town (Sandwich) and a great variety of villages. Policy CP1 of the Core Strategy sets out the settlement hierarchy for the District. The settlement hierarchy has been developed to set out the general role of individual settlements. The settlement hierarchy is as follows:
- Dover Secondary Regional Centre
- Deal District Centre
- Sandwich Rural Service Centre
- Aylesham Proposed Rural Service Centre
- Local Centre Ash, Capel-le-Ferne, Eastry, Shepherdswell & Wingham
- Village Alkham, East Langdon, East Studdal, Elvington, Eythorne, Goodnestone, Kingsdown, Great Mongeham, Lydden, Nonington, Preston, Ringwould, Ripple, St Margaret's, Staple, West Hougham, Woodnesborough, Worth
- 6.3 To assess the health of Dover, Deal and Sandwich town centres officers have surveyed the primary and secondary retail frontages in these towns to identify the number of vacant shop units. The findings of this survey have been compared to previous years monitoring and the results are presented in Figure 6.1





Figure 6.1 The number of vacant units in the primary and secondary shopping frontages in Dover, Deal and Sandwich

- 6.4 Figure 6.1 shows that in 2017 Dover has 24 vacant units in the primary and secondary shopping frontages (15.28%), Deal has 3 vacant units (2.83%) and Sandwich has 6 vacant units (7.00%). Over the last monitoring year vacancy rates in Dover have increased slightly by 2 units and are now back to the rate seen in 2012/13. The vacancy rate in Dover is above the national average of 11.1%. Clearly the vacancy rates in Dover is of key concern and needs to be very closely monitored in relation to the opening of the St James's development and how the Local Plan can be used to support the existing town centre.
- 6.5 The vacancy rate has increased slightly in Deal over the monitoring year although this centre still has the lowest overall percentage. Sandwich has seen some losses in the secondary shopping frontages although this has been offset by some gains and therefore the overall number of vacant units remains unchanged from last year.
- 6.6 Core Strategy Policy DM 22 concerns the protection of shopping frontages in Dover, Deal and Sandwich. This policy prescribes that within ground floor premises in the primary retail frontages of Dover and Deal town centres permission will only be given for A1 (Shops), A3 (Restaurants and Cafés) and A4 (Drinking Establishments), and within the ground floor premises in the secondary retail frontages of Dover, Deal and Sandwich town centres permission will only be given for A1 (Shops), A2 (Financial and Professional Services), A3 (Restaurants and Cafés), A4 (Drinking Establishments) and A5 (Hot Food Takeaways).

6.7 Figure 6.2 provides a breakdown of the different use classes in the primary and secondary retail frontages in Dover, Deal and Sandwich.



- 6.8 Over the monitoring year both Dover and Deal have seen a decline in the number of shops (A1 use class) from their shopping frontages with some of these units being converted to other A class uses for example; restaurants and cafes, public houses and wine bars and hot food takeaways. Sandwich and Deal have seen a reduction in the number of financial and professional services from the shopping frontages.
- 6.9 Figure 6.2 illustrates that the main town centre uses in Dover and Deal are A1, A2 and A3 use classes which accords with the Council's adopted policy. Sandwich's main town centre uses are A1 and A2 and 'other uses'. It is evident that other use classes (including B1, C1, C2, C3, D1, D2 and Sui Generis) are present within the town centres. This could be due to changes in retail floorspace through permitted development rights. It is also possible that other uses classes could have pre-existed policy DM 22. Any future changes will continue to be monitored to assess any long term trends which may effect the District's town centres.
- **6.10** To assess the health of the local and village centres in the District, officers have carried out a review of the services and facilities provided in these settlements to document whether any changes have occurred over the monitoring period. This has shown that one village hall has been gained in Westmarsh.
- **6.11** It is important that local and village centres maintain their range of facilities to ensure their vitality and viability and therefore keep their position in the Hierarchy. Officers will however continue to monitor this in the AMR.
- **6.12** The full results of the survey are presented in Appendix 2 Settlement Hierarchy.

### **6.2 Changes in Retail Floorspace**

- 6.13 This section covers changes in the amount of floorspace during the monitoring year in each of the five retail use classes A1 (Shops), A2 (Financial and Professional Services), A3 (Restaurants and Cafés), A4 (Drinking Establishments) and A5 (Hot Food Takeaways).
- 6.14 Over the monitoring period 2,299 sq m (net figure) of retail floorspace (split across A1, A2, A3, A4 & A5 use classes) was permitted in the District. Table 6.1 illustrates changes in retail floorspace across the District over the monitoring period.

Table 6.1

Retail Floo	Retail Floorspace Granted 2016 - 2017						
Location	Floorspace Change (sqm)	A1	A2	A3	A4	A5	Total
Dover	Gross Gains	2960	0	99	150	106	3315
	Gross Losses	-240	-281	-306	-38	0	-865
	Net	2720	-281	-207	112	106	2450
Deal	Gross Gains	468	0	185	0	0	653
	Gross Losses	-622	0	-30	0	0	-652
	Net	-154	0	155	0	0	1
Sandwich	Gross Gains	0	0	245	0	0	245
	Gross Losses	-85	0	0	0	0	-85
	Net	-85	0	245	0	0	160
Rest of	Gross Gains	68	0	92	7	43	210
District	Gross Losses	-60	0	0	-462	0	-522
	Net	8	0	92	-455	43	-312
District	<b>Gross Gains</b>	3496	0	621	157	149	4423
Totals	Gross Losses	-1007	-281	-336	-500	0	-2124
	Net	2489	-281	285	-343	149	2299

- 6.15 Table 6.1 shows that across the District there have been net gains in A1, A3 and A5 and net losses in A2 and A4. This follows the trend reported in last year's AMR. The most notable gain in retail floorspace over the monitoring period can however be attributed to the application for a Lidl foodstore at Whitfield for 2,760 sqm of A1 retail floorspace.
- 6.16 Another important factor when looking at changes in retail floorspace is to consider what is being delivered. Table 6.2 provides a District wide picture of how much retail floorspace has been completed, is under construction or remains not started during our monitoring period.

Table 6.2

Retail Floorspace Delivered 2016 - 2017				
Retail Use Class	Floorspace completed (net sq m)	Floorspace under construction (net sq m)	Floorspace not started (net sq m)	
A1	-372	10233	7573	
A2	-52	-90	172	
A3	329	2249	531	
A4	-752	157	-13	
A5	132	0	132	
Total	-715	12549	8395	

- 6.17 Over the monitoring period a total of 715 sqm of retail floorspace (across all use classes) was lost in the District, this is a net figure taking into account gains and losses. This can largely be attributed to the loss of the Snowdown Working Mens Club, Snowdown and the Hope Inn Public House, St Margarets at Cliffe.
- 6.18 More positively however 12,549 sqm of retail floorspace is currently under construction in the District, with progress being made with the St James's in Dover town centre and the Lidl foodstore in Whitfield. In addition to this, there is 8,395 sqm of retail floorspace not started (with permission), which is around half the amount of retail floorspace to be delivered in unimplemented planning permissions than was reported last year. This is extremely positive and clearly shows that investment is happening in the District.

### 6.3 Changes in Community Floorspace

- 6.19 Over the monitoring period 895 sq m of community floorspace (use class D1) was granted planning permission in the District. This is a cumulative figure from a number of applications at the Battle of Britain Memorial, Capel-le-Ferne, The Old Harbour Station, Dover, Land to the west of Albert Road, Deal and White Cliffs Business Park, Dover.
- 6.20 Table 6.3 shows the gross gains and gross losses in community floorspace broken down by area: Dover (including urban area), Deal (including urban area), Sandwich and the rest of the District.

Table 6.3

Community Floorspace (D1) granted 2016 - 2017					
Area	Gross gain sq m	Gross loss sq m	Net difference sq m		
Dover	580	0	580		
Deal	280	0	280		
Sandwich	0	0	0		
Rest of the District 38 -3 35					
Total	898	-3	895		

6.21 In addition to this, 3,477 sq m of D1 floorspace was completed in the District over the monitoring period (which can be largely attributed to the development of the Maritime Training Academy at Whitfield) a further 35 sq m of floorspace was under construction and 7,588 sq m of community floorspace remains not started with planning permission. The not started figure is made up of applications from the urban expansion of Whitfield (outline application), a doctors surgery at Sandwich (part of a foodstore development), United Reform Church, Dover and Channel House, Dover.

### 6.4 Changes in Leisure Floorspace

- 6.22 Over the monitoring period a total of 447 sqm of leisure floorspace (use class D2) was lost in the District through the grant of planning permission this is a net figure taking into account gross gains and losses.
- 6.23 Table 6.4 shows the amount of leisure floorspace permitted in the District over the monitoring period, broken down by settlement.

Table 6.4

Leisure Floorspace (D2) granted 2016- 2017			
Area	Gross gain sq m	Gross loss sq m	Net difference sq m
Dover	150	-361	-211
Deal	0	-96	-96
Sandwich	55	0	55
Rest of the District	0	-195	-195
Total	205	-652	-447

- 6.24 In addition to this, 108 sq m of leisure floorspace (use class D2) has been completed in the District, over the monitoring period; 6,695 sq m is under construction and 1915 sq m remained not started (with permission). The large amount of leisure floorspace currently under construction can be attributed to the development of a new visitor centre and mining museum at Betteshanger Country Park and the cinema at St James's Dover.
- 6.25 The Council has granted planning permission for a new leisure centre at Whitfield, Dover, Gross Internal Floor Area 5,712 sq m (outside of the monitoring period).

# Housing

### 7 Housing

20 0

Dover


Deal

Sandwich

7.1 This chapter sets out the Council's progress with delivering new houses in the District; looking at affordable housing provision; Gypsy & Traveller accommodation; and future housing land supply.

### 7.1 Delivery of New Homes

- 7.2 The number of net housing completions across the District for this AMR reporting period is 406 dwellings.
- 7.3 There are 4, 196 units which currently have planning permission however have not started and 387 units which have planning permission and are under construction in the District, which should help to maintain the rate of housing completions in the District over the coming years.
- 7.4 Figure 7.1 below shows the number of completions by settlement:



Avlesham

Number of completions

Local

Centres


Villages


Hamlets

Figure 7.1 Completions by Settlement Hierarchy

7.5 This illustrates that the most development over the monitoring period has taken place in Deal (179 units), Dover (87 units), Aylesham (78 units), and 62 units coming forward from the other settlements across the district.

- The Settlement Hierarchy (Policy CP1) states that the major focus for 7.6 development in the District should be in Dover, given its classification as a Secondary Regional Centre. However, during the monitoring period the level of completions in Dover fell significantly below those in Deal. This is primarily due to housing allocations being taken forward at a greater pace than those in Dover as a result of infrastructure and viability constraints. Completions in Sandwich (5 units) were below the other Rural Service Centre (Aylesham) which is not reflective of the adopted Settlement Hierarchy (Policy CP1). The majority of completions in the 'villages' were due to development in Preston (former Salvatori site). Officers will continue to monitor the trends experienced during this monitoring period, and will look at ways of unlocking sites to stimulate house building that is reflective of the Settlement Hierarchy.
- Figure 7.2 demonstrates the source of housing completions over the monitoring period. A total 63% of completions were from the Council's housing allocations, whereas, 37% were from windfall sites. (12) Whilst it is encouraging that the Council's housing allocations are starting to come forward, a significant amount of development in the District over the monitoring period is windfall, and is therefore not plan-led development. This highlights that the adopted Development Plan is not working effectively in delivering housing across the district and that the housing market instead is determining what is built and where.





- 7.8 On a site-by-site basis the most significant completions over the monitoring year were:
- Whitfield Urban Expansion (Phase 1A Abbey Homes) 26 units completed and application built out;
- Whitfield Urban Expansion (Phase 1 & 1a Phillip Jeans) 17 units completed;
- Aylesham Village Expansion 70 units completed;
- Sholden New Fields (land NE Sandwich Rd and NW Sholden New Rd) 17 units completed and application built out; and
- Sholden (land between Deal and Sholden, Church Lane (now known as Timperley Place)) - 112 units completed.
- 7.9 Of the total gross completions during the monitoring period, 276 dwellings and 144 dwellings were delivered on greenfield land and brownfield land respectively; reflecting that the Council's housing allocations are now starting to be delivered, which are primarily based in greenfield locations.
- 7.10 Of the dwellings granted permission, 775 were houses, 196 flats, 28 bungalows and 7 maisonettes. Figure 7.3 shows the breakdown of units granted planning permission over the monitoring period by numbers of bedrooms. The Core Strategy (2010) sets out the preferred housing mix for new developments coming forward in the district. This states that: 15% should be 1 bed homes; 35% should be 2 bed homes; 40% should be 3 bed homes; 10% should be 4 bed homes. Overall, a higher proportion of 3-bed homes were delivered during 2016/17 which is reflective of Policy CP4. Given this, it is clear that the number of 1 bed homes coming forward is significantly below the Council's Policy CP4. Additionally, the number of 2 bed homes coming forward is below Policy CP4. However, the number of 3 bed homes coming forward is close to the policy target and the number of 4 bed homes coming forward is significantly over the Policy mix. This follows a similar trend from the monitoring period 2015-2016.




Figure 7.3 Housing Mix

#### **Delivery of Housing Allocations**

- 7.11 The Council adopted the Land Allocations Local Plan in January 2015. The Land Allocations Local Plan allocates a number of sites across the District for housing development. The Council is now working with developers to bring these sites forward.
- 7.12 Appendix 3 sets out progress with delivering the Council's housing allocations. The Land Allocations Local Plan (2015) allocates sites to deliver approximately 10,273 homes across the District. To date, 4,211 of these homes have been granted planning permission (221 within the monitoring period) and 1,023 of these homes have been completed (248 within the monitoring period). The total housing allocations granted planning permission is lower than what was granted during 2015/16 where two large planning permissions were granted for; Phase 1 Whitfield with over a 1,000 units and Discovery Park, Sandwich with 500 units which bolstered this figure.
- **7.13** Whilst it is evident that the Council's housing allocations are now starting to be brought forward, with 40.5% of the homes allocated on sites in the Land Allocations Local Plan (2015) now granted permission, completions are still behind schedule, with only 9.8% of the homes allocated on sites in the Land Allocations Local Plan (2015) now built.
- 7.14 To date, the majority of housing development on the Council's allocated sites has taken place in Deal/Sholden and Aylesham. Housing completions in Whitfield, Dover (which is where the majority of growth is planned in accordance with Policy CP3 in the adopted Core Strategy (2010)) are significantly behind the milestones in the adopted Core Strategy (2010), with only 91 units delivered on site so far. The application submitted for Phase 2 of the Whitfield Urban Expansion, comprising 1,190 dwellings, however has yet to be determined.

**7.15** Furthermore, the Department needs to be more proactive in encouraging developers that have land allocated for development to come forward and use its pre-application advice service.

#### Self Build Register

- 7.16 The Self-Build and Custom Housebuilding Act 2015 requires relevant authorities, including District Councils, to keep a register of individuals and associations of individuals who are seeking to acquire serviced plots of land for self-build and custom housebuilding. The definition and operation of the register was prescribed by The Self-Build and Custom Housebuilding (Register) Regulations 2016 however superseded by the Self-Build and Custom Housebuilding Regulations 2016 from 1st October 2016. The Act 2015 requires that prescribed authorities must have regard to each register that relates to its area when carrying out its functions in relation to planning, housing, the disposal of any land of the authority and regeneration.
- 7.17 The Council's self build register went online at the start of April 2016. Since the last monitoring period, a further 23 people have registered their interest in acquiring a self build plot in the district. Therefore, to date a total 79 people (77 individuals and 2 associations) have registered their interest.
- 7.18 As it stands, such entries have identified Deal as the most preferred location for a self-build site, followed by Sandwich, St. Margaret's at Cliffe, Whitfield and Walmer. Additionally, 3 to 4 bedroom detached houses are the property type most commonly sought to be built. The majority of those who registered have expressed that they would like to start a self-build project in the next 1 to 2 years.
- 7.19 Given that both the Core Strategy (2010) and Land Allocations Local Plan (2015) predate the need for a self-build register the Council does not currently have a policy on the delivery of self build plots, and therefore to date, no land has been allocated for this purpose. Owing to the fact that self build can be another way of accelerating the rate of house building it will be important consider the demand for self-build and custom housebuilding set out in the register as the preparation of the new District Local Plan advances.

#### **Brownfield Register**

7.20 The Housing and Planning Act 2016 makes provision forLPAs to prepare, maintain and publish a register of brownfield land. The register should identify previously developed sites in the district that the Council has assessed as being suitable for housing. The register should comprise a standard set of information, prescribed by the Government, that will be kept up-to-date, and made publicly available, to help provide certainty for developers and communities and encourage investment in local areas. The registers will then be used to monitor the Government's commitment to the delivery of brownfield sites.

- **7.21** To date, there are 42 sites listed on the brownfield register. The brownfield register will be updated annually and the results will be presented in the AMR.
- **7.22** LPAs are required by Regulation 3 of the Town and Country Planning (Brownfield Land Register) Regulations 2017 to prepare, maintain and publish registers. Specifically, by 31st December 2017 the Council is required to enter brownfield sites in Part 1 of the register and those sites listed in Part 1 that have been granted permission in principle on Part 2.
- 7.23 Further information on this will be collated during the next monitoring period (2017/18) and published in the next AMR.

### 7.2 Five Year Housing Land Supply

- **7.24** The NPPF (2012) requires LPAs to identify and update annually the supply of specific deliverable sites sufficient to provide five years' worth of housing against their housing requirements. The relevant five-year period is currently 2017 to 2022.
- 7.25 The 5 year Housing Land Supply (5Y HLS) calculation is simply a comparison between the anticipated supply of new homes against the number of new homes that are required to be built across the Dover District over a 5 year period. For the purpose of this report, a 5Y HLS is expressed as the number of years' worth of supply.

### 7.2.1 Background

- 7.26 The adopted Core Strategy (2010) sets out a housing target of delivering 10,100 new homes over the plan period from 2006 to 2026. This figure is derived from the revoked Regional Spatial Strategy (RSS) for the South East (2009) and is therefore not NPPF (2012) compliant.
- 7.27 The Council has recently updated the SHMA (2017) for the District, which has identified an Objectively Assessed Need (OAN) for housing for the District of 529 dwellings per annum (dpa).

#### **Adopted Policy**

- 7.28 In determining the Core Strategy housing target the Council considered the following four possible options for housing growth set out in the Council's January 2009 submission document:
- Low growth 6,100 homes based on a continuation of trends and the original provision in the draft Regional Spatial Strategy.
- Medium low growth 8,100 homes which became a level recommended in the Panel Report to Government Medium.
- Medium high growth 10,000 homes which is reflected in the minimum requirement set out in the Government's proposed changes to the RSS.
- High growth 14,000 homes based around the recommendations of the Dover Regeneration Strategy.

- 7.29 The Council supported the 'high growth' option and the independent Inspector's report on the Core Strategy dated 21st January 2010 supported the Council's position confirming its compliance with the Council's policy for economic growth.
- 7.30 The NPPF is clear that local authorities should plan to meet their 'full, objectively assessed needs' (OAN) for market and affordable housing (paragraph 47). The Core Strategy (2010) housing target was selected to encourage and facilitate economic growth in Dover. Therefore, the Core Strategy (2010) started with the policy requirement rather than an OAN figure.
- 7.31 This position is considered as what Hickinbottom J called at p53 of <u>Gallagher Homes Ltd v Solihull MBC [2015] J.P.L. 713.</u> (in the High Court) a "bottom up" approach. In consequence, the Core Strategy figure does not comply with the NPPF's objective to meet OAN and as a result cannot be used as a proxy for a full OAN figure in development management decisions (<u>Hunston Properties Ltd v SoSCLG [2014] J.P.L. 599</u>); nor is it a proper basis for a new development plan process (<u>Gallagher Homes Ltd v Solihull MBC [2015] J.P.L. 713</u>).

### Which Figure is the Proper Starting Point

- 7.32 The Core Strategy (2010) housing requirement is in an adopted Development Plan document which successfully passed through the examination process. Whilst the PPG suggests that this figure should be given "considerable weight", (13) the housing target was adopted prior to the introduction of the NPPF (2012), does not seek the meet the District's OAN as it is a 'policy-on' figure and in turn does not adequately reflect the Council's needs identified in the SHMA (2017) and is out-of-date.
- 7.33 In contrast, the SHMA (2017) represents a NPPF (2012) compliant assessment of the Council's OAN for housing. Therefore, the SHMA (2017) figure is considered to be the only and most appropriate figure for the Council to use when preparing 5Y HLS as part of the development of its new Local Plan.

### Implications of using the OAN for the 5YHLS calculation

- 7.34 The reasoning behind using the OAN figure for calculating the Council's 5Y HLS was detailed in paragraphs 7.25 to 7.33 in the Council's AMR 2015/16.
- **7.35** Using the OAN figure of 529 dpa, as identified in the SHMA (2017) DDC is able to determine whether the District has 5 years' worth of supply for housing. As part of the calculation, the Council has used 2014 as a base date of the project to reflect the assessment period (2014-2037) set out in the SHMA (2017). Therefore, it should be noted that the housing backlog based on historic under delivery between 2006 and 2014 has been removed from the calculation. This approach was endorsed in <u>Zurich Assurance Ltd v Winchester City Council</u> (2014) EWHC 758 (Admin) see Sales J at §94.

7.36 The Council's 5Y HLS calculation is detailed in table 7.1 below.

### 7.2.2 The Calculation

7.37 Table 7.1 sets out an overview of the methodology applied to determine whether the Council has a 5Y HLS.

Table 7.1 5 Year Housing Land Supply

A. Housing target for 5 year period	529 dpa x 5 = 2,645 dwellings		
(2017 - 2022)			
B. Housing delivery since the 2014 base date (housing requirement to date (1,587) minus housing completions to date 1,476 dwellings)	111 (difference between the requirement and completions to date)		
C. Total housing requirement	2,645 + 111 = 2,756 dwellings		
(A + B )			
D. Plus the required buffer	2,756 + 5% = 2893.8 dwellings		
E. Housing land supply	3,345 dwellings		
(inc. extant planning permissions UC + NS, resolution to grant, site allocations (CS,LALP,WNP), future windfall allowance)			
F. 5 year Housing Land Supply	3,345 / 2,893.8 = 1.16		
	1.16 x 5 = 5.80		
Total	5.80 years of supply		

7.38 The above calculation shows that the Council has a housing land supply of **5.80 years**, meaning that for the purposes of decision making the Council can demonstrate a 5Y HLS.

### 7.2.3 Key Components of the 5 Year Housing Land Supply

7.39 For housing sites to comprise part of the 5Y HLS there must be a realistic prospect that housing will be delivered on the site within the next 5 years (2017-2022). In addition to sites with planning permission, sites from other sources, including existing Core Strategy and Housing Land Allocations, and potential future windfall completions can also be considered where this is supported by evidence.

The NPPF explains that:

<u>"Sites with planning permission should be considered deliverable</u> until permission expires, <u>unless there is clear evidence</u> that schemes will not be implemented within five years, for example they will not be viable, there is no longer a demand for the type of units or sites have long term phasing plans."

The Planning Practice Guidance further explains that:

"Deliverable sites for housing could include those that are allocated for housing in the development plan and sites with planning permission (outline or full that have not been implemented) unless there is clear evidence that schemes will not be implemented within 5 years.

However, planning permission or allocation in a development plan is not a prerequisite for a site being deliverable in terms of the 5-year supply. Local planning authorities will need to provide robust, up to date evidence to support the deliverability of sites, ensuring that their judgements on deliverability are clearly and transparently set out. If there are no significant constraints (eg infrastructure) to overcome such as infrastructure sites not allocated within a development plan or without planning permission can be considered capable of being delivered within a 5-year timeframe.

7.40 Given this, LPAs are required to determine whether a site can reasonably be considered as 'deliverable' in the context of the NPPF for 5Y HLS purposes. This is explored in more detail below:

#### A. Housing target for 5 year period (2017-2022)

#### Objectively Assessed Need

- 7.41 As set out in the previous AMR 15/16, the housing requirement identified in the adopted Core Strategy (2010) is not NPPF compliant and is therefore considered out of date for the purposes of calculating the Council's 5Y HLS. In contrast, the SHMA (2017) represents a NPPF compliant assessment in determining the OAN for housing for the Dover District and is in turn considered appropriate to use as a starting point for the above calculation.
- 7.42 The SHMA (2017) identifies an OAN for housing for the district of 529 dpa over a period from 2014 to 2037. Over a 5 year period (2017-2022) this equates to a need for **2,645 new homes.**

#### B. Housing requirement since 2014 base date

- 7.43 To use the OAN figure of 529 dpa as the starting point for the above 5Y HLS calculation and to be consistent with the study period of 2014-2037, the Council has removed historic under delivery between 2006-2014 from the calculation. The historic under delivery of housing against previous requirements has been assessed following advice in the PPG and factored into the calculation for the OAN through the market signals uplift and there is therefore no need to specifically make an allowance for this in the 5Y HLS calculation. Given this, the base date applied to the above calculation was reset to 2014 to align with the Council's updated SHMA (2017).
- 7.44 In light of this, the Council has used a base date of 2014 as the start of the calculation period. Since 2014 a total of **1,476 dwellings** were completed compared to the required 1,587 dwellings between 2014 and 2017.
- 7.45 The breakdown of housing completions by year since 2014 is shown in the table below:

Table 7.2 Housing	Completions	hetween 2014	and 2017	(dwellings)
Table 1.2 Housing	Completions	DELWEEN 2014	anu 2017	(aweilings)

Year	Net Completions	OAN	Supply of Housing
2014/15	344	529	-185
2015/16	726	529	197
2016/17	406	529	-123
Total	1,476	1,587	-111

7.46 Table 7.2 portrays that since 2014 there have been a total 1,476 completions. This equates to a cumulative under delivery of **111 dwellings** against the OAN requirements between 2014 and 2017 of 1,587 dwellings (529 x 3 years).

#### C. Total 5 year housing requirement

7.47 In order to determine the total number of dwellings required for the 5Y HLS period (2017-2022), the Council has added the under delivery for this monitoring period to the OAN requirement for the 5 year period (2017-2022); creating a total 5 year housing requirement of **2,756 dwellings**. Therefore, the Council is required to demonstrate the availability to deliver 2,756 dwellings for over the next 5 years.

#### D. Buffer Requirement

7.48 Paragraph 47 of the NPPF (2012) requires that either a 5% or 20% buffer is added to the 5 year supply to ensure choice and competition in the housing market, depending on whether or not local authorities have a record of persistent under delivery. In this case a 5% buffer has been applied. The Inspector's findings on the Council's adopted Land Allocations Local Plan (2015) considered that whilst there <sup>100</sup>

had been a considerable slowdown in the rate of house building in the District due to the economic downturn, evidence did not indicate a persistent under delivery of housing when economic conditions have been favourable. Furthermore, this view has been reinforced by the level of housing delivery since 2014/15 which, although subject to fluctuations, is close to the requirement on average.

- 7.49 It is considered more relevant to focus on delivery performance since 2014 as the Land and Allocations Local Plan (2015) was in advanced stages of bringing forward the hitherto missing elements of supply and it aligns with the base date of an NPPF compliant SHMA that has identified an appropriate OAN. Consequently, it is not considered that a buffer of 20% is justified during this monitoring period.
- 7.50 Therefore, applying a 5% buffer to the total housing requirement of 2,756 equates to a total **2,893.8 dwellings**.

#### **E. Housing Land Supply**

**7.51** The housing land supply figure is comprised of the following factors: extant planning permissions, extant site allocations set out in the Core Strategy (2010) and Land Allocations Local Plan (2015), resolutions to grant and the Council's windfall allowance. Over the next 5 years (2017-2022) it is anticipated that a total **3,345 dwellings** will come forward. Detail of the Council's housing land supply availability during the 5Y HLS period is set out below:

#### Extant planning permissions

- 7.52 Extant planning permissions include development that has planning permission that is either under construction or has not started. In total, there are 387 dwellings in the District that are under construction during this monitoring period. All extant planning permissions have been considered to be deliverable during the 5 year period and therefore a total **387 dwellings** has been applied to the calculation.
- 7.53 As of this monitoring period (2016/17), there are a total 4,196 dwellings (gross figure) across the District that have planning permission but have yet to be started. However, of this only **1,775 dwellings** are considered to be deliverable during the 5 year period (net of any dwelling losses associated with permissions 45 units) and have therefore been applied to the associated calculation, this is shown and explained in the tables accompanying the AMR.
- 7.54 Therefore, a total **2, 162 dwellings** (387 under construction and 1775 not started) from extant planning permissions has been included in the 5Y HLS calculation set out in Table 7.1. A list of such extant planning permissions can be viewed in Appendix 4.

### Extant site allocations

7.55 The Council has a number of sites that are allocated for residential development in the adopted Core Strategy (2010), Land Allocations Local Plan (2015) and Worth Neighbourhood Plan (2015).

- 7.56 Sites allocated and with planning permission can be considered deliverable unless there is clear evidence to the contrary. In order to establish whether such evidence exists officers have:
- contacted all land owners to determine their intention of bringing sites forward between 2017 and 2022 and if so, what the phasing for the sites will be; and
- identified sites which are currently being considered as part of the pre-application advice process - sites that are currently subject to positive pre-application advice have been considered deliverable within the 5 year period.
- 7.57 Allocated sites that have been granted planning permission have been included as extant planning permissions to avoid the risk of double counting.
- **7.58** The total housing supply from the Council's allocated sites is 10,273 dwellings. Of these, it is considered that a total 958 dwellings will be delivered on such allocated sites during the 5 year period. Therefore, a total of 958 **dwellings** from extant site allocations has been applied to the 5Y HLS calculation.

#### Resolutions to grant

**7.59** An application for residential development proposing the erection of 90 dwellings on the allocated land at Chequer Lane, Ash was submitted during this monitoring period and has a resolution to grant permission subject to a S106 agreement that is not yet concluded.

#### Windfall allowance

7.60 Paragraph 48 of the NPPF allows windfall sites to be taken into account in the 5Y HLS, having regard to the Strategic Land Housing Availability Assessment, historic windfall delivery rates and expected future trends. Windfalls sites are identified in the NPPF (2012) as:

"Sites which have not been specifically identified as available in the Local Plan process. They normally comprise previously developed sites that have unexpectedly become available".

**7.61** In determining the Council's windfall allowance, windfall sites have been identified as those which have not been considered as part of the preparation of the adopted Development Plan. Table 7.3 sets out an overview of the Council's windfall allowance calculation:

Table 7.3: Windfall Allowance Calculation

a. Average windfall completions on previously developed sites	140 dpa
b. Average windfall completions on garden land	20 dpa

c. Windfall allowance	120 dpa	
(a-b)		
d. SHLAA sites consideration	50% deduction	
d. StieAA sites consideration	30 % deduction	
	60 dpa	
e. Application of windfall allowance to 5Y HLS	Apply windfall allowance to years 3,4 and 5 of the 5 year supply period	
(d x amount of years in 5 year period)	180 dwellings	

- 7.62 The table above shows that an average of 140 dpa have come forward separate to what is allocated in the adopted Development Plan. Additionally, an average of 20 windfall units on sites comprising garden land are expected to come forward each year. Paragraph 48 of the NPPF (2012) requires the removal of garden land from any windfall allowance calculation. Therefore, in compliance with the requirements of the NPPF, the Council has taken a cautious approach and deducted the average garden land windfall completions from the overall average windfall completions; resulting in an average of **120 dpa windfall completions**.
- 7.63 In order to avoid the risk of double counting, it is essential that consideration is given to the influence of SHLAA sites during the 5 year period. SHLAA sites are identified for potential inclusion as allocations in the Development Plan. As the Council undertook a Housing and Economic Land Availability Assessment between June and August 2017, it is likely that larger windfall sites identified during 2016/17 will be considered as part of the Local Plan review and in turn may not be regarded as windfall development in the immediate 5 year period. Therefore, as a cautious approach, the Council has taken this into account and applied 50% of the 120 dpa figure to give a total average of 60 dpa windfall completions.
- **7.64** Since 2012/13, the number of windfall completions exceeds the average annual windfall completions rate for a total of 2 years. This demonstrates a strong case to apply the windfall allowance to the last 3 years of the 5Y HLS period (i.e. 2019/20, 2020/21 and 2021/22).
- 7.65 Therefore, the windfall allowance applied to the 5Y HLS calculation is a total of **180 dwellings** (60 x 3 years).

#### F. 5 year housing land supply

7.66 By applying the above components set out from paragraphs 7.39 to 7.65 to the 5Y HLS calculation, the Council has **5.80 years** supply of land for housing and can therefore demonstrate a 5Y HLS.

### 7.3 Housing Trajectory

- 7.67 The NPPF sets out the requirement for LPAs to provide information on housing policy and performance, including illustrating the expected rate of housing delivery through a housing trajectory for the plan period and setting out a housing implementation strategy for the full range of housing, describing how they they will maintain a 5 year supply of housing land to meet their housing target. The housing trajectory assists the monitoring of both past and anticipated completions across the Plan period and can help indicate at an early stage whether any steps need to be taken to ensure that planned housing requirements are met. It is however, important to note that a housing trajectory is not intended to produce 'perfect forecasts' of the future, nor necessarily absolute answers regarding the past and present delivery. Rather, it illustrates the potential delivery rate of new dwellings, sets out the anticipated supply and the number of dwellings that are predicated to be built over the plan period, apportions previous under delivery over the first 5 years, and sets out what the range of sites in the trajectory is considered capable of delivering over the next 5 years.
- 7.68 Figure 7.4 sets out the housing trajectory for the District over the period from 2014/15 to 2037/38. This shows the current housing supply position in relation to the OAN for housing identified in the SHMA (2017, the solid orange line across the centre of the chart). Different types of sites run in 'waves' through the trajectory period, illustrating the future supply of land for housing in the District, based on sites with extant planning permission, sites allocated in the Core Strategy (2010) and Land Allocations Local Plan (2015) and windfall development. The housing trajectory also highlights the expected cumulative supply of housing across the trajectory period, taking into account under delivery and over delivery against the OAN.
- 7.69 The housing trajectory illustrates that from 2017/18 to 2021/22 the Council has a sufficient supply of housing land to meet the OAN, and if windfall development continues at the current rate then this will ensure the District has a sufficient supply of housing land until 2024/25. However after this date, the Council's supply of housing land falls below the level required to deliver the OAN, meaning more housing sites will need to be found in the future to continue to support housing delivery in the District.




Figure 7.4 Housing Trajectory 2016/17

### 7.4 Affordable Housing

- 7.70 The provision of affordable housing in the district is a key response to pressures of housing affordability. Affordable housing can either be provided by the Council, other affordable housing providers, or registered social landlords operating locally. New affordable housing can either be the result of the direct construction of new properties or the purchase of open market properties for use as affordable housing.
- 7.71 The Council's policy on affordable housing, DM 5 of the Core Strategy (2010), requires residential development of 15 or more dwellings to provide 30% of the total homes as affordable homes and for developments of between 5 and 14 dwellings to make a contribution towards the provision of affordable housing in the District. (14)
- 7.72 Over the monitoring period 91 affordable houses were granted permission in the District on five sites. However the Council only achieved its target of delivering 30% affordable housing on two sites: The Old Sorting Office, Charlton Green, Dover and land adjacent to allotments, Folkestone Rd, Dover.

<sup>14</sup> A recent Court of Appeal judgement upheld the government decision to exempt developments of 10 houses or fewer from section 106 of the Town and Country Planning Act 1990, which enables local planning authorities to seek contributions from developers to provide affordable housing and mitigate the impact of developments.

- 7.73 Further to this, during the monitoring period, 78 affordable homes were completed in the district on two sites: Aylesham and Timperly Place Sholden (Deal). This equates to 19% of all housing completions.
- 7.74 Whilst progress is being made with the delivery of affordable housing within the district, the percentage delivered continues to fall short of the policy requirement in the Core Strategy (2010) as the average level of affordable housing completions in the district since 2006 is 23.2% (see Table 7.4 below). Whilst this is below the policy requirement, it should be noted that the policy sets out a standard for affordable housing delivery, taking into account economic viability, which may in practise mean that provision is lower, particularly as there are some very low value areas in the district.

Table 7.4 Affordable Housing Completions 2006 - 2016

Year	Total Housing Completions	Total Affordable Homes	Percentage
2006/07	327	64	19.6
2007/08	342	15	4.3
2008/09	269	54	20
2009/10	262	112	42.7
2010/11	201	18	8.9
2011/12	227	67	29.5
2012/13	228	96	42
2013/14	228	28	12.3
2014/15	344	110	31.9
2015/16	726	185	25.4
2016/17	406	78	19.2
Total	3,566	827	23.2 (Av since 2006)

7.75 Furthermore, the SHMA (2017) advised that in order to meet housing need, 167 affordable homes should be delivered in the district per annum, and that the vast majority of these should be for rent with more than half at social rent levels. Table 7.4 clearly shows that the level of affordable housing delivery in the district is below this level (with the exception of 2015/16) and indicates the need to review the Council's strategy to affordable housing provision as part of the preparation of the new District Local Plan.

106

7.76 In addition to delivering affordable housing on the ground, the Council has also collected £197,010 in S106 Contributions<sup>(15)</sup> towards the provision of affordable housing in the district. These monetary contributions were collected from four developments in the district.

#### **Rural Exception Affordable Housing**

7.77 Policy DM 6 of the Core Strategy (2010) sets out the Council's policy on delivering rural exception affordable housing. There have been no rural affordable housing schemes within this AMR reporting period. The last rural exception site was developed in Goodnestone in 2012.

### 7.5 Gypsy and Traveller Pitch Provision

- 7.78 Policy DM7 of the Dover Core Strategy (2010) states that the Council will allocate sites to meet the accommodation needs of gypsies, travellers and travelling show people through the production of the LALP (2015).
- 7.79 A Gypsy and Traveller Accommodation Assessment was completed in 2014 which identified a need to deliver 17 pitches over the Plan period (2006 2026). This figure was translated into the Land Allocations Local Plan (2015) which states that the Council will produce a Gypsy, Traveller and Travelling Showpeople LALP to deliver these pitches (Policy LA1).
- 7.80 However, since the adoption of the LALP (2015), 7 Gypsy and Traveller pitches have been permitted, either through the grant of planning permission or at appeal, meaning that there is now a need to plan for 10 pitches until 2026.
- 7.81 Since the LALP (2015) was adopted however, the Government has issued revised Guidance on planning for Gypsies and Travellers (August 2015) which amended the definition of Gypsies and Travellers for planning purposes, and in 2016, the Housing and Planning Act revoked the need for Local Authorities to carry out Gypsy and Traveller Accommodation Assessments (see Section 124). This created a level of uncertainty around planning for Gypsies and Travellers, and as a result the planned work on a Local Plan for Gypsy and Traveller accommodation was put on hold.
- 7.82 The Council has now commissioned Arc4 to update the Gypsy and Traveller Accommodation Needs Assessment which is currently underway. The findings from this updated Study will be taken forward as part of the Council's new District Local Plan.

Planning obligations under Section 106 of the Town & Country Planning Act 1990 (as amended) commonly known as S106 agreements are a mechanism which make a development proposal acceptable in planning terms that would not otherwise be acceptable. They are focused on site specific mitigation of the impact of development. S106 agreements are often referred to as 'developer contributions' - Planning Advisory Service

# The Economy

## 8 The Economy

8.1 Dover represents a reasonably small but productive economy in the wider East Kent area, with the Dover economy seeing strong business growth but a decline in employment over recent periods (in part due to the consolidation of Pfizer).



Figure 8.1 Market Share of the East Kent Economy by Local Authority

## 8.1 Changes in Employment Floorspace

- 8.2 Floorspace within Dover is dominated by industrial uses, with the total B class employment floorspace in Dover amounting to approximately 603,000 sq m in 2012. Compared to other East Kent local authorities, Dover has the second largest stock of industrial space and the second smallest stock of offices.
- 8.3 Office floorspace has remained relatively constant in Dover, while industrial floorspace grew significantly in 2010/11. The largest clusters of B class floorspace are located in and around Dover Town and Sandwich, with key employment sites located across the District supporting a large share of existing space e.g White Cliffs Business Park, Discovery Park Enterprise Zone, Sandwich Industrial Estate, Coombe Valley Rd, Southwall Industrial Estate. Table 8.1 illustrates the share of total floorspace for offices and industrial uses across the District.

Table 8.1 Share of Total Floorspace for Offices and Industrial Uses Across the District

	Sh	are of Total Floorsp	ace
	Office	Industrial	Total
Dover Town	46%	32%	37%
Sandwich	44%	19%	28%

	Sh	are of Total Floorsp	ace
Aylesham	3%	16%	11%
Deal	5%	7%	6%
Rest of District	2%	26%	18%

**8.4** Completions have principally focused on industrial uses, with development slowing over recent years. This is illustrated by Figure 8.2

12,000 17,600sq.m Offices (B1a/B1b) Gross Floorspace Completions (sq.m) 10,000 Inc. Seafield Industrial (B1c/B2/B8) Industrial Unit in Aylesham 8,000 6,000 4,900sq.m 4,000 1,200sq.m 2,000 0 2007/08 2008/09 2009/10 2010/11 2011/12 2012/13

Figure 8.2 Employment Floorspace Completed in the District 2006 - 2016

8.5 While the loss of employment space has been more evenly split across office and industrial uses (see Figure 8.3)




Figure 8.3 Losses in Employment Floorspace in the District 2006 - 2016

8.6 This has resulted in positive net completions of industrial space and negative net completions of office space, as illustrated by Figure 8.4.




Figure 8.4 Completions of Office and Industrial Floorspace in the District

- 8.7 Over the monitoring period a total of 4,650 sqm of employment floorspace (B1, B2 and B8 uses) was permitted in the District (see Table 8.2). This is a net overall figure taking into account gains and losses.
- 8.8 The main gains in employment floorspace can be seen in B1c, and B2 and can be largely attributed to two applications at Discovery Park Sandwich.

8.9 The main losses in employment floorspace can be seen in B1a office space, with some of the largest losses in this category coming from Protea House, Market Square and Castle Street in Dover.

Table 8.2 Employment Floorspace Permitted in the District 16/17

Employment Use	Total Gain in Floorspace (Gross sqm)	Total Loss in Floorspace (Gross sqm)	Net Overall Figure (sqm)
B1a	1,395	2,282	-887
B1b	0	0	0
B1c	2,690	0	2,690
Mixed B1	0	580	-580
B2	4,392	1,142	3,250
B8	0	260	-260
B1 - B8	437	0	437
Total	8914	4264	4,650

8.10 Over the monitoring period a total of 1,693 sq m of employment floorspace (in B1a, B1b, B8 & B1-B8) was built and 885 sq m of employment floorspace (in B1c, Mixed B1 & B2 uses) was lost, either through demolitions or change of use, meaning that net completions of employment land were 808 sq m. A further 17,529 sq m of B1a, B1c and B2 floorspace was under construction however, with 90,883 sq m of employment floorspace still not started over the monitoring period. This is illustrated in Table 8.3.

Table 8.3 Employment Floorspace Completed, Under Construction and Not Started in the District 16/17


Employment Use	Completed Floorspace (net sq m)	Floorspace Under Construction (net sq m)	Floorspace Not Started (net sq m)
B1a	114	1036	24,945
B1b	64	0	0
B1c	-98	314	32,991
Mixed B1	-580	0	0
B2	-207	16,221	4,366
B8	717	-42	10,276

Employment Use	Completed Floorspace (net sq m)		Floorspace Not Started (net sq m)
B1 - B8	798	0	18,305
Total	808	17,529	90,883

- 8.11 In summary, its clear to see that long term trends in employment floorspace have been replicated in this monitoring period with gains in industrial uses (B1c and B2) and losses in B1a office space.
- 8.12 Furthermore, whilst there have been moderate gains in employment floorspace completed in the District over the monitoring period, there is still a large amount of employment floorspace in the District that is yet to be delivered.
- 8.13 It is also evident that the main focus for employment development in the District continues to be Discovery Park, with some B2 development also underway at Tilmanstone Colliery.
- 8.14 Whilst the high level of investment at Discovery Park is extremely positive for the District, as its a key employment location, the low level of investment at other employment areas in the District is a concern and illustrates that more needs to be done to promote other employment areas such as White Cliffs Business Park.
- 8.15 The Council has recently undertaken a review of its existing economic strategy as part of the Economic Development Needs Assessment (2017) and the findings of this will be taken forward as part of the Local Plan review. In addition to this, the Council also needs to work with developers to progress the development of sites that are currently 'not started' to ensure that they are brought forward in a timely manner.


#### 8.2 Jobs

8.16 Dover has recorded a loss of employment (jobs) during the first ten years of the Core Strategy plan period from 2006 to 2016. Over this period the total workforce jobs lost was 4,700 (net figure). The District saw employment losses in a number of sectors, with only education; hospitality and recreation; finance and insurance; and information and communication showing an increase in employment.



8.17 Recent growth has however been proportionately greater in a number of sectors in Dover compared with East Kent and Kent as a whole, as shown by Figure 8.6

Figure 8.6 Change in Workforce Jobs Across the Employment Sectors for Dover, East Kent and Kent



8.18 In absolute terms the majority of sectors in Dover have seen employment losses over the first decade of the Core Strategy plan period, with the strong employment losses recorded in manufacturing largely driven by pharmaceuticals, caused by the contraction of Pfizer in 2010.




Figure 8.7 Change in Workforce Jobs Across Employment Sectors in Dover

Total Change in Number of Workforce Jobs (2006 - 2016)

- 8.19 Dover's workforce mostly live in the District (71%), Thanet (8%), Shepway (8%) and Canterbury (7%), and Dover's residents mostly work within the District (67%), Canterbury (10%), Shepway (9%), Thanet (4%) and Ashford (3%). Overall, the District has a net commuting outflow of 6,900 workers with a self-containment rate of 67%. However, there has been an increase in out-commuters and decline in in-commuters since 2001.
- 8.20 The District has a moderate performing labour market which has supported a relatively productive workplace. Recent workplace earnings within Dover are achieving a greater level than other East Kent Local Authorities, however the District has moderate residence earnings compared to other East Kent local authorities. There has also been a relatively low growth in earnings in the District over the last decade, with residence earnings achieving a greater relative gain.

## **Changes in Jobs Over the Monitoring Period**

8.21 Table 8.4 shows ONS figures for the total jobs <sup>(16)</sup>in the District and the jobs density for the District, and compares these to the figures for Kent and Great Britain as a whole. ONS figures take around 2 years to be published – the most up to date figures are therefore from 2015.

Table 8.4

Area	Jobs Figure	2012	2013	2014	2015
Dover	Jobs Total	37,000	42,000	41,000	40,000
	Jobs Density	0.55	0.62	0.61	0.59
Kent	Jobs Total	661,000	685,000	709,000	727,000

The total number of jobs is a workplace-based measure and comprises employee jobs, self-employed, government supported trainees and HM Forces

Area	Jobs Figure	2012	2013	2014	2015
	Jobs Density	0.72	0.74	0.76	0.78
Croot	Job Total	31,957,000	31,654,000	32,621,000	34,059,000
Great Britain	Jobs Density	0.78	0.80	0.82	0.83

- 8.22 In 2013 the economy was emerging from recession and this is evident in the significant increase in jobs in the District from 37,000 to 42,000. However since 2014, the District has experienced a decrease in jobs from 41,000 to 40,000. The Business Register and Employment Survey (BRES) (17) shows that the District has lost 700 employee jobs over the monitoring period. Looking at these figures more closely there are gains and losses across a number of sectors. However, the sector with the largest loss over the monitoring period is 'human health and social work activities' with a loss of 800 jobs, in fact the same sector shows an 800 increase in the previous period 2014/15. KCC who have published this bulletin have highlighted this figure as potentially unreliable and if the number of jobs in the District is considered without this sector being included there is no overall change in the monitoring year. However, it will be necessary to monitor this going forward particularly given there have been gains in jobs on both the county and national level.
- 8.23 Jobs density is the ratio of total jobs to the working age population aged 16-64. In 2015 jobs density in the District declined slightly to 0.59 (per one of the population), however increased in both Kent (to 0.78) and nationally (to 0.83). As a result there is now a growing divide between the District and the county as a whole. An under-supply of jobs in the District will also lead to potential increases in out-commuting and higher numbers of people claiming job seekers allowance if they cannot find work.

### **Unemployment Levels**

- 8.24 The level of unemployment in an area is one of the most closely followed indicators of economic health and can be measured in several ways. The most literal measure of unemployment comes from the ONS annual population survey (via NOMIS). This indicates the percentage of people of working age who are not currently in employment, except where they are economically inactive (for example because they look after family at home or have retired). By this measure the current (2016/17) unemployment rate for the District is 5.0%. This is a significant improvement on past figures and represents a downward trend in unemployment. The District still has a slightly higher unemployment rate than the national figure of 4.7% however.
- **8.25** Rates of Job Seekers Allowance (JSA) claimants are another means of monitoring unemployment. JSA is intended to address the financial hardship of unemployment, but not every unemployed person is eligible to claim for example, the income of an unemployed person's spouse may put their household income

above the main threshold. Many unemployed people also choose not to claim JSA for a variety of reasons. JSA claimant rates are therefore a better indicator of the actual deprivation caused by unemployment. As JSA figures indicate the actual number of claimants, they are also more reliable than overall unemployment figures which are estimates based on a sample.

8.26 In June 2017 the rate of JSA claimants within the District of Dover was 2.3%, showing that the number of JSA claimants has increased slightly since last year and remains higher than the national average of 1.9%.

#### **Skills**

8.27 Since 2006, there has been an uplift in qualification attainment for the local population supporting the Dover economy.

Table 8.5 (Nomis data)

	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015
NVQ4 and	9,800	15,600	14,600	14,900	19,900	18,900	12,500	22,000	19,400	18,600
NVQ3 and above	23,600	29,700	31,200	28,500	30,900	33,400	31,400	37,100	32,600	31,300
NVQ2 and above	42,500	45,300	45,100	42,100	43,100	50,100	46,800	50,400	45,800	46,600
NVQ1 and above	51,100	52,300	53,300	53,400	53,700	58,600	57,500	58,300	57,000	57,900
Other or no qualification	12,200	12,000	14,200	15,200	13,200	7,800	10,900	7,200	11,000	9,100

8.28 Table 8.5 shows that the number of people in the District with NVQ level 1 to 4 has increased dramatically over the Plan period, whilst the number of people with no or other qualifications has practically halved.

## 9 Environment and Sustainability

9.1 This chapter looks at the District's environment and the sustainability of new development; across a range of topics including the historic environment, open space, energy, and transport.

### 9.1 Environment

9.2 Dover District has a very diverse landscape comprising coastline; broadleaved woodland; grasslands; areas of outstanding natural beauty; agriculture; parks and gardens; sites of special scientific interest; and open countryside.

## **Kent Downs Area of Outstanding Natural Beauty**

- 9.3 Dover District has an area of 31,892 hectares, with a coastline of 32 kilometres. Approximately 6,900 hectares (21%) of the District is designated as part of the Kent Downs Area of Outstanding Natural Beauty, with 876 hectares (3%) of this designated as heritage coast.
- 9.4 The Kent Downs AONB Management Plan was first published in April 2004, and revised in 2009 and 2014. The management plan sets in place clear aims, policies and actions for the conservation, management and enhancement of the AONB for a five year period in addition to setting a longer term vision. The Kent Downs AONB Management Plan has been formally adopted by each of the Local Authorities who have the AONB in their area (including Dover District Council).
- 9.5 Up on the Downs has created, restored and improved 175ha of chalk grassland habitat for the benefit of wildlife and people within and adjacent to the AONB, including the creation of two new nature reserves. In addition, it has improved the condition of 16 20<sup>th</sup> century military structures and four Scheduled Monuments within the AONB and vastly increased the understanding of the South Foreland Lighthouse, helping to ensure its long term conservation. Lastly, the creation of an Access for All path at Langdon Cliffs has greatly improved the visitor experience at the White Cliffs of Dover, whilst significantly reducing the impact of visitor pressure at this iconic site.
- 9.6 Over the monitoring period 44 dwellings were granted planning permission in the AONB, amounting to 25,594 sq m (total site area). Of these 44 dwellings, 29 came from one application off Folkestone Road, Dover towards Maxton.

## **Protection of the Countryside**

**9.7** The Core Strategy recognises the highly diverse nature of the District's landscape. Policy DM15 of the Core Strategy concerns the protection of the Countryside and Policy DM1 of the Core Strategy concerns development outside settlement boundaries.

Over the monitoring period 438 dwellings were granted planning permission outside settlement confines. Of these, 69 dwellings were adjacent to settlement confines and 369 were completely outside. The majority of these homes were granted at Aylesham (277), Bisley Nursery in Worth (32), Woodnesborough Lane, Eastry (12), Albert Road (15 out of 142).

## **Green Infrastructure Delivery**

- Provision of open space is guided by the standards adopted as part of the Land Allocations Document (DM 27) and associated strategies, including the Review of Play Area Provision 2012-26. The Council's review of Play Area Provision 2012 - 2026 identified the St Radigunds ward as being deficient in play provision. The Council met its objective during this monitoring year when it constructed the St Radigunds play area project at the Triangles Community Centre. This project was informed by consultation to identify the local communities' preferences.
- Other play area providers have also been actively increasing capacity of their facilities. For example, within the monitoring period Wingham Parish Council is developing a project to replace the local play area and to provide a Multi-Use Games Area (MUGA).
- The Review of Play Area Provision 2012-26 still provides useful guidance, but the majority of projects listed have now been delivered. Furthermore, new play areas have been provided and others have been removed, for example at Freemen's Way Deal. It would now be worthwhile considering an update to the strategy.
- The adopted Parks and Amenity Open Spaces Strategy placed a very high priority on raising standards and capacity at the District's most popular park, Kearsney Abbey. The Heritage Lottery and Big Lottery funding awarded a £3 million grant to restore Kearsney Abbey and Russell Gardens. The grant was awarded in July 2016 and DDC are in the delivery stage of the phased project which runs until June 2020.
- 9.13 The plans include:
- Restoring Thomas Mawson's designed listed structures for Kearsney Court within Russell Garden
- Celebrating the parks' unique heritage including mills, ecology, people and landscapes through new activities and interpretation
- Creating a multi-use extension to the Grade II listed Billards room and Cafe in Kearsney Abbey to facilitate new education, training and volunteering programmes
- Raising standards across the parks to apply for Green Flag status
- The main gap in provision of parks and amenity open spaces identified in the strategy was a lack of strategic level provision in Sandwich. A report to Cabinet in March 2016, defined the 'Sandwich Town Walls' site, consisting of open spaces around the town that are linked by the historic walls. This has been adopted as a strategic site in addition to the six sites defined in the Parks and Amenity Open 120

Spaces strategy and the Sandwich Parks Project. The Council will start to write a bid document for an HLF type funded project in early 2018. This will be called the Sandwich Parks Project and it is hoped that this will join all of the pieces together in one bid consideration is being given to adding Gazen Salts to this project.

## 9.2 Sustainability

## **Energy**

- 9.15 Indicator 11 of the Core Strategy is concerned with making more efficient use of natural resources. In 2006 average domestic water consumption was 160 litres per person per day, with latest figures showing that this has fallen to 150 litres per person per day<sup>(18)</sup>. In 2006 average domestic electricity consumption was 4,164 kWh per person, with latest figures showing that this has decreased to 3,844 kWh per person, with latest figures showing that this has decreased to 16,615 kWh per person, with latest figures showing that this has decreased to 12,234 kWh per person<sup>(20)</sup>. This shows that overall there has been a decline in the use of natural resources in the District over the first half of the plan period, which is a positive trend.
- **9.16** Whilst the number of renewable energy schemes being developed in the District is growing, there haven't been any applications granted permission over this monitoring period.

## **Sustainable Transport**

- 9.17 Indicator 8 of the Core Strategy is concerned with improving the ease of travel and encouraging walking, cycling and use of public transport.
- 9.18 The Core Strategy aims to increase sustainable commuting by 2% from the base figure across all modes. The Census records the percentage of the population in an area that commute by rail, bus, cycle and foot. In 2001, 2% of people went by rail, 4% by bus, 3% by bike and 12% on foot; in 2011, 2.3% of people went by rail, 2.3% by bus, 1.3% by bike and 7.7% on foot.
- 9.19 This shows that trends in the use of sustainable transport have worsened rather than improved, meaning that more measures need to be put in place to promote sustainable transport use in the District to meet the 2026 Core Strategy target.
- 9.20 Core Strategy Indicator 8 also identifies the High Speed 1 train service as being a key mechanism for measuring whether the ease of travel and use of public transport has improved in the District. High Speed 1 came into operation from Dover Priory Railway Station in December 2009, making Dover just over an hour away from London in commuting times. The service has since been extended to Deal, Sandwich and Martin Mill.

<sup>18</sup> Kent State of the Environment Report 2015

<sup>19</sup> DECC, Business Intelligence KCC 2013

<sup>20</sup> DECC, Business Intelligence KCC 2013

- 9.21 In 2012/13 904,970 passengers entered and exited Dover Priory, this rose to 943,970 passengers in 2013/14 and 961,174 passengers in 2014/15 (Office of Rail and Road, Estimates of Station Usage). However for 2015/16 the number of passengers entering and existing Dover Priory fell to 883,394 (Office of Rail and Road, Estimates of Station Usage).
- 9.22 This fall in passenger numbers may however be explained by the fact that the line between Dover Priory and Folkestone West was closed for a number of months in 2016 whilst emergency repair works were carried out on the sea wall adjacent to the railway line.
- 9.23 Whilst the initial upward trend in the use of Dover Priory Station and High Speed 1 for commuting is encouraging, the fall in passenger numbers in 2015/16 is concerning and will need to be monitored, especially as passenger volumes at Dover Priory are still relatively modest compared to other stops on the High Speed line, and efforts need to be made to capitalise more on the High Speed line in the District through the construction of car parking facility adjacent to the railway station.

#### **Sustainable Construction**

9.24 Policy CP5 sets out the Council's requirements for sustainable construction standards. Whilst the Council is continuing to implement the part of the policy relating to BREEAM (the Building Research Establishment Environmental Assessment Methodology), it is no longer seeking to ensure that new development meets the Code for Sustainable homes requirements under the policy. This is due to the fact that the Government has withdrawn the Code for Sustainable Homes and replaced it with optional additional requirements under the Building Regulations which can only be implemented through a new policy in a local plan. Any such policy must be underpinned by a local justification for implementing the additional requirements and an economic viability assessment to demonstrate that they would not place undue financial burdens on development. The Council will consider this issue as part of the preparation of the new Local Plan and in the meantime will not implement the parts of policy CP5 that relate to residential development. The remainder of the policy relates to non-residential development, and is not affected by the Government's changes and continues to be implemented by the Council.

## 9.3 Historic Environment

9.25 This section sets out progress with the implementation of the Heritage Strategy and monitors changes in the historic environment in the District.

## Changes to the National Heritage List for England

**9.26** Over the monitoring period there has been one new heritage asset in the District added to the list with the designation of a pair of acoustic mirrors in the Fan Bay as a scheduled monument. There has also been an upgrade of the Maison Dieu in Dover from grade II\* listed building to grade I.

9.27 There have been no new entries on the Heritage England risk register during the monitoring period.

## **Heritage Assets**

9.28 A variety of conservation projects are currently being undertaken across the District to safeguard the future of important heritage assets for all to enjoy. An example of this work is given below.

## Case Study: Western Heights Heritage and Landscape Appraisal

• Kent County Council provided a significant contribution of £12,000 towards the development of an appraisal bringing together the built heritage and landscape of the Dover Western Heights. The aim of the appraisal is to inform recommendations for future vegetation management of the Western Heights based on an understanding of the areas heritage, landscape and amenity value. The appraisal advances actions in the Dover Western Heights Masterplan and it is intended that it will be followed by more detailed surveys to further our understanding of the ecology of the Western Heights and how the landscape and built heritage is used by particular species.

#### **Conservation Area Appraisals**

- 9.29 The Heritage Strategy identified the need for a programme of Conservation Area appraisals in order to facilitate understanding of the special interest of the Conservation Areas, and to enable management and monitoring of the areas through the development of guidance and advice, and the widening of Article 4(2) Directives.
- Nelson Street Deal Conservation Area Appraisal: A review of the Nelson Street Deal Conservation Area Appraisal drafted by the Deal Society was adopted by Cabinet in January 2017. The recommendations included the extension of the boundary, which was approved in May 2017. Work has progressed on implementing an article 4 direction on the newly defined conservation area in order to manage changes such as replacement of windows to residential properties in order to help preserve the character and appearance of the conservation area.
- Waterloo Crescent Conservation Area Appraisal: The draft appraisal was carried out by the Regeneration Delivery in the early autumn of 2016 and following a period of public consultation was adopted in May 2017. Further work will be undertaken to develop design guidance on the replacement of windows in response to the recommendation within the appraisal.

## **Archaeology Projects**

- **9.30** The Heritage Strategy made a number of recommendations intended to improve knowledge and understanding, and generate greater interest in the archaeology of the District. Some of these projects are described below.
- Development of an Urban Archaeological Database: work continues by Kent County Council Heritage Team on the development of an Urban Archaeological Database for Dover; a detailed database and mapping system recording all known archaeological discoveries in Dover which will help planners and developers prepare and assess development proposals with much more confidence in their decision-making and thereby help to conserve Dover's remarkable heritage. The first stage of collating and mapping the information is to be completed by the autumn of 2017 and further funding will be sought for the development of an Archaeological Plan which will seek to characterise and identify priorities for the conservation and management of the archaeology.
- Review of historic parks and gardens: volunteers from the Kent Gardens
  Trust have completed the review of the Districts historic parks and gardens with
  support from DDC, KCC and a gardens expert. The reports will be available in
  spring 2018.

## 103

# Infrastructure

## 10 Infrastructure

10.1 The Council's Adopted Core Strategy sets out what infrastructure is to be provided in the District over the plan period. Appendix 5 indicates what infrastructure has been delivered, which projects are in the process of being delivered, and which have not yet been delivered.

## **10.1 Infrastructure Delivery**

- **10.2** A number of important infrastructure delivery projects were completed during the reporting period, many of them listed in the adopted Infrastructure Delivery Plan, but some in addition to the plan.
- 10.3 The Council's Indoor Sports Facilities Strategy (2016) sets out an understanding of the current and future supply of demand issues for key sporting facilities across the district. Specifically, the Strategy highlighted the low level of swimming provision across Dover and recommended that the Council continues to support plans for new swimming pool provision to address this. Additionally, the Land Allocations Local Plan (2015) identified that the current facilities provided at the Dover Leisure Centre do not meet current expectations and needs and in turn set out objectives to investigate the potential building of new facilities on the existing sites or whether the Dover Leisure Centre site should be relocated or redeveloped.
- 10.4 In March 2017, a planning application for a new £26 million Dover District Leisure Centre was submitted. The new leisure centre is on a 2.1 ha site based in Whitfield to replace the existing 40 year old Dover Leisure Centre. Facilities at the new leisure centre are to comprise: a county competition standard 8 lane swimming pool with seating for 250 people, along with a learner pool with moveable floor; 4 court sports hall; squash courts; multi-function room; fitness gym; fitness studios; clip 'n' climb walls; and a café. The new leisure centre will also feature 2 outdoor 3G artificial pitches for five-a-side football.
- 10.5 The HS1 rail link to London was reinstated on 5 September 2016 following £39.8m repairs to a damaged section of sea wall.
- 10.6 Provision of a roundabout linking the A256 to the Whitfield Urban Expansion (Richmond Park) is now completed.
- 10.7 In addition, works on a key road scheme in Dover comprising junction improvements at the Prince of Wales and York Street roundabouts on the A20, along with improved access to Union Street continued throughout the monitoring period In particular, the replacement of the Prince of Wales roundabout with a Mova Smart system traffic lighted junction was completed in February 2017.
- 10.8 Dover District Council have awarded a contract to Adspace 2000 to replace and maintain 46 new bus shelters across the District. Additionally, 2 new bus shelters have been installed in Deal funded by KCC. The Council is aware that some parish councils have also installed bus shelters during this period.

## **10.2 Development Contributions**

## **Community Infrastructure Levy**

- 10.9 The Community Infrastructure Levy (CIL) was introduced to allow local authorities to raise funds from developers undertaking new building projects in their area. CIL is in effect a levy used by local authorities to fund the provision of local or sub-regional infrastructure.
- 10.10 On 6th April 2011, the Council agreed in principle for the need to prepare a Charging Schedule for the purposes of the CIL. The Council consulted on a CIL Preliminary Draft Charging Schedule in December 2012, and a viability study of the proposals was commissioned in December 2013. In March 2015, the Planning Advisory Service supported an independent review of the information gathered so far and the Council is considering the results obtained.
- 10.11 Since the introduction of CIL, the legislative basis underpinning the levy has been amended by the Government on a number of occasions. Through this, the Government has sought to introduce a number of exemptions to CIL which has undermined the effectiveness of the levy as a way of funding infrastructure.
- 10.12 As it stands, the Council does not operate a CIL and there are currently no plans to prepare and adopt a CIL Charging Schedule. Funding sources for infrastructure delivery will be investigated as the preparation of the new District Local Plan advances and the Council will continue to work closely with partners to address existing deficiencies and secure appropriate levels of funding.

#### **Monitoring S106 Agreements**

- 10.13 The District Council has established a system which monitors the progress of developments to ensure that S106 contributions are collected when they reach the relevant triggers. The Council records and manages income received from S106 agreements to ensure that these financial contributions are spent in a timely and effective manner.
- 10.14 Over the monitoring period the Council secured £744,518 in S106 contributions from developments across the District. Of this figure, Dover District Council received £543,703 to assist in the delivery of: affordable housing, children's play space, community space, the Thanet Coast Mitigation Strategy, a Community Development Officer for Aylesham Garden Village, and school playing pitches. The remainder of the contributions passed to Kent County Council for the delivery of transport projects, libraries, social facilities and education.
- 10.15 Contributions secured through S106 agreements in this monitoring period are £379,875 less than last year. This can be explained in part by the fall in the number of housing completions as S106 payments are often triggered on

commencement of development or by a certain number of occupations and as a result there is a correlation between housing activity/completions and S106 collections.

**10.16** Table 10.1 illustrates which sites have contributed towards infrastructure delivery over the monitoring year from developments in the District.

Table 10.1

Development	Category	Amount (£)
DOV/13/01037	Children's equipped play space	3,306
Snowdown Working Mens Club		
DOV/00842	Thanet Coast & Sandwich Bay Special Protection area &	6,042
Land at Salvatori, Preston	Ramsar Mitigation Strategy	
DOV/13/01008	Affordable Housing	8,987
St John's Ambulance, Mill Hill		
DOV/12/00460	Thanet Coast & Sandwich Bay Special Protection area &	1,668
Hammill Brickworks	Ramsar Mitigation Strategy	
DOV/11/00965	Community Space	3,935
Woodnesborough Village Hall		
DOV/00120	School Pitch Contribution	96,116
Aylesham development	Play Area Contribution	100,852
DOV/07/01081, DOV/01095 Aylesham development	Community Development Officer	17,854
DOV/12/00700	Affordable Housing	37,169
Blue Berries Early Care and Education Centre, Sandwich		
DOV/00455	Affordable Housing	16,804

Development	Category	Amount (£)
59 The Marina, Deal		
DOV/00873	Children's Play Space	30,735
Cannon Street, Deal		
DOV/01010	Thanet Coast & Sandwich Bay Special Protection area &	64,205
Whitfield Urban Expansion	Ramsar Mitigation Strategy	
DOV/01167	Affordable Housing	134,050
Land at 104-106 Church Lane, Deal	Play Area Contribution	6,590
DOV/00976	Bus Service Contribution	15,390
Lidl Foodstore, White Cliffs Business Park		
	Total	543,703

# Strategic Sites

108

## 11 Strategic Sites

11.1 The Council is in the process of delivering a number of strategic sites across the District that are allocated in the Core Strategy (2010) and Land Allocations Local Plan (2015). This chapter provides an update on the progress being made to deliver these sites.

## 11.1 The Port of Dover and Dover Waterfront




Figure 11.1 Image of Dover Waterfront, taken from above the Western Docks

## **Dover Waterfront**

- 11.2 Policy CP8 of the Core Strategy (2010) allocates the Dover Waterfront site for a mixed use scheme including retail (A1 uses up to 20,000 square metres floorspace), restaurants, cafés and drinking establishments (A3 and A4 uses up to 7,000 square metres), assembly and leisure (D2 uses up to 15,000 square metres), residential (C3 use of at least 300 homes), offices (B1) and hotel (C1) uses.
- 11.3 In view of the importance and complexity and to enable communities to help shape the proposals for the Dover Waterfront, there is a need for development to be proceeded by the preparation of a masterplan (criterion of Policy CP8). Alongside the masterplan it has been identified that there is a need for a public realm,

environmental and highway improvement strategy for Dover Waterfront to the Town Hall (via the Market Square) and Dover Priory Railway Station to the York Street junction with Townwall Street.

- 11.4 Officers from DDC have been working in partnership with Dover Harbour Board, a landowner, a range of stakeholders and local organisations on proposals for the Dover Waterfront AAP area. The work will create a mixed use development that will complement and build on the momentum that will be generated when the St James' development opens. It will improve connections with the town centre and create a continuous commercial area stretching from the St James' development to the seafront. The site's location offers a unique opportunity to create a mixed waterfront development but it also brings with it the challenge associated with bringing forward a regeneration scheme next to a busy trunk road in a manner that complements the town centre.
- 11.5 The proposed timetable for the production, consultation and adoption of the Dover Waterfront AAP is set out in Chapter 3 of the Council's revised LDS dated September 2017.

## Western Docks Revival Project (WDRP)

- 11.6 The Dover WDRP aims to create a transformed waterfront with a new marina pier and curve to attract a host of shops, bars, cafés and restaurants within Dover's unique backdrop of the harbour, cliffs and castle. The project will also involve the relocation and further development of Dover's cargo business with a new cargo terminal and distribution centre. This will create greater space within the Eastern Docks for ferry traffic and much needed high quality employment opportunities for local people. Kick starting the wider regeneration of Dover.
- 11.7 Dover Harbour Board is currently carrying out a number of enabling works associated with the Terminal 2 development, approved under the Harbour Revision Order 2012 granted by the Secretary of State at Western Docks. The current works fall short of delivering the full Terminal 2 Scheme, but proposes an interim development to meet current port operational and regeneration objectives.

## 11.2 Mid Town Dover





- 11.8 Policy CP9 of the Core Strategy (2010) allocates the Dover Mid Town area for mixed use development of C2 uses (residential institutions), C3 uses (residential of at least 100 homes), A1 shop uses, A3 restaurant and café uses and A4 Drinking establishments uses (of up to 15,000 square metres), D1 (non-residential institutions), the redevelopment of South Kent College (around 5,000 square metres), and parking to serve the development and the town centre.
- 11.9 The development of Dover Mid Town area is considerably behind the milestones set in the delivery programme in the Core Strategy (2010) which estimated that plans and construction phases of this area would now be complete. However, there are a number of challenges in the development of the 'Mid Town' site due to complex land ownership and physical constraints on site as part of this area falls within flood zone 3. Due to time and resource constraints the Council is not currently pursuing a masterplan for this site however this will be kept under review.


## 11.3 Former Connaught Barracks Complex



Figure 11.2 Aerial view of Connaught Barracks

- 11.10 Policy CP10 of the Core Strategy (2010) allocates the former Connaught Barracks complex for residential development (C3 use), with 500 dwellings planned for the site.
- 11.11 The Homes and Communities Agency (HCA) has transferred the ownership of two parts of the former Connaught Barracks site (Fort Burgoyne and the former training area) to the Land Trust.
- 11.12 Progress is being made to bring forward the rest of the site:
- Planning permission has been granted for the Officers' Mess site (64 units) and the HCA are now promoting this to the market in efforts to secure its delivery;
- The buildings on the site have now all been demolished to facilitate the release of the land for residential development; and
- The HCA are undertaking further work on utilities.
- 11.13 The development of Connaught Barracks is considerably behind the timescales set out in the delivery plan in the Core Strategy (2010), mainly due to its complex nature and infrastructure issues set in a sensitive setting. Owing to the fact that this is one of the Council's second largest strategic allocation pressure has been put on the HCA to bring forward this site in a comprehensive and timely manner.

## 11.4 Whitfield Urban Expansion






- 11.14 Policy CP11 of the Core Strategy (2010) allocates the site to the west, north and east of Whitfield for an urban expansion comprising of at least 5,750 homes supported by transport, primary education, primary health and social care, utility services and green infrastructure together with retail, financial and professional offices, eating and drinking establishments (Use Classes A1 to A5).
- 11.15 The Whitfield Urban Expansion (WUE) SPD was adopted by the District Council in April 2011. Outline planning permission for 1,250 homes has now been granted under Phase 1 of the WUE and the planning conditions have now been discharged.
- 11.16 Work is now complete on the Abbey homes development, on the land east of the Sandwich Road.
- 11.17 During the monitoring period a new roundabout was constructed and opened on the A256 which will ultimately provide access to the east of Whitfield development. An initial sub phase of 90 dwellings is now well underway, with 37 units being completed and 21 homes under construction this monitoring year. However, the issue of sewerage still needs to be resolved and is subject to an appeal by Phillip Jeans which will be heard by the Planning Inspectorate in December 2017.

- 11.18 An outline planning application for Phase 2 of the WUE, comprising 1,190 dwellings, in the areas of Parsonage Whitfield and Shepherd's Cross (areas identified in the Whitfield SPD) is waiting to be determined.
- 11.19 A planning application by Abbey Homes for the erection of 133 dwellings off the south side of Singledge Lane was refused planning permission on a range of issues and is now the subject of appeal. An application for 100 dwellings on the same site has recently been submitted by Abbey Homes by not yet determined but this is outside of the monitoring period.
- 11.20 The construction of new roundabout on the A256 and the progress on site is now being made on site to deliver an initial sub phase of Phase 1 is extremely positive news although it must be acknowledged that the overall timetable for the delivery of the WUE at least 3 to 4 years behind the Core Strategy Programme.

## 11.5 St James's, Dover





- 11.21 The redevelopment of the St James's Area for a mixed use scheme including B1 employment, retail, residential, leisure and tourism uses is covered by Saved Local Plan Policy AS9 from the Dover District Local Plan 2002.
- 11.22 The Council has granted planning permission for:
- a mixed use development comprising of 7,473 sq m of retail (A1) floorspace,
   1,422 sq m of restaurant (A3) floorspace,
   2,472 sq m of community (D1 for

- cinema) floorspace & loss of 8,000 sq m office (B1a) through the demolition of Burlington House; and
- a 4 storey building for use as a hotel with separate restaurant/bar, providing 108 bedrooms and 827 sq m of restaurant (A3) floorspace.
- 11.23 Construction of the St James's lesiure and retail development in Dover Town Centre is well advanced with a planned opening in 2018.
- St James, Dover is being developed by Bond City and has been funded by 11.24 Legal & General Real Assets who committed £53.25m to acquire and fund the development in 2016. The scheme is over 80% pre-let.

## 11.6 Discovery Park Enterprize Zone




Figure 11.5 Image of Discovery Park, Sandwich

Discovery Park Enterprise Zone, formerly Pfizer's Research and Development facility, at Sandwich has an established employment function. It is the largest employment site in the District and comprises around 280,000 sq m of high quality research and development buildings, offices and ancillary facilities set within a landscaped campus. Having achieved Enterprise Zone (EZ) status in 2011, the site offers business rate discounts, has the potential for improved superfast broadband and future capital allowances to investors and occupiers on site.

- 11.26 Discovery Park Enterprise Zone is being marketed towards life sciences, Research and Development (R&D) and business start ups and should remain the focus for high tech research companies making the best use of the existing high quality buildings and facilities and marketed towards businesses that are not going to locate in the White Cliffs Business Park (WCBP).
- 11.27 Discovery Park is now one of the UK's top performing EZs and is home to over 150 companies and over 3,346 people from established organisations to emerging start-ups in the fields of life science, pharmaceuticals, biotechnology, science and technology and has a vibrant community of skilled professionals sharing knowledge and expertise.
- 11.28 Over the monitoring period the Council has granted planning permission for 2 applications relating to this site;
- Erection of an algae farming facility with associated external loading area and vehicular access (B1c 2,304 sq m)
- Erection of new research and development and manufacturing unit, ancillary office floorspace (B2 4,230 sq m)

(11.1)

#### 117

# eleven Strategic Sites

## **End Notes**

11.1 All photographs used in this section of the AMR are the property of Dover District Council. Crown Copyright all rights reserved.

## 118

# **Overall Conclusion**

## twelve Overall Conclusion

## 12 Overall Conclusion

- **12.1** The Dover District Core Strategy was adopted in 2010, and covers the period from 2006 to 2026, meaning that the Council is now over halfway through the adopted Plan period.
- **12.2** With regard to the outcomes of this monitoring period (2016/17) detailed in previous chapters, Table 12.1 sets out the key objectives of the Core Strategy and identifies whether each objective has been met. It should be noted that green represents those objective that have been achieved whilst orange indicates those that have been partly achieved and red identifies those that have not been achieved.

Table 12.1 Key Objectives of the Core Strategy (2010)

Indicator	Key Objective
Housing	Deliver 10,100 homes by 2026 (equating to 505 dwellings per annum)
	Maintain a supply of suitable housing sites
	Deliver the urban expansion at Whitfield - 5,750 new homes
	Provide a better mix of housing to attract families to the District
Employment	Deliver 6,500 jobs by 2026
	Deliver 54,000 sqm retail floorspace in the District, with the majority being within Dover Town
	Improve the skill level of the resident population
Social	Support a population increase of around 15,500 and an increase in working age population of 4,300 people
	Have no areas falling within the most deprived 20% in England
Environmental	Make better use of the District's historical assets
	Maintain and enhance the District's green infrastructure

12.3 The above table demonstrates that whilst progress has been made in some areas against the objectives of the Core Strategy such as those regarding the environment and skills attainment, the Council has not achieved as much in relation to demographic and housing mix objectives. Additionally, the Council has neither met objectives concerning levels of deprivation and jobs and retail floorspace provision nor the delivery of suitable homes across the District.

## 120

# Monitoring Indicators

one Monitoring Indicators

# Appendix 1 Monitoring Indicators

Table 1.1 Core Strategy Monitoring Indicators

Objective	Measurement	Base Figure	Latest Data	2016 Target	2026 Target	Comments
1 - Population and labour supply growth	Total Population	104,800 (2007)	113,100 <sup>(1)</sup>		111,500	Core Strategy 2026 target already exceeded in 2016
	Working age population (16-64)	73,800 (2001)	67,700 <b>(2)</b>		72,100	
2 - Transformation of Dover town	Retention of shopping spend	Convenience 71% (3)	Comparison 44.5%(5)		92%	Analysis from the recent Canterbury Retail Study (2015) indicates that Canterbury City Centre has increased its market share of total comparison goods expenditure from Dover's shopping catchment in the past 5 years. This may indicate that the District has lost a greater proportion of its comparison expenditure since the last Retail Study. However, this recent work doesn't analyse

# one Monitoring Indicators

Objective	Measurement	Base Figure	Latest Data	2016 Target	2026 Target	Comments
						leakage of comparison expenditure to other areas and so it is not possible to adjust the overall figure.
						This retention figure of shopping spend will be reviewed as part of the Council's Retail & Leisure study which is currently underway.
3 - Improved housing range	Local Authority housing stock	4,646 (HSSA 2008)	4,375(6)			
and choice	Total housing stock	48,340 (HSSA 2008)	53,210 (7)		59,500	
	Registered Social Landlord Stock	2,101 (HSSA 2008)	2,584 (8)		5,350	
	Rank in Kent by new Residential build rates	12th (2006)	7th <sup>(9)</sup>		7th	No new data available
4 - Progress with Middle/North Deal investigation	Completion of Investigation and Preparation of Area Action Plan		Work is currently underway to prepare a Deal Transportation Study along side work on a North Deal Study	Land Allocations Documadopted and implementation started. Work undertaken with landowner.	Land Allocations Document adopted and implementation started. Work undertaken with landowner.	An Area Action Plan is no longer required. Development to come forward via the normal planning process.

Objective	Measurement	Base Figure	Latest Data	2016 Target	2026 Target	Comments
5 - Economic performance	Total employment in the district	47,700 (2006)	40,000(10)		54,200	
	Increase in economic activity rate	%22	81.6% <sup>(11)</sup>	82%		
	Increase the business stock	35 businesses per 10,000 population	47.7 businesses per 10,000 population <sup>(12)</sup>	50 businesses per 10,000 pop		
6 -Social disadvantage	Have no areas within 20% of most deprived in England	6 areas in 20% most deprived (2007) - National Rank of 153 out of 354 Councils	11 lower layer super output areas (out of 67 LSOAs in the District) in the most deprived 20% nationally (13)	6 areas in 20% most deprived	0 areas in 20% most deprived	
	District's national ranking	142 (out of 326 at 2007)	126 (out of 326)			
	District's ranking in Kent	5 (out of 12 at 2007)	5 (out of 12)			
7 - Improve residents' skills levels towards the County average	Percentage of working age residents with no qualifications	15.1% (2006)	6.1% in 2015 No information available for 2016 <sup>(14)</sup>		25% over the regional average	
	Percentage of working age residents with NVQ level 4 or higher	15.4% (2006)	32.9% <sup>(15)</sup>		25% less than regional average	
8 - Improve ease of travel and encourage	HS1 train service in operation	No HS1 service at 2006	Service in operation from Dover Priory Railway Station (Dec 2009).			

walking, cycling and use of public transport  Western Docks T2 in Preparatory Stage public transport  Western Docks T2 in Preparatory Stage public transport  Western Docks T2 in Preparatory Stage peration  Operation operation  Operation Docks T2 in Preparatory Stage Peration Preparatory Stage Peration Toward Project  Increase sustainable Rail - 2%, Bus - 4%, Rail - 2.3%, Bus	Objective	Measurement	Base Figure	Latest Data	2016 Target	2026 Target	Comments
Western Docks T2 in Preparatory Stage begun to implement its operation operation  Preparatory Stage begun to implement its consent under a Harbour Revision Order for new facilities at the Western Docks through its Western Docks Revival project.  Increase sustainable Rail - 2%, Bus - 4%, Goods Revival project.  Proot - 12%, Bus - 4%, Rail - 2.3%, Bus - 2.3%, Cycle - 1.3%, Foot - 7.7%(16)  Proot - 12% (2001 Carle Strategy and Action Plan is currently being updated.  At A Number of visitors to Dover 280,000 333,289(17)  Seassets Average domestic water 160 litres per person 150 litres per day 160 litres	walking, cycling and use of public transport			HS1 extended to Deal, Sandwich and Martin Mill.			
Increase sustainable Rail - 2%, Bus - 4%, Cycle - 1.3%, Bus - 2.3%, Cycle - 3.3%, Eoot - 7.7% (16)  Foot - 12% (2001 Census)  Improve condition  Expand network  Expand network  At a Strategy  And Action Plan is currently being updated.  See Figure 2.4 of the Strategy and Action Plan is currently being updated.  At a sasets  Average domestic water 160 litres per person 150 litres per day 160 litres 160 l	1	Western Docks T2 in operation	Preparatory Stage	Dover Harbour Board has begun to implement its consent under a Harbour Revision Order for new facilities at the Western Docks through its Western Docks Revival project.		Operational	
brove Improve condition  Letture Expand network  Ake Number of visitors to Dover Strategy  Core		Increase sustainable commuting	Rail - 2%, Bus - 4%, Cycle - 3%, Foot - 12% (2001 Census)	Rail - 2.3%, Bus - 2.3%, Cycle - 1.3%, Foot - 7.7%(16)		2% increase in all modes	
Number of visitors to Dover 280,000 Castle Average domestic water per day consumption  Augmentation  150 litres per day	9 - Improve green infrastructure network	Improve condition Expand network	See Figure 2.4 of the Core Strategy	The Green Infrastructure Strategy and Action Plan is currently being updated.		Implement proposals as shown on Figure 3.7 of the Core Strategy	
Average domestic water 160 litres per person 150 litres per day consumption	10 - Make better use of historic assets	Number of visitors to Dover Castle	280,000	333,289 <sup>(17)</sup>			
resources		Average domestic water consumption		150 litres per day <sup>(18)</sup>		120 litres per person per day	

Objective	Measurement	Base Figure	Latest Data	2016 Target	2026 Target Comments	Comments
	Average domestic electricity 4,164 kWh per person 3,844 kWh per person (19) consumption	4,164 kWh per person	3,844 kWh per person (19)			
	Average domestic gas consumption	16,615 kWh per person	per person 12,234 kWh per person (20)			
12 - Infrastructure provision	Provision of infrastructure identified in table 3.3 of the Core Strategy	Progress report given in Chapter 10.	ı Chapter 10.		All identified infrastructure delivered	
Key:						
Green = On track	X					
Amber = Work ongoing	ongoing					

ONS Sub national population projections June 2016 ONS Sub national population projections June 2016 RNAS KCC 2007 

Red = Area of concern to be closely monitored

Retail Study Update, 2012 Retail Study Update, 2012 HFR, DCLG HFR DCLG 2016

Housing Flow Reconciliation Form 2016/17 HFR DCLG 2016

NOMIS 15

NOMIS Labour market statistics 16 DDC State of the District Report 2015 English IMD 2015.

Census, 2011 Nomis 2016

Association of Leading Visitor Attractions, 2016 Kent State of the Environment Report 2015

147

DECC, presented by Business Intelligence KCC 2013 DECC, presented by Business Intelligence KCC 2013

### 127

# Settlement Hierarchy

Train Z Z Z Z Z Z Z Z Z Z > > > Z > > > > > > > **Area/Outdoor** Recreation Children's Area (1) Z Z > Z > > > > > > > Play Community **Facilities** Z > > Z Z > > Z Z Z Z **Primary** School Z > > > Z > > > > Z Church > > > > Z > > > > > **Facilities** Medical Z Z Z > > Z Z > > Z Z **Vage** Hall > > > > > > Z > > House/Cafe **Public** Z > > > > > > > > > Shop > > Z Z Z > > > Z > > Post Office Z > > Z Z > > > Z Z Z Hougham Without Great Mongeham Goodnestone (4) **Parish Council** Capel-le-ferne Eythorne <sup>(3)</sup> Denton with Wootton (2) Aylesham Alkham Guston Eastry Ash

# Appendix 2 Settlement Hierarchy

Parish Council	Post Office	Shop	Public House/Cafe	Vage Hall	Medical Facilities	Church	Primary School	Other Community Facilities	Children's Play Area/Outdoor Recreation Area <sup>(1)</sup>	Bus	Train
Langdon parish <sup>(5)</sup>	>	z	<b>&gt;</b>	>	z	>	>	Z	>	>	>
											(9)
Lydden	z	z	>	>	>	>	>	Z	>	>	z
Nonington	z	z	>	>	z	>	>	Z	>	>	z
Northbourne <sup>(7)</sup>	z	z	>	>	z	>	>	Z	>	>	z
Preston (8)	z	>	<b>&gt;</b>	>	z	>	>	Z	>	>	z
Ringwould with Kingsdown	>	>	>	>	z	>	>	>	>	>	z
Ripple	z	z	<b>&gt;</b>	>	z	>	>	Z	Z	>	z
Shepherdswell with Coldred	>	>	<b>&gt;</b>	>	>	>	>	Z	<b>&gt;</b>	>	(6) <b>\</b>
St Margarets at Cliffe	>	>	>	>	>	>	>	>	>-	>	z

Parish Council	Post Office	Shop	Shop Public House/Cafe	<b>Va</b> ge Hall	Medical Facilities	Church	Church Primary School	Other Community Facilities	Children's Play Area/Outdoor Recreation Area <sup>(1)</sup>	Bus	Train
Staple <sup>(10)</sup>	z	z	>	>	z	<b>&gt;</b>	Z	Z	<b>\</b>	۲ (۱۱)	z
Stourmouth	z	z	>	z	z	z	z	Z	Z	>	z
Sutton (12)	z	z	z	>	z	z	Z	Z	Z	<b>&gt;</b>	z
Tilmanstone	Z	Z	<b>\</b>	<b>\</b>	Z	<b>\</b>	N	Z	Å	Å	z
Wingham <sup>(13)</sup>	<b>&gt;</b>	<b>\</b>	<b>\</b>	<b>\</b>	<b>\</b>	<b>\</b>	Υ	<b>&gt;</b>	Ь	λ	Z
Woodnesborough	Z	Z	Z	Υ	Z	Y	Ν	Z	Å	λ	z
Worth (14)	z	z	>	>	z	>	>	>	>	>	z

Not recorded under previous survey

Details not recorded previously

Including Elvington Including the settlement of Chillenden Including East Langdon, Martin Mill, West Langdon, Martin

Rail service at Martin Mill Including Emergent, man and Service at Martin Mill Including Elmstone rail service at Shepherdswell including Barnsole bus service at Staple Including Little Mongeham, Ashley and East Studdal Including Wingham Green Including Sandwich Bay

The characters in red are indicative of where change has occurred in the District's settlements during the monitoring year. For further details on these changes please see the Retail Services and Facilities chapter of this report.

### 132

# **Delivery of Housing Allocations**

three Delivery of Housing Allocations

# Appendix 3 Delivery of Housing Allocations

Figure 3.1 Delivery of Housing Allocations

	stnammoO gnized9	The HCA have been connected about this site and confirm that they have appointed WMG to investige are the utilities and will be undertaking on the site in order to facilitate the submission of a planning application	A planning application for Phase 2 has been submitted but not yet determined for 11190. The remainder of the sife has been phased at a conservative level given the size of the strategic	This site is a strategic advantage in the adopted Core Strategy and the Council is currently working on a Area Action Plant to the Strategy and the Dring Strward development on this site. The time table for this is included in the Council's LDS.	This is strategic allocation in the adopted Core Strategy. The phasing is reflective of the anticipated timetable for this site.	Phasing assumptions made following consultation with the Council's Estate Valuation Manager	Update from planning agent on 03.11.17 stating that planning application is to be submitted early in the new year	Email confirmation of phasing received from the Council's Estate Valuation Manager 15/16	This is site has been phased outside of the 5YHLS as is dependant on a decision of rationalisation of the TA. Centre (nationwide).	This site has been phased outside of the 5 yr period as it covers a number of sites and this moment in time whilst there has been whilst there has been development in the Combe Valley this is unlikely to come forward in the 5 yr period.
		The HCA has contacted a and confirm appointed \( \) investigate will be under to submission application application	A planning Phase 2 ha but not ye 1190. The site has be conservati size of the allocation.	This ste is a si allocation in the Core Strategy Council is curred on a Area Action on the site. The for this is included the site is included the site of the sit	This is strate the adopted The phasing the anticipal for this site	Phasing assumption following consultation the Council's Estate Valuation Manager	Update fro on 03.11.1 planning a submitted year	Email corr phasing re Council's I Manager 3	This is site outside of dependan rationalisa Centre (na	This site hourside of it covers a and this mand this whils the developm Valley this come forw period.
	одинест	An application for 64 dwellings has	4 applications have been granted on this site at present for a total of 1,324 total confirmation of the second				Pre application 16/00175 submitted 01/09/16			This site has been phases outside of the 5 years of
	6£02 bnoyed beseft stinu to oV	4.0	88							m a =
	95/8502 gnizer19		S							
Ш	7E/3E0S gnizeri9 8E/7E0S gnizeri9		8							
Н	3E\2002 gniserl9 \TE\3E02 gniserl9		8							
Н	Phiseing 2034/35		8							
Н	Phiseing 2033/34		09							
Н	Phasing 2032/33		8							
H	ZE\IE02 gnised9		8							
H	1E\0605 gnised9	36	05							
Н	0£\e202 gnised9	09	05							
П	62/8202 gnizer19	8	8							
	Phasing 2027/28	05	08		82					8
ear 1	VS/3202 gnizerI9	90	20		20					30
18 = Ye	Phasing 2025/26	8	08	8	8					8
,2017,	\$2\\$202 gnizeri9 2024\25	8	8	8	8			9		*
ocation	Phasing 2022/23	2 02		8 08	2				01	
the all	SZ\ZSS gnizerIq	01	01	8					-	(1)
der of	Phasing 2020/21			8		25	15			
remair	02\e102 gnised9						10			
ofthe	et\8105 gnizerl9									
Phasing of the remainder of the allocation 2017/18 = Year 1	81\710S gnized9									
Ī	Completions to date	0 9	16	°	0	15 0	0	10	0 01	189
	Total allocation remaining without	436	4434	980	100	ä	25	ā	ā	
Ц	Total units granted permission	59	1316	•	۰	15	22	۰	9	450 261
Н	Greenfield Total allocated units	808	082/5	38	100	-	2	-	a	
Ц	Ward code / name PDL - Previously Developed Land or G -	104	9	104	104	PDL	MDL	g	PDL	104
	amen / alons brew		D	own & Pier		rown & Pier	ydden & Temple Ewell	pressand	St Radigunds	12/00111 (08/01181 13/005/15 Redieurds
Ц	Planning application No	Guste	1 7 0 0 Whiffield		Priory	Town	Lydde	Buck	St Ra	25 88 88
	olf noirenings animals	15/00.260 Guston	10/01011 13/00607 10/01010 15/00878							12/0011.
	Settlement	20vee	Dover 1	bover	Over	Dover	Dover	Dover	Dover	Dower
uc	sta.gpe (изод	AQ Spring (Pressor)	O Par	Sow Warrion	Do Do	Albany Place Car Park Do	Manor View Nursery, Lower Road, Temple Ewell Do	ny School		ooms with a series of
formatic	Allocation Reference	Ü	Whiffeld		PW	Alban	Mano	Adjac	Form	
Sitein		CP10	CPIT	80 CB	8	3	8	LA6	Š	3

are 1 of 3

# three Delivery of Housing Allocations

tion	_	_																										
ssa-ppe pratog		Settlement	oM notiszilique gninnelique gn	PDL - Previously Developed Land or G - Greenfield	Total allocated units	noitzimae batneng zinu letoT Total allocation temaining without	planning permission Completions to date	81\710\ gnizerf9	et/8105 gnizeriq	OS/610S Snised9	TZ\0208 anizeriq 2\7202 anizeriq		PL/ESOS gniserI9		82/25/25 Bnizerld		82\7205 gnizeriq 92\8205 gnizeriq	0E\e202 gnizerI9	£E\0E02 gnizedq	SE\1502 gnised9	Phisedg So2/33	Phasing 2033/34	26/2502 gnizeriq 36/2502 gnizeriq	Phisering 2036/37	8E\YE02 gnized9	ee\8eos gnisedq	6605 bnoyad baseriq zilnu to oV	гришист
Buckland Paper Mill	Dover	0/90	06/01455 Buckland	HDI	265	141	124 76			8	28											-					This site is owned by the HCA who are considering the best means to bring the site forward	nare Email confirmation ng phasing received 05/07/2017
Factory Building, Lone Road	Dover		Buckland	PDL	- 00		8																				Application implemented on this site for change of use to mixed use BZ/88 micro brewery (16/00792)	3 €
and off Duned in Drive	Dover		Buckland	PDL	00	0	8			00																		Email o phasin Council Manag
and off Wycherley Gescent	Dover		Buckland	g	97		9			10																		Email confirmation of phasing received from the Council's Estate Valuation Manager 15/16
Westmount College, Folkestone Road	Dover		Priory	PDL	100	-	0 001			-	15 35	35	15															Email confirmation of phasing received from the Council's Estate Valuation Manager 15/16
Stalco Engineering 126 Mongeham Road	Deal		Great Mongeham	10d	%	0	36 0			15 2	17																	Email confirmation of phasing received 04/07/2017
Land to the rear of 133-147 St Richard's Road	Deal		Great Mongeham	9	8	0	04		13	8		_															Application received for 33 dwellings (17,700312) - not yet determined	
and west of St. Barts Road and South of Woodnes borough	Sandwich		Sandwich	9	120		120 0		20	20 8	9.													-			Pre application advice so ught 04/04/16	Developer has been confacted on 0.3.11.17 and has confirmed th planning app has been submitted and subject to approva early old/16 next year our 'if gues are flere or there abouts'
Land adj Sandwich Technology School, Deal Road	Sandwich		Sandwich	g	8	0	0 09			-	15 15	15	15															Email confirmatio phasing received 04/07/2017
and at Chequer Lane , Molland Lea, Ash	Ash		Little Sour/Ashtone	9	06	0	90 06				30	30															Resolution to Grant an outline application for 90 dwellings	Email confirmation of phasing received 04/07/2017
Land between Cherry Garden Lane and 79 Sandwich Road, Ash	Ash		Little Shur/Ashtone	PDL	8	0	95 0			10 2	8	20	8	un.							-	-+						Email confirmation of phasing received 05/07/2017 Email confirmation of
ormer Council Yard, Molland Lea 57-99 Sandwich Road, Ash	Ash		Little Stour/Ashtone Little Stour/Ashtone	PDL	s	00	90					2									-						Amendment to settlement confi	pnasing received 13/10 from the Council's Estate Valuation Manager
Guilton Farm, Guilton Land to the north of the junction of Capel Street and Winehouse Lane, Capel le Ferne	Ash Capel le Ferne		Little Stour/Ashtone Capel le Ferne	NDI G	2 0	0 0	0 0			2			Ш								-	-					Amendment to settlement confines	Email confirmation of phasing received 07/07/17
Land between 107 & 127 Capel Street, Capel	Capel le Ferne		Capel le Ferne	g	8	0	40			101	15 15											$\vdash$					Resolution to Grantan outline application for 41 dwellings	Email confirmation of phasing received 05/07/2017 Fmail confirmation of
Gore Field, Gore Lane, Eastry Eastry Court Farm, Eastry	Eastry Eastry	+	Eastry Eastry	9	88 0	00	0 0			15 2	20			Ħ	-H	-H					$\dashv$	+	$\perp$	$\prod$			Amendment to settlement confines	5 6. (
Eastry Hospital, Eastry	Eastry		Eastry	PDL	8	0	80 0			10 2	8	20																phasing received 05/07/2017
The Old Chalk Pit, Heronden Road, Eastry	Eastry		Eastry	PDL	8	0	20 0			-	10 10																	

e 2 of 3

# three Delivery of Housing Allocations

Site informatio	mation					L	L	F	$Phasing\ of\ the\ remainder\ of\ the\ all\ ocation\ 2017/18=Year$	ofther	emaind	er of th	e alloca	tion 20	17/18	. Year 1	I.				ı	H	H	L			t	-			
Allocation Reference	szalda látof	Settlement	Planning application No	эшез / эроз рлед	PDL - Previously Developed Land or G - Greenfield	Total allocated units	Total allocation remaining without	Onestime of snotheldmoo	81/7.105 gnised9	et\8105 gnizsdq	Phasing 2019/20	2021/202 gnised9	Phasing 2022/23	PASSINg 2023/24	Phiasing 2024/25	92/25/05 gnized9	Phasing 2026/27	8X/\ZOZ gnized9	0£\eS02 gnized9	TE\0605 gnized9	SE\1605 gnised9	FE\SE02 gnized9	46\660S gnized9	26/2602 gnized9	TE\3603 gnized9	8E\TEOS gnizerl9	95\8505 gnizsH9	No of units phased beyond 2039		Comments	
1432		She pherds well		Eythome/Shepherdswel G		9		9				92																		This si policy the tin the sit owner intenti	This site is alocated under policy LA32 in the LALP. At the time of putting forward the site in the LALP the owner site confirmed their intention to bring forward the site for development.
	Land to the south of Staple Rd and north of Goodnestone	Wingham		Little Stour/Ashtone	9	0	0	0													L							Ame	Amendment to settlement confines		
LA35	PPPINTS IS 63 "AURAINN PPPINTS I S63	EastStuddal		Eastry	10d	8	3	30 0			7	15 15																		Email phasin 10/07	Email confirmation of phasing received 10/07/2017
	Homestead Lane	EastStuddal		Eastry	9	0		0																				Ame	Amendment to settlement confines - pre application advice sought 04/08/15 for 2 semi-detached dwellings	s - 8/15	
A36	Sweetbriar Lane, E Mington	Elvington		Eythorne/Shepherdswell G		8	s o	0 09			25 2	SZ.																		Email phasin from t Valuat	Email confirmation of phasing received 15/16 from the Council's Estate Valuation Manager
1436	3 discent to Homeside, sythome	Eythorne		Eytharne/Shepherdswell G		22	2	25 0					10	15																This si outsid	This site has been phased outside of the 5 year perioo
Г		Eythorne		Eythorne/Shepherdswell (	9	0	0	0	l		Ļ			t	ŀ	$\vdash$	L				ŀ	ŀ	-	L	L		ŀ	Ame	Amendment to settlement confines		
Г	Eythorne	Eythorne		Eythorne/Shepherdswell G	9	0	0	0						-	H	H	L				t	H	H	-				Ame	Amendment to settlement confines	2	
LA37	Land at North bourne Road, Great Mongeham	Great Mongeham		Mongeham	9	10	1	10 0			9	10																App (16/	Application submitted for 12 dwellings [16/00986] - not yet determined		Email confirmation of phasing received 14/07/2017
	Goost Managem Farm Cherry Isna	Great Money am		Median				0																				Ame Appl agri dwe	Amendment to settlement confines - Application for conversion of 2 agricultural buildings and 2 new dwellings (17/00157 - granted outside of this monitoring period)	s - s	
LA37		GreatMongeham		Mongeham	9			0	t	H	L				t	+	-	L			t	t	ł	-			t	Ame	Amendment to settlement confines	20	
LA39	Land between Innisfree and Glen Lodge, Glen Road, Kingsdown	Kingsdown		Ringwould	9	0		0																				Ame appl (17/	Amendment to settlement confines - application received for 1 dwelling (17/00564) - not yet determined	÷	
1941	reet, Nonington	Nonington		Aylesham	PDL	18		35 0				8	15															Pre- 02/0	Pre-application advice sought 02/06/17 - PE/17/00107		Confirmation of phasing received 06/07/2017
7	Land at Lynton, Mill Lane	Nonington		Aylesham		0	0	0	Ť	+	4			1	+	+	4	1				+	+		1		1	Ame	Amendment to settlement confines	20	
٦				Totals		8354 1782 6572 184	2 657	2 184	0	33 2	40 39	33 240 391 294 355 275 205 200 150 159 100 100 86	355	275	202	00	15	9	100	86	8	S	20 20		S	20	50 50 3584	35.84		4	

e3 of 3

### 136

# Appendix 4 Extant Planning Permissions

Figure 4.1 Extant Planning Permission

	paracecy	Currently. Es units us build out on this size has been allow despize the fact that the flood defence resources were in place.	This lide has been phased out of the 5 yr period as the renaint in 26 unts flasts the developer no longer warfs to pursa. Anne application for 30 deel legs has been received but not yet.			The renainder of the hybrid planning application has been planned over the 5 y period as different horses are currently on the.			Costrecorded in LIV Mi survey - no amendment to male, site considete			Net gan 0 - norous 2 fron total chasing figure (n. SYMLS) cas recorded in 12/15 survey - no		Phasing assure phoes reflect	current build out raiss which the developer within to maintain. There are no infrantucture constaints to this build out rate.	Site now built out.		Total net gain 1 tharefore remove 1 from total phasing frot in 9H1S)	Total net gain 1 thanefore remove 1 from total phasing/not in 99415)				Total net gain 1 therefore remove 1 from scal phasi nginot in 19H15)	Total net gan 1 therefore remove 1 from seal chain refine in 904150						
ŀ	REGS broayed beauting ration to old beauting from stron to old				H												t													
t	TE\AEDS gelean'S St\TEDS gelean'S				#		Ħ			H	L			t	8											_				
	SE\ZEOS grinerio				#		Ш			H	L			t	9.		t					4				_				
ŀ	AT, LEDE Spinselly 2T, AEDE spinselly				₩		H			П	-			H	9		+				Н				Н	_		+		
ı	EE/ZEGZ Busings														9															
ŀ	TE/OEDE Bujunid				╫		H		H	H	H	H	H	t	9		+				H				H	_				
	OE/SEDE Burshid SE/SEDE Burshid				H		П			Н	L			Ŧ	40 40		F				Н				П					
	BE/LEGE Burney						H			H				t	99		t				Н				Ш					
ŀ	22/SZDZ Busseld	52			₩		$^{+}$			Н	┝			+	9		+				Н				H	_		+		
ı	SE/VEDE Busines	20					ш							t	9										П	_				
-	EZ/ZZDZ BUNNYA	200	20		-		+			H	H		-	+	9		+	~	~	-	-	-	~ ~	-	H	-	-	+		
	ZZ/IZZZ Burneld	8													9															
ŀ	OZ/610Z Rujskyd	22			#		H			Н				+	9		+				H	-			3		H	H		
I	61/8102 Superior	115			7	8					-			0											6 12	-				
ŀ	construction (Column 5 plus Column T))	91	×		3 4 0	8	-	-	٥		-	**	1	0	180	٥		- ~	~	0 1	-		~ ~	-	22	~ 0		- 0	0	
ļ	no grinismen stiru to ok sij stiru treste leto?										۰			0							٥	00							0	
	zinu. a.() yevnus sits gained stol stims to oli			0	0 0		00	olo		0 =	-	0		-	0		0			N 0	0	00		0 0	0	0 8			PA .	
ŀ	No of units under construction Units completed during the survey year	2		-	+	8	H		-	10	-			0	-	0	-	-			0	0 0		-	-		-	•	0	
Į	betrate ton atima to off	170	ž	0 1			00	0	٥	00	°	0		0	798	٥	0	1 1	~	0 "		- 0	~ ~		28	- 0	٥	Î	0	
L	Net number of units on application (le Column P minus Column Q)	Ŕ	8	,	1	ä			°		12			_	120	250			-		لِيا				77				2	
L	cyaudic o, me (Biose) go o, meja jost ou abbycatiou (puonilly quinoption ou	۰			II.	Ů	Ľ			Ĭ,	Ļ			1	°		1		-	ů	Ľ	ľ			Ľ	ľ			-	
ŀ	bisiness 2 - 5 to brail bequipped ykuolvet 4 - JC9 futors political per pattiring ratur to off	28		d .	15 6	2 2	H		-	Н	- 1			ď	177	238	1				Н	0 1			4	O O		1 0	-	
Ì	Ward code / name		-	-		-	00	98		è e	-			2			9 .								-		- 20		2	
					pergane		pang c		4 Cliffe	Sakon Ehrs ValaBhiony Saks of						Shidden						Little Sour/Ashione Castry	herdowel			.	Shidden			
		-6			home/Shap	lad gurds	VTorrple	96	s Canada	V Chris	Redgands	Autgards		Dead	5	Ded & Sho		one le ferre		. 6		tour/list	ne/Shiple	gacong shelth	Radgends	Teo Dear	liddle Deal & Shidden	78	Pier A	
L		Sardee	Webse	3 /	0 2			Whathe	- 5	5 8				North	Medv	Widdle	water	5 0	Wahre	Wahre	Wahre	utte 9	Wahre	3 5					Town	
	Spidthon RO	15832	15163	15178	15045	14286	164339	144808	14472	1509081	1425.55	14232		15272	151278	15262	200391	118528	15138	1501F	14564	158457	1896aT	15838	142230	153403	152215	15239	139978	
Ī	Sutres 50	63.837	63.628	637660	67.676	63080	62883	6300.99	63/00/20	637597	630077	63.0063	00000	637543	633672	635577	637536	62.076	637728	63,0779	636622	62805	62794	68.016	630616	999.69	637165	63.556	630633	
ŀ	Application area (ha)	1	3	000	180	3.8	0.00	000	800	900	910	100		900	90 98	7.3	0.18	013	80	000	110	000	0 00	80 0	0.74	000		9100	000	
ŀ	Appin type (in Ct, RM, Ft)				#		-		H		L	Н	₩	ł							Н	7			Н	44		$\vdash$		
ŀ	agap Aydrg	8	- 0	000	100	1/80	14 500	0.00	0.04	14 150	14 200	0.00	9	0.05 FL	000	0.00	1450	0.00	900	79 900	NZI STO	035 FL	13900			1300	0.06 Ft	1/90	13 900	
		10/07/2	24,05/2	27/03/12	7/10/10	20/02/02	17/05/1	20,004/2	07/10/2	14/10/2	09/02/2	22,02/205	04000	09/10/2	05/11/20	13/11/2	2/10/90	11,04/20%	30/04/2	13/05/2016	24,06,202	18,07/2016	OL/NR/2016 OR/NR/2016	25,090	W/10/20X	07/10/2 18/10/3	14/11/2	16/11/2	16/12/2	
Ī	Section date	1/2003	9000	200/2003	0,004/2010	9,2010	V2010	2004/2011	72011	1102/4	2/2013	2102/20/2	A COLO	V2012	72013	1/2012	102/1	II/04/2018	4/2013	BANG/2013	\$72013	26,07/2013 26,07/2013	G/06/2013 GN06/2013	A2018	06/10/2013	V2013 V2013	M/11/2018	1/2013	6/12/2013	
L		out	0/4	War 2	0,0047		17/05/2011		07/10	1/0	102/20/00		8	17/00	1/90	1/11	2/20/20	0/11	aus		20/06/201	26,0		0 %	17/00	17/3	1/4	1/4		
Ī	noistinsed	on before a developered control they glot film bend to bouse with grangs, poring and access fereigo by wayed a new estate road layout connecting the strangaler boad and an hemergancy access to Schoolech Pedazahal Listan, begicher with seculated words roads ing banding, landsapping and dealings works and the formation of public copen- nation of the secular securation security s	Drange of use and exciton of silons, deedings for like affordable undig he observed doctors suggery which age with weighting problem branchall plannings, how here to there had drap to provide a STATH Claus III how eyes, together with nuces had road paching, googness of for dissivers, handsaping it no roading of right of account	wing of our de spite De Tallacher excellent of 2 deal allegio Dimense (rest verd weg retail derectains of resting building.  Coll cont a datached building incorporating 1.2 no. resident a fluis and entation of 6 the bind cont on deal legis and construction of verhalter access (set sizing public bouse the bind control of the spite for set.	ated	posits A(NS), Ane one and		Fredion of a duadwood dwelling and construction of a white clar access (size amended by loppid cate on LEXXX 15 to add an extension on to the house which afrestly has permit salon but any construction of the production of the production of the Duales of use and inconvention to a find a residential heading.			rlacs	Dange of Lus and convenion to two resi dential dwellings. Bell string single stoom from a tons ion to be dened sinedy.	Trought or agrammer comment.  Therefore of one of ground and first floors to a nuseum? Beauty Boar Class ED) and the resists of one self-contend flast at second floor, together self-the exection of an immediate out that welf-handrals. In second list is that and a detained manage.		residential devid opment of up to 1210	ADS London and cyde riting	ess n of a detached	graph to supervisors to 2 dwellings the cloud first and rear domes road solars local to a storey table extension and rear consensiony (existing conservatory and solars local to be derivelently and greation of access and puring.   11.1	and second floor	rendered to a pight story dwelling and erection of two single story electricins to burge of use and conversion to dwelling, eved on a single story actors for conversion of amount to offer, and allots external alreadors and construction of refeat at cons.	wat of planning permission DOV/10/00388 for the erection of a detached dwelling	ir panagara	reained flats	end for and	grandesp	a for phase 6 of	restriction of attention and conversion de subreg building to form dwelling excellent of bookle garing and associated work garanded plans - industry the incorporation of a garind code to garing and a first was being required and artificial and controved. A state of the state of the controved on the state is a con-	dregs derection of	souched or parting and lands; at appearing to that up to be denoted but	
		t grage truth as matter	Mitter und State with Cofright	affes an	u Yasno	Siregolet Neszaua Adacose 80 bedra	a acess	r access ich afres	9969	r acon	ortaine	a Bayes	frech free		-audopu	ocessoria edearia dated po	oracac d arecte	andrea ealsting	noffrit	torey at	on of a d	200 DEC	gas o ang	a possoci na of g	8300 B	toreroor sing laye	regibe in a)	resons a	to be of	
		mecting mecting bygethe sytthe fo	Margard Set byget -roufing	du ding esidenti dar acce	order acc	(ii) compraints (iii) cafe anting ar laturits, ref lands	ehicular vehicula	vehicula ous e urbi	oe demo	which	B 7 s eff c	100	/ Brary gether wi	prations	ritial des	Your a	of a vers	nof ford watery ( parting	owerso	sreje s eratoro	e eredic	7 9 100	egue p	ange of	pue suc	x with a wed part	ing to for ting gate	Surding roof ests	bolding	
		s and ho ayout co al Esate, works a	gs (nd.) provision bor spa	ElZnor g1Znor of vehic	28 flab	ge of us caping, p resident arance a	tionofs tionofs	to the h	Negto	tionofa	g and lar	that due	floor, top	Second dis	rareside	w Road, w Road, c Church	ed car pa	arcone essand	Sontte	edion d ecrait d	till for th	ecrasi du	erkiá du	all for cl	coler ao	twofun to appr 0673	ing but ed plans dace on h	dorner	(estative	
		g 303 flar te road brokazis drainage	acting Das 81 Lendon	the erec sporative struction	y Centrol	and char east (A1) on, lands op to 265 als, appe	CONTRACT	resion on	Zive dw	CONTRACT	bubbing by	o resi de	t second	ndasso	attonfo	A Fornsk olden Ne 3 Stol der	and con	n andre on of ao	WDADO	edre, co	W10/00	de reso	withas	900000 W10\00	ou of weh	poratory terations DOV/ON/ Effoor to	for each for each	shigh re- two side	dicaping	
		oreprising new esta landwich sing and	nof: Sinc mcBay t 1572n² i dayared,	rop to 2 flats and the of easting building hed building worm buildings and cons.	S and to	ew build if units, n. spen span is all for u, syout, so	ding and	ding and dancedo	lvg (o b	The and	securing security	Sontotes 3	of first hed first all	of shedy	gidde aus	to of the are	ding and	iento Ze redensio nd oreats	od no tech	y dwell yonto de k.e, ass o	groups	drig drig	and lings ton of sin	aton DO	and the	ding hox ers and all dunders on of fine	ornersic ad work a brick w	angle a setonol	and lan	
		wayof a coss to 5 bridges	duding a provide: :e find pl	repto 2 of existin hed bulk hed lings	dueding rgmy, Co	mert (v 1s identa. 248 f. o 1A. 2.38 atters (b	hed date	Tisto ad Uction)	sed dwell		ess and a	convers molibres	feortain stars of	be dene	stion - Ej Outine appil	noy acce ween the fragnicity	heddael	zeyside streyside fehedia	'Bit and to	controof	g permits	sed dues	sorvers.	g applica vel clerts	fings, co to be der	hedbur hyscote ngranto convenie	associat age and a	sion, or	ir parling	
		al develo, precoby precy ac xanding,	Fuse and argery in I drugs to spen spac garden	rollion Faddao Hooms	o as obross native hange of use to 2 dwelling; send construction of whicular access reed on of a 40" surgery, Community Centra, 28 false and 41 houses, related	for 14th n ty hub/ (f (phase): otherm	4 a deza	Auconal MODAL of MODAL	ra dezed	fa dead	of 5 dwell	to be de-	fore sell	Drage to	pleation	demerge entable g and in	fadead	fuse and s, two sto se derso	f planni.	9 and 15 1 use and n of carp Kors	fplanin	T a dated	'use and	f plannin o sinele r	A 26 days	Tadita (credii embio	rage and of to gar	ory ater.	clated or	
		texteent coess for a th emer- robading b	hange of foctors a, tony bull sarking, o temorial	artial de rediono o, two be	harge of redion o	A sed use phase 1). corr mant ropos dis.	redions	redion. opticato rditurd	regiona	rediono	redion (	hange or atgresion	hange of reation o	est Sing a	symple of the state of the stat	redion load) and reprovers ands capin	redions	harge of atms for arage to l	renewal c	numbers hange of ornersion ehiodar a	greeato	ands capit red ton o	oo jan oo ay	retion	redion.	redioni redelect farrings hange of	redion. locklegs (td)edro	orneral orneral	rea, 8500	
l	Serial eresent	5			witten		NY.	150	2 Maranets D	a d		and a	,	2	ehan	aden i	,	pette ferre		in the	7	landeith la		moods.	1 1		-		Mer.	
İ	Forbal ledson		å	ě ě	5151 6	8	oc.	ŏĕ	5	000	00	ŏ		0	Ą	iden Sh	ő.	5 5	ő	, e	90	25	90	3	νg	- 616	ő	5 6	ó	
		Mgate Pood														h East of Sendwich Road (A.254) and Rort: Was t of Solden New Road, Solden Year Year								ea, CTI a Sup					910	
		Sale, Roc			Ш		П			Ш	Down					3rolden					$\  \ $	αD		8 00em,	Ш				or, CT17	
		Shride	29.		Ш		Cuel				The Road					Weto	CT14BA					W CITS		ade, roy	TD 00.Y			2 8	afe, Do.	
		Sandari Sandari	ad,wa	Wakrer	warre		Temple				Side, Lon					ndNorth	Wahrer		34.746	T13 08V		n, CTS 2/	J l	gton Pa	DOMY, CTD BY		9	ACT14	stone Boad, Ayd Fe,	
		W part of	anada Po		ne kard, re	Died o	hStreet, wed			Down	rd fast	1			5.0	P 250 as	Parade, 1	2112	Deal,C	T14 TQ	hra, Da	Sandwid Gore La	TABBL	Z William	y Board, C	1	CTIASM	Poat, De	atore 8	
		- Street	ctonic	th Barra	ones to	T H	tage, Hg Temple E	Whiteld	aret's Ba	or Road	Tartris Ya			714640	n, Alykest	ich Road	trutton	76, Cl. 8	Webser,	r, Deal, C	wer, Wal	Cottages	Whome,	VCT139	e De Vaño	1460A	ne, Deaf,	vtrcote	Oldfolk	
		r Stor	stem Se	ning Non	Burgit	II Oab	as and	t Boad, V	8 Mars	Post Fa	ite, 2 N	at Dose	1	d.Ded.C	Wage Espansion, Ayleshan	# Sended	- 92 WK	Selle fer	2 Beach	( Wahre ( Down F	Hawledo	The Src	, Warner	ianded	Pe, Coon	Doel CT	V MILE	of to, No.	Access,	
		h of files	vads (Ea	I. & land adjoining Porth Berradi Poad,	ope board	Paper N	the adjoining Starley Cott Undown, 15 Waters and, 1	ne Court	Be Road	rear of 100 folkestone hoad Do at 3 Herschell Road East, Wahres	er Car Sales site, '& Marfirs Yard, East	ti London Road, Dover		hope Road, Deal, CT14 6AD	e Wilger	thfato New Fiel	zguaan.	apd Street, Opetic Form, CTIS 72	KHOUSE, 1 The Beach, Walner, Deal, CT14 THE	S Station Road, Wahrer, Deal, CTIA TQR nnnear of 88-84, Dover Road, Sendwich, CTI3 009	Land Adj, Hawledown, Wahrer, Deal	ronking 50k The Street, Ash, Sandwidy, CTS 2Ah.	Netroy, Charch Hi, Eyhome, CTLS AME serpool Road, Walmer, Deal, CTLA 7H.	arqueers to burniversome, 108 M	Yer Barwick Site, Coorabe Valley Road,	armon Street Deal CTL4 6QA Georges Passage, Deal, CTL4 6G.	observed Mill Louer Mill Lane, Deal, CT14 9MG	noor read, rece: harop Anjacento, Northcote Road, Desl, CT14-89.2	Gles Cottage & Access	
		androut	iorh Ban	Notab	59 Adeta	bookland	Sze ad ol	HAArch	5 Gram	Academ	'arrer G	90811.or		41 Sarbs	Western	and North	undbet	Capel St	Tark Hou	915 Stati	3 loss ta	andfror	Q Uwrp.	5 Herret	graceB	15 Carro	DattysN	Morkshop	Stoller	
ı	Allocated Site Policy No			T	Т	8	П	П		П	Γ	П		Ĭ	T.W.	WIZ	П	П			П	П			Ne v	T	П			
ļ	(M no Y) notitality application (V or M) (M no Y) notitality and make a sidt at	8	z	2 1	2 2 3		> 2	- 8	>	2 2	2	2 1		2	ž	k	N :		2	> 2	>	2 2			2	2 2	2	Z	2	
İ	Appn status (Not Souted, UC, CP)	8	8	8 5	88 8		88	85	8	88	3	8 8		ô	8	å å	9 !	5 2	2	9 8	22	13/002/7 NS Y N 13/0024 UC Y Y	2 2	2 2	. N	88	ð	8 6	8	
- 1		187	ē	5410	2000	9	11983	20073	100	10037	11.02	5800	688	9,000	1001	3001	0000	900	9810.	2000	ogo	1200	10000	2000	10000	000	990	omo.	0.000	
						et 2	扫描	1 38	1 3	ı≓ŝ	1 8	1 ≦ 8	2			3	154 3	સ ≱	- 8	S 2	1 %	2 2	i≥l ≦8	al 5	a >			H 3		

159

	princed for signify of the signify of significant s	Application built out			Net loss 2 therefore dedut 2 from	Net loss of 1 pot in 574 by Net loss of 1 pot in 574 by Net loss -1 therefore distact 5	from stalightsing figure (in STRLS)		net gan of therefore ratios 2 from the total phusing figure (in 5714.9)	Net sain 2 Berefere remova	from total phasing figure (in SYM.S)		15 units remaining cortine at the have been phrased in the first year as the devel open is on site.	Net gain of 0 therefore narioue 1.	from the total physing figure (in SYMLS)			Net gan of 3 no amendment to make as complete and nothing to phase	Net gain of 1 ferefore ranou. 1 from the total phasing figure (in cons. 5.										This size has been plaused outside of the 5 yr period at there is currently uncertainty on the plefvering of the size. The size is allocated in the LAP under policy is AB.			or created in 19 to answer	all complete nothing to phase				
	AL NOON SHOWN BE/CECK School Section 66/RECK School S					Ħ																		F		ŧ				Ħ	7	7	ŧ				1
	SE\RECK gnised*			ł		Ħ		П				Ħ		H								F				ŧ		H		Ħ	7	#		Ħ			1
	EE/CEDS galands M/EEDS galands																														7	3					
	Ef/EESS gelean's			t		H		П				Ħ				1								t		t					+	#	#	Ħ			1
	et/atot grineri		Ш	1	L	Ш								L								L		L		+		H		H	+	1	#		Ħ		1
	TC\2005 gniseff		ш	t	Ł	Ħ						П			_									t		t				Ħ	#	#	#	Ħ			1
	ST/SCOC Bulletin			ļ		H										#	#							Ħ	H	ļ	ļ	H		Ħ	#	#	#	Ħ	H	Н	1
	EZ/ZZOZ Bujana		3	1		9 17		П		1		П				1				Ė		Ė				ļ	t		972		#	#	#				1
	tc/ococ Bures,			ļ		Ħ				1						1						F		F		ŧ	ŧ				#	#	#	Ħ		~	1
	BI/CIOX Bussell			ļ		Ħ	9	-	-	1	×	Ħ	81		-	-	1 6			-	-	Ħ		-	+	-		1	-	P.	7	7	#	Ħ		-	1
	otal seatant units (ie No of units remaining on ripplication which are either not started or under centruction (Column 5 plus Column 1))	٥	3 (	-		7 7	9		~	٥	м.		8	T	-	-	1 6	۰		-			۰		. 0	1	*	101	220	~		1	00	00	П		1
	so of units lost during the survey (i.e. units femolished or change of use underway)	۰	00	٥	0	0	00	0.0		0			۰	0	0	٥	00	۰		٥	0 1	۰	۰	0		0	0			٥	0	0	00	00		00	1
	éo of units under construction Inits completed during the survey year	0	0 0	0	0	3 3	00			0	8 8	0	= = =	-	8	-	0 0	-	^	-	3				- 0	-	4	000		0	0	0	88	5 5	000	0.0	1
	es of units not started	2	9	-	-	9 9	-		. 0	4	~	H	8	-	0	-	11 00	-	-	-	n .	-	-	-	-	-	61	1 0 0 1	22 02	~	+	+	0 +	0 0 0	H	00	1
	to notifiomab diguoriti notication provide demolition or familie of use (gross)	۰	00	٥		-			N	٥		۰	۰	٥	-	٥	00	-	-	٥		۰	۰			٥	•	0		۰	0	-0	-10	ľľ		00	
	bielinean C - Creenfield  Land or C - Creenfield  (eron) of unit permitted on aplication (grow)	2	100		0	2 2	9 1		, ,	D)			9 XZ		ğ	70	100	Ď,			g .	. 18	, a	υ.			g ,	0 70	g g		-	-	g o		, p	9 00	
	дина соде / изиле			ned	8	8	dden				8	8	qqe		8	Me	ndowell	&mon.		necl	Ш,		8						8	8	8	poor	arre arre	dden	200		1
		ek	rhankts	dder/Terrple Ewell	tte Sou/Mhene	tte Scor/Ashto	Adde Deal & Shidden sable	own & Pier	oreg	Adjunds	Utte Sour/Ashtone	Sou/Ms No	liddle Deal & Shidden	ppo	te 2cu/Ashene	Margaet's at Offe	horne/Shipherdavel wn & Per	MON Elms Valderior	to Sour/Mythere	rdder/Tarsple Ewell	ardet di	dig.	tfe Sour/Ms Hone		Fast Buddel	Harriets	6	Tadry Walner	Te Sour/As ho Pad gunds	Bour/Ns No	de Stour/As Hone	dden/Torple Ewel	tte 2cur/Mintere t Mergaret's at Citr	e Dest & Sh	Worth Deal	esp	1
	gridtion Ri	5975 What		-2		156250 Utfe	152738 Widdl 141400 Casto		146506 Brgs	142285 St Pac	1578XSUITE		152578 Wedd		com little	×	1483G fyho 14115 Town	141302 Maso	- 5			1579 <i>G</i> Sarch	- 3		145638 Eag 5	2008 Towe	SEE Sard	154930 Eastro 151105 Walve		- 5	160196 Utfe	145427 Lydde	150747 LINE 164055 St.Ms	165t Eastn	1525.8 North	1415% Caste 14523 White	1
4 on	Buggers by			11 11 11		03220	1200	30750	63.2897 14	3076	624612 15	24659 15	69807 15		2.263	935.66	3 EOS 14	21.77	2610 15	03009			624601 15		632568 14	3726 14	15001 11	63203 11	11 12		28871 16	17	1035	354.78 15 342.08 12	63.880 15		1
Extent Planning Application	pplication area (ha)		0.027	0110	9 590	000	9 9000	2000	174	000	0.0	9 9500	1517		990	9009	018 0	800	800	011	000	010	910	2200	1.6	000	573	000	297	010	9000	9900	000	000	0000	000	Page 2 of 7
Deart Plan	(Pi OU, RM, FL)	-	14	ď	У		٠,	٦.		7			×	2	=	ž	70	-	-	3				4	1 1	4	2 :			Z.	N.	ŏ				32	
	agap Audic	12/03/201	19/09/201	29,04/201	07/08/201	13/05/201	27,05,72017 C	04/06/2010	11,06,2017	11,06,201	25,06,2017	03/07/2010	04/07/2010	102/20/00	202/2020	23,07/205	28/07/2017	01/08/2010	ON WEATON	27,08/201	10/09/201	17/09/201	22,09/201	24/09/201	06/11/2017	07/11/20	13/11/201	25/11/2017	107/21/01	17/12/201	17/11/200	06/01/2038	202/10/20 202/10/60	19,02/2012	27/00/201	12,03/2018	1
	data malaba	403/2014	V03/2014 V04/2014	29/04/2014	0,05,2014	DANSAZOTA DANSAZOTA	27,005,2014	04/06/2014	1,06,2014	11/06/2014	2,06,2014	107/2016	/07/2014	07/2014	102/2014	8,07/2014	28,07/2014	A,08/2014	N.YBC2014	V06/2014	000/2014	0,00,2014	25,09/2014		00/11/2014	/11/2014	15/11/2014	2/11/2014	D/12/7014	/12/2014	/12/2014	00/01/2018	G/01/2015 G/01/2015	202/2015	27/03/2015	03/2015	1
	подартия	nded n	-			Ħ	$\dashv$	П		_	$\neg$	-	S S S S S S S S S S S S S S S S S S S	8	8	.	T	8			Q :				y to	8	9		4	TI DI	eting D		+	RR			i
		Soping, acors, scale, Layouci 00/4/10/2011 phase 1A gime	ling and contruction of a whicular access contruction of a velt oder access and parking lies size		redi on of a dwelling and gazage (dusting outbuilding and gazage to be deen oldered). hange of use of dwelling to form a 12 bed boarding like liky and house parent. commodal on, together with the ence ton of two, two-stoney side extensions (a stain).		Authorized to the control of a detacted building incorporating four flats active buildings to the denotes heat.  The second of the control o	abovette	institute to observe and against the condition of the condition of the observe conditions are the conditions and the observed the conditions and the conditions are the conditions and the conditions are t	one car park	white on of property into three separate residential E3) units, rear extension and starral absentions	1 50000	se evel nitico spokažion for residental skekioprerect of 300 deel legis of public sporosopis and a coso from Harcock Held, human Well, and legis of the Valdeg sporosopis od sporosopis variety and service respectation sporosopis vode, kad recessive to establing public regis of service sporosomic, buyes, and such	athritae	realtion of an access (retrospectivel) drive, gales ; ferrorig and hedging lesisting, had ling to be derived being favored if alm s).	integration of a debiation oberating, construction of versional access and association of such kig. Such a against about for the evection of a detached deal king, same and creation of	d design)		b-disk son of estaing dwelling to form two separate dwellings and elevational annealism (amended).	ege to be	harge of use and convenion of that and second foom to three self-contained flass for agrowed for the change of use from an agrouhuselbuilding to a residential	(arrended p	treation of a no, dwellings on size of former budder's serial industry, deen observed enabling bud dregs and pair, rouse of enabling materials, and provision of bamporiary construction access from 8. Mary's Meadow.	re obshed) rd associator	Jaint ve. Presti on de adstadred dwell ing and there bay agricultural building with cell on over to nobule landscaping and as coloued worls. (a lating mobile home to be removed)	4 to outline	Acodhesboro E garago ana	fred on of obtached dwell Vg. Change of Use of Oz. Bulding to Single Supported Living Unit.	rection of a detail rectioned upon the second and care packing the extent out in epiderring permission (DOV/07) (1000) for upon 200 deed lings, and and any produced with the second with the second care produced and careful and conference and careful the line for the preventation.	o two resides	espectal du	Octobre application for the evection of a detachad dealing and construction of a vertical or according to the constitution of a detachad from the form of the constitution of a province of a detachad conference or dealing from the foot the their form to be decirible of the constitution of a detachad from the constitution of the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detachad from the constitution of a detac		redi on of a detadred dwelling with associated parking. redi on of an attadred dwelling and creation of vehicle at costs	and associat	Charge of use and convention from offices to 2 cleedings and a files incorporating 3 to account to rear elevation (set althig single store) rear electrical to be demolshed from the control of 3 deeplays and creation of whouler account and pushing.	1
		rig, access, s 710/2011 ph	of a whicula		digarage to story and hor story side	and line	g incorporal realined file	contained flat and one majoriette	ed works (e	creation of	nitt, rear o	of whicuts	it of 200 den lab, and Hy rig Landscapi sppearanos,	colar access fr an d'fice i	Bandhedgi	V. Briggin	vehiol # is cos i redi on of 9 dwelings libetals pun unk to ID24/1AVXII TR) (an ended dis lgr)		et Ings and	od Buyson	building to	demdibled	dindudre, d provision	eds to be de dar access as	attoubling w	sect pursue	fred dwell in	Unit	ng 299 for up to (enisting but mentaliton	budding int	a bding to a n	of or or or or	hicular acon	r acons	mainedflat	r and & flats terration to be and parking	i
		9 9	onstruction of a verto.		Abulding a boarding flu of two, two	esideritate	ched budde	ortainedfla	and is sood a not lahed)	transes suc	breat City	constructo	developmes ( Huntons W incorporati nds caping,	disease with	ales fendin	Chat ded is	20/11/00	tainedfats	separate de	Buryand jo	end floors	dregstobe	builder's yer reateriels at	budding/9	y agricultur statug m obi	f vehicular sideresis ph	not a dead	ortedtWrg	ed car parks DOV/07/011 ated works R for impler	apricultura	rioduratio	Chan Dave	tionofave	tod parking	a to a self co	o 2 duelling prey rear es Aar access	1
		atters application for 76 dw d fings i details pursuant to outline pennie	fing and o		r a 12 bed he grection	one shifte	on of a deta adi upper floor	o orno self o	rg facilities ay to be der	h i i rogral vol shedi	parate resi	garage and	residental recodos Field : Bary work: Is of way (bt	and detachs	net dive.	on of a deta	unumeto	version of easting building into 6 self-contained fats	to form two	indoreator	fink and sa use from an	prog Buzza prog	of former of eathing 's Meadow	o haing out	ed worls (a	d oreaton o	fre erection	Single Supp	nnd a sod at permis sion ( s and a sod the three line	use from an	use of an ag	on or a Deca	enterophia	with associal and creation	storage are	or office to ing single st on of vehic	1
		pleaton for oursant to	оз якданорафезре из из гразд Виданорафезре из до из гразд щанорафезрация де из гразд	receiped	gandgarag tilling to for other with t	s reat) verifings into	a derotal revention of	large of use and convension into one self	ings, parep vd.2 Hope B	n houses with	rito three se	d dwelling.	plication for ess from Ha objective, and g pubble right	dduetre	(retrosped shed) (and	o ower rg.	ts Seeals p	Ebuldingi	g dwelling	Buganop	riversion of	Bu panp p	dingsonsit dpat reuse fors & Man	Suppopp Suppopp	d dwelvg.	dwelling an	Discussion for	dueling Dubling to	d dwelling. e planning : ethic le acces r to extend	o charge of	charge of	of the entered	Buganop	d dwelling	rwerson of	ration (est 9. ps and creat	1
		Smatters ag nc di detals	of fishent do of an attack of a obtacks	restobed	of a dwellin of use of dw odel on, top	on of two d	pplication f buildingto of use and o	of use and o	of two dwe	of four four sizing build	of property alterations	of a detach	freatters ag ice, with ac de paths, fr ris to existin	of a detacts	of an access to be deno	or a certacry god cation?	of 9 dwellin	on of easitic	don of est 23	of a detachs red)	of use and o roval for th	of a detachs	of 4 no. dw out drugs an tion access	of a deads	of a detach	of deadler finations ag	on DOW/12/ fireatters ag	of detached of Use of Ou	of a detach searer out is proposed red), in orde	orosal for fi	and section	pps cace	d plans) of a detach	of a detach	of ose and o	of 3 dweller	1
	\$19,619,623,6	Ristoria appeara detably	fredion	outsuld	Charge	Convens	Cuthe	Charge	Eredion	Space			Risiave open spi noads, o alteratio	Credion	du ding			Converse	Sub-div	(nedion devote)	Priorage	Erection	estation contrac	redion fredion			Ranve	Garge	Figlace Industry demoks	Prior App durding	Prior App	vehiola	Gredion	Erection	Charge	Change a balk onle tredson	i
		4	share er	dden	ngpu	3000	led	oser	mopdi	, a	Writher	dan		unopp	a e	Margarets	hepherds well loser	¥	upper		the sh	delp	Wretern	Asi .	and Studies	4	odverborou	yatry	W 19			dden	Arranees	pag	Ded D Messeef	oer	i
	sauppe jepoj	ő	A Ve	8	W	A G	200	80	N D	000	W	W	30	N D	20.0	S. P.	She	80	š	60	or :	oeg Gao	W	per .	Cas	000	Wo	Cast	8 6	A.A.	4	8	AND	ra O	900	000	i
						094																															1
		bey Horres	avo			on Model, W							rtey Place)				2693																		907 **		1
		L Down (Ab)	stran ses Place, D			w Mireo			unc	Dover			Deal(Timps				5 well CT15									b				are, Ash	Lane, Ash	enCTS Z	Citing		D William		1
		n, Whitido	South, My to 1 Mathe	ridden		A, Port Zor			as, Kręsd	Hais Road,	200		e, Broklen,			argaret's at	d, Shepharo					5	ghan			versus, Dos	diron.		8	tage, treel	ottage, kvel	Post, Lydd	StMargine		- 1 Marca	od Whither	1
		-Whitfield Urban Buarsion	nd adjacent	ury Boad, L	d, Wright	омине	RB et, Dover		dos, The L	Road and R.		thau	Owchlan	d, Yangs do		Road, St. N	Porrie Roa		Coffere	190		Sendalch	Breet Win	Auge	tuddel	retre Parts	Woodnes be	id,Wahrer	kreet, Fres 17 01)	elfamCol	odifamic	Carberban	couse Road,	n Road, De	vee, Deal	Sreet, Dow	1
		Philipsid Unit	nd PH, Don don Road as	36 Carbert	d, High Stre	d Road, Ad	Ded CT145 Outh Stre	treet, Dove	tope Bay 20	pacorefletd	H.Wrighan	leadow, Wir	& Sholden	Mrnoraffloa	wer Road, Staple	stion, Reads	fous q 44 E	d, Dower	base, 14 High Street, Windows	n Meadow, Temple Ewell	detdi	of and Solven Street, Sorbeit	r of 67 H gh	e Terrace, E	Post, Esg. 5	fload & fro	Havel	atry stridge Ro	erage, The d	to Great Yr	\$to Great	e Hope Inn.	adin voa	Z Morgeha rchard Mer	N.7High Sa	& 1 Passel ous q Arche	1
		Pase 1A - W	ar of 17 ton	stween 34 & 36 Carberbury Road, Lydden.	OldFärground, High Street, Wingham	Divisirs but danders. 8 Land at CHB CLAC, Fort Zong Willington Nobel, Writted on Serv. Durkot Road, 44h	456 Abert Road, Deal CT14 918 por floor, 1 & 2 Chuch Street, Dover	4135 Stargate Street, Dover	Hope Bay & Hope Bay Budos, The Lass, Magadow	id at corner of Beacondfield Road and Milais Road, Dove	7.8.97AHigh Street, Wrighten	3 Marys M.	tween Deals	d adorring & Barnoral Road, Kings down	b, Lower Ro	and Rice Station, Reach Boad, St. Mergaret's at Ciffe	of The Coach House, 44 Eytho 156 Snargate Street, Dover	Folkestone Road, Dover	then. 16 His	m Meadow.	tar Breet, Sandal ch	ir of and 59	on's Yans, near of 67 High Brees, Wingham	ar of 16 0o	ne Follies, Downs Road, East Studdel	44 Sals bur.	Bidwork	43 Serayna Way Eastry. Arro House, IT Certbridge Boad, Wahrer	zmenh Preston Gerage, The Street, I to at, Berwick Road, Dover CT17079	d Bam, ad	able 8f ods, ad	adjacent to the Hope Inc, Carterbury Road, Lydden CTS, XT	verland Ash verland Ash	and adjusters to 162 Mongeham Road, Deal	Dockson's Pharmacy, Thigh Street, Deal	ti de Cuada Stroet & 1 Passal Breet, Dower and at the Term Hous q Arches Court Roa	1
	olicy Policy No	Steat	Steat	andbe	2 The C	Outon Outon	SAPSA Upper	134135	1821	Separa	- 8	1 6	ž	3	Norten	andre.	Rear of 149.150	137 Folk	FGNCO	3 Make	1 Potta	landres	å	pun	The foll	hear of	Series .	43 Swa	Steat, G	The Blas	96	pur	andre.	Steads	П	П	1
	(y so g) well as the control of the	N G	z z	>	>		z z	z		z	z,	N Y (A33	N SALS		z	z	> 2	k	2	-			N N (A33		z	>	K 1	> 2	2 Z	z	z	z	* *	2 >	L,	2 >	1
	VEBARTTED APPLICATION number typn status (Net Started, UC, CP)	8		22		22	88	38	. 2		22.1	88	13,000 se n n	8	22		23	ð	9	8	20 1		8	3	8 8	8	9 8	14,00000 OP Y Y 14,00000 NG Y N	2 2	20	2	2	14,00013 OF Y	88	2 5	1470078 NS Y N 15,00003 OP Y Y	1
		13/0007	11,00962	14,00,007	140033	140057	13,01021	14,0020	14,00076	14,00001	13,0076	13,009.2	33,00965	14,00363	13,0120	14,0084	15,0109	14,0062	99,000	14,0068	14/00/12	13,01064	14,0030	6000/91	14/00365	13/01115	14,0062	14,00003	14/00/55	14/0105	6010/91	14,00004	14,002.3	14,01267	14,00087	14,00678	ı

TOWARDS 3				Net gain 0 - no arrendment to make assite complide	This is the certainder of hase Illoadeding the SO Let b) hosted glock also he have naturated but as the elevent goal is called on all free is easy indication that the cheekper will construe with the build.			The phasing is red acting the correplations on site and there is every bed cut on that the devel oper as II be leven to (or piece the development within the symmetry.							Las recorded in 15° Sa suvey - no irrendment to make site complete				The owners of Discoury Park. That been conflicted and the phaling has been agreed with there	From the distriction and the state of the st	Net gan of 2 Perefore deduct 1	from total phasing figure (in SYHLS)	devel sper (Wingey Norriss) and	the landowner were unable to reach agreement on the purchase.		The phasing of this site is in accordance with the rate of delivery on site.	Net gain of 1 freedore babact 1 from the total phasing figure (in SHLS)		
An Jeroz Bussus passus and an agent and an agent and agent a		t	Ė			1				t	F					Ħ					Ħ		1						
BE/CECE BARRATE		ŧ	F			1				t								#			#								İ
as/asos grinning										t							Ш												Ì
AE/EEGE grinning 2E/AEGE grinning		+	H		, F	+	+		Н	+			Н		-	₩	Н	+			$^{+}$	$\dashv$	+	$\dashv$			-	H	Ì
EE/CECC Busin44										t																			
12/0005 grissA9 55/1005 grissA9			┢			+	-			٠	+	-				H	Н	+			$^{+}$	$\dashv$	+	$\dashv$			-	H	Ì
CE/SZCZ BANKAS SZ JEFOZ BANKAS					έ.					L							Ш				П			$\neg$					Ì
BX/TGGK grinn/9		+	H	Н	- 2	+	+		Н	۰	+		H			H	H	$^{+}$			$^{+}$	+	+		+			H	
12/3000 Summed or form Summed		-	F		ž.					F						H	Ш	$\blacksquare$	9		H	_	_	$\exists$					
22/9505 Busin46					ŕ					t									£					33					
ES/ESGE Busin44		÷	H		E E	-	-		Н	+			Н			H	Н	-	E E		$^{+}$	-	+	35					Ì
ES/ESSE Business					8														8					8					Ì
02/6105 grins/49		+	H		- 8	+		2		+	+					H	Н		9.		+	+	+	8		22			Ì
61/STCC Superus	9	-4	~			~		1 20		1	1		7	1	Ť		-				- 4	~	1	90 1	1	22	~	1	Ì
construction (Column 5 plus Column T))	- 3	4 0	N	٥	118	~	0 -	- 5	1	0		•	1.6		0 .	00			- 8	~ -	-	~	-	223	-	5	~ -	1	Ì
Total extent units (le No of units remaining on		0 0	۰						00	0			۰	٥	0.0	00	00	0.0					٥				0.0	٥	Ì
No of units lost during the survey (i.e. units	0	0 =	0	-		0	- 4	0 2	0 0	-	0 .		0	1		000	0 =	00	0 0	0 0	00	0	0	00	. 0	5	0 0	0	
nother construction of an area or		4 0	۰	۰	-		-	- 3	1 0 0	۰	•	t	F			000	0 0	00	•	~ 0	"	-	0	228 0 0		- 07	0 4	0	
No of units not started	9	0 0	~	0	0 115	2	0 0	9 5					14	1 0	0 1	0 0			0 500	-	- 0	2	-	3 228	1 1	96 9	7 0		
Net number of units on application (le Column P minus		0 0		_					0 1				1 0	٥		00		0 0				-		0 223			- 0	٥	
No of units permitted on application (gross) No of units lost on application through demolition or			~		8	N		- E	1 0	-		١.,	16	N	-	0 0	-	00	- 8			-	-	1 0		8	~ -	-	
Pile Previously Developed Land or G Greenfield	, a		, id	ğ	2 0	g	ď o	9 8		ğ	g 8		PO.	N.	4	7	П	00	9 8	g 8	2 2	Ď,	0	90			Ø.	0	Ì
eman / eboo bwaWi							9		hipherdovel 8 Shidden	Ī				,			SE Cytome/Shapterduel 0	u	Yery		П	viory							
							& Shido		apherda & Shd d		Set City			Sacom	Ashtone	y at Ciff	Ashtone	SShdd	11 V # 086			1574086	S at GIM	8	W LECON		Attace	8	
	Sardelch	wheld	Brewould	1111	aned	rth Deal	Adde Ded & Shidder	and and	Cyhorne/Shig Middle Ded &	rth Deal	Vargaec	9	orth Deal	Vargance	te Sour/	ston Wrgaret	rome/52	Western Vidde Ded & 5	aton, Elvi	but the	2000	aton, Ev	Marganets at Ciffe	Wahrer Japal to Ferrio	dro.	athed	Padgards To Sourch	apd le Ferne	
gridhon 50	158397 Sar	3 2		1500XD Will	- w		152268 We	15 02.0	149588 EV	23@ No	26,000	* Y	153338 No	4563650	3598.010	DATE PY	8390 UT	15252 Ay	4136 W		1515D Ca	175 00	145062.51	149948 Wu		8230 W	2522 St.	138549 Ca	
Sultres SD	633058 15		63.7566 14	530035 15	9055		630001 14		119 14	12		1 .	63.572 15	536892 14	12 22	31 16	158391 158399 1 148348 148348	15 15	12 20 21		632966 14	631586 14	635718 14	696832 14	637820 15	123 14	610000 14	13	
400 000 000 000			000		- 5			1 630	000 63930	63.2	68377	3	0.35 637	4 636	2 627	000	5 629	623623				8 682	2 635			6 631123	909		
(ed are otherhole	000	0 00	0	00	9	8	0.1285	0 5	000	ŏ	900	5 6	0	17	0	000	0.078	0.048	72.315		000	100	ō	11.49		52	000	0.087	Page 3 of 7
Appn type (ie OL, BM, FL)	NSN	4 4	8	7	ĕ	ď	, we	74	22	2	z i		r,	я	2 1	11	1,1	25	4 6			3	Vie	44		Wes	2.8	fi.	
app Aidx3	27/03/2018	204/201	14,04/2018	17/04/201	712/2018	02/50	12,05,701	#02/50V	ONOGZOB OSCOGZOB	,06/201	906/202	2000	13/07/2018	V7/201	07/20E	11,06/2018	14,06/2018	7/06/2016 8/06/2018	V08/2018	V09/2018	17/09/2018	71072016	710/2016	710/201	10/201	#02/01/	710/201	710/2016	Ì
eteb notabe	-	-	-	-	20 21	-	-	25 25	015 00	110	2			015 15	210				015 01		9.0	015	015	015 00	00 210	21 510	210	015 20	
	27/03/2012	08/04/2	M/O4/201	17/04/20	8004/2	0,05/2	10/26/20	2,05,0	0,00,2015	2/00/2	2006/20	WWW.	10/07/201	5,07/2	2/20/2	11/06/2015	M/06/2015 M/06/2015	17/08/2015 18/08/2015	2,00,2	0,09/2	IV/O9/201	0.710/2	01/10/20	0k/10/2	00/10/2	2/01/21	M/10/2	20/10/201	
uosph29800	ž	pa			mended to and supported to 28 Primary supprising up to surgements, car ann of access off	ces and (partial	you and scale three databed	arpark. p and related (XX8A2 - for the with the		roof	CD) and to	frost use of terns	ands caping	the dwelling			Queel rg	gyland dwelling	of some e existing sook the Sui Geneth) and loking, h some matters	ement windows change of use mark bay		perty at		ns odated risk Avg	e aberations to not first floor	Pichel nei ding to The progress and pichel fi		ohud huke	
	It ensual of It arring Pormisal on DOV/ILQ/DOLII. for the erection of a detached build in receptoraling 6 flats together with the erection of a car port with terrace above (estaing build regio to obriolish and).	orage building into two residential dwellings of dwelling and gazage, creation of whit older acc to windows and reaked location of exceed-	r the enection of two dwellings (a taking dwellin	ed on of a data deed ing (a lating deed ing to be denotified).	Coultie p privipage district the controller of top 1.450 and (previded)  1.153 (controller part of 2.50 and 2.5	Stoney dwellings and construction of whitculars point demoit on of easi ting barry Schildt burgalow, boundary breden ett, and gal	dwellings inclaion for approval of the acons, appearance, utine permission DOV (1,19587) for the erection	Treation of a Maked and head the partipant change of use to a time term park.  To sen not in attention applied also for the cention of To maked maked the participated of maked the participated of the cention of To maked the cention of the cention	dwelling	wendon to single readderstal dwelling wendon of gange to dwelling incorporating a front donner roof	extension and rodigits to the front and rear flactured matters application for the event on discuss home (use class CD) and are consistent of course in subtraction of a consistent consistent of course course on the course of course c	wenion of first and second floor to four flab, c conmercial off to (Uk e Class A?) and ass colated	Errect error is their legs, sealer road, garages, associated parking and lands caping. (est sing buildingto be derrols had).	rred) on of the oldedned the dirigs, a sool ated party and ambitight of curving and landscaped terraces to part below ground dwelling (et outh and west wings to be derively).	Erection of replacement dwelling (sel strig dwelling to be deride had). Front inner a natrid some detached dwelling.	residential da ding. Soueling and condruction of a whicklar acces	is tans lons to easiting stables and barm to fix 8 tate cranversion to simple dwelling, recti on of a obtached dwelling and construction of a vehicular access	Author application (with all matters reserved) for the erection of an attached dwelling, rection of a obtached dwelling.	Author is a bland the part printers for a part of the control force that the part of the p	The control of the co	noose to from eventoon Lanenoed description	wenionisto three self-contained flat (mrpky property at	and we could be partialled in the payons of a partial of the could be partialled by the could be partialled by \$1200000 km and received by the could be partialled by \$1200000 km and the could be partialled by \$1200000 km and the could be partialled by \$1200000 km and the could be partialled by \$1200000 km and the could be partialled by \$1200000 km and the could be partialled by \$1200000 km and the could be partialled by \$1200000 km and the could be partialled by \$120000  km and the could be partialled by \$1200000 km and the coul	redi on of 223 dwel lings (including 66 affordable unity) together with as odated ethol ar acces, our parking lands; aping and open s pacefarmended plans) redi on of a datached dwelling and oreation of whit clair acces and pathing	d deet ing and mod aco or date date access of deet ing and oreat on of whicular access, and with removal of eaciting rear window and insert w (innernded description)	OS PO PARA PARA RATORIA (1 T. 1979A). TO STRANG TO STRANG PARA TO STRANG PARA PARA RATORIA CONTROL STRANG PARA STRANG PARA PARA PARA PARA PARA LISTA PARA STRANG PARA PARA PARA PARA PARA PARA PARA PAR	werson to two 1 of contained fixs	fred on of a datadred dwelling and construction of a whicular acons (a labing pango to be dan ola half) (amended plans)	
	tof Planning P rafing 6 fats to g buildingto be	detacher refreere	attonfo	dade	ringappii rising a r althvohiu fing early see early served fo	wothree in parking datachee	ttensing atem app uant to o	dander atenap eostee 5 resider	deade	o pur e	droodig sters app core for	no and co	d outto	a o olello Yd landoo Olt wings	placeme	famto	gazza	ation (u	district dis	externio externio ethupax roofests on of an	our eard on	so pue as	orqueb	23 duel I 255, Cir p databa	detadre dwelling on windo	sters app you, layou sdrig dills	a and co	shed) (ac	
	seual of 1 orporatr (sing but	dionof.	thre appl Tolehed	dionoli	the plan 20, com rg units, cod ind u bays of r sing, infr	dionof dionof	terrotton terrotto detalipur de dires	puop puop para	dional	n po adini	ansion a aron of	t ground	dionof.	strongs undres An and su	dionof	werson	gratorat	the appl	dion of three application of wision of idential ( satructus aved)	referrod Idoors u stronof- Iconers	nuce of u	hange of use and con- resent)	3 curre to	dionof.	dionof esizing rit eleviti	anders Spears Sing bet	n podici	dionof.	
Instruction2	(s (r	00 00	8.8	ug ug	8333118	200	8238	0 P	ine fine			36 ā 1	Cre (ea	700		П		88	56536556	588587	5 6	6 8 8	-	2 2 2	tro fro	8 6 8 8	- 6 8		İ
	(into	ver motion	unopali		ş		7 5		torne d	-	varbucks	4		Varganee	lenden	Presson St Marganets	A sh Shephards wdl	Verham	de in			A.	Magnets	a sette ferr		5	3	pette ferne	İ
ssauppe lateoid	ž	00	ě	o O	- 8	å	90 00	g 2	oc oc	e e	2 3	3	De	35	6.8	Sti	A SP	A o	8 3	å	9 0	ô	š	8 5	oc oc	ears.	000	ő	İ
	at Hory Gate Wharf Stand Street, Sordwith	Cotage, Old Park Hij, Dover, CTL6 2081	FP G, Victoria Road, M rigs down, CT14 8DY	ard Cottage, El ens Poud, Deal, CT14.900	WHITEGUES I Everlan (bard southeas of Activa Court Road) Whitek, C16.	50 delf float, Deal, CTM 400	grat eq. Lover Millano, Deal, CTM 9A G Trib Sartha bir Rost, What lead	LANGHAN TRIGOS, LOND TON, DOWN, CTL OTT. SAMMER SWINISHED TON TON THE PROMODER OF THE STANDARD COMMENT.	itte atjoining 3 Valley Wew, Wignore Lune, Eythormy, CTIS AV U and Rear of No 7, Charch Lune, Ded, CTIA 9020		gers, Garnelle Road, St. Margaret slavy Doner, CTIS 607	Section Young Three St. Common Via Principal Later Portrop	red occupants to the first the first management of the	Precident, Ung das n Road, St Margaret's at CITTe	wh, short greet, Chlerden, CTJ 198 point Boat, CTJ 709	to Blary, Longovete Polack Presion, CIS. RY D. The Bruddoevy St. Margarets Road, St. Maagaret's Blay, CT15 620,	Nam and Rabbes at Saunders House, Sounders Law, Ads, CTB 3500. and r/o. 28 Exthorn: Road and fronting The Glan, Straphendowed , CTB, THG	a an Avenue North, A yea han CT3 38P rear of White Lodge, Lower Will Larre, Deal, CT14 9MG	1991, Identifier Need, Coper, CT P 930.	he Stand, Walner, CTL& TDK he Stand, Walner, CTL& TDK	The Strates & Charma Wells, York Book, Walnier, CTLA ALD Bench Street, Doder, CTB 134	Noors, 9 High Street, Dover, CT16 10P	Lindley, Staton Road, St. Margaret's-a-Ciffe, Dover, CTB: GTR	and off, Station Road, Walver, CT14 RH LAT You Dov't Road, Capil for tring, CT18 XF	Doctovers LD & THE V FROTES, FROM STOCK, AND LL 13 LDW. And access to 3 Herschell hoad East, Walney, CTI 4 75.0	ses 18 Substrate LA WUE (land south east of Arctins Court foad, WHiffeld (1994) p. sea bronoof Parit)	don Road, Dover, CT17 070	Jarence Road, Capel In Ferne	
	Steat	Opposite at 6	San Pi o,	April Cot	Phase 1, Dernain	Sto A. S	Begges	Stores		2.2	continu	1	Jopon	Upper A	The Art.	O/U o'as	daman dandah	11 Dorn	O soover	2 The s	4A Benc	Upper R	Sheat		Stre	£ĕ	215 ton	9 Claren	
Allocated Site Policy No			L	Ц	Ē	4	L		Ш	L	1	8	Ш				IIII				Щ	4	1	1/14		11-0		Ш	
opper season, y/005 Staffed, UC, US; (it shis a "windfall" application (Y or N)	× 92	2 >	2	× 8	, z	2	2 > > >	> 2	A A	× .	> 1		2	2	2 2	A A	2 2	2 2 2 2 2 2		2 2	e e - e	2	> 9	2 2		2	2 2	× 94	
redmun MOLTACLIPAA GETTIMARR	13V078 M	9 4	94 97		9	2	8 9	2 4	15,0026 NS Y Y 14,0138 NS Y Y	200	0000		11 NS	9	20	10 9	15,000g3 ns n n 15,000g3 cp y y		2 8			- 1	80 E300			n saoc	2 2		
	13,000	14,01018	9800351	15,0024	στορι	15,00,	15,000	00/51	15,000	15,00	18/00	3	14/01211	15,004	15,000	200,51	15,000	15,0032	14,000	02/50	15,006.6	15,000	15,000	140081	15,0006	15,000	15,004	15,0013	ji

161

		GECC bronged baseing clean-book baseing ban clean ba coli baseing ban clean-book baseing ban clean-book baseing		-	Wet gain of I feerfore datact 2 from btal phasing figure (in 5714.9)			+++	from total phasing figure (in SYNLS)		Net figure Otherwicze datact 1 from total phosing figure On	SMLS							Net gan 1 Perefore dedut 1	$\dashv$	Phasing assurgitions reflect current build out rakes which the devel oper waltes for naintain. There are or infrast but use containts to this build out rate containts to this build out rate.	Phasing assure phones reflect current buil d out rakes which the devel oper within to maintain. There are no infrast sucture	constants to the ball out rate				Wet gain Otherefore deduct 1	From tetal phasing figure (n 57965)		Net gin Offerefore dedxt1	from total phasing figure (n smaa)	See main O Beconforce declare 1	from total phasing figure (n.57MS)		
		TE\2ECZ gelearly BE\TECZ gelearly	$^{+}$					H												+								+							
		SE/HEDZ Buyane											H	Ħ	1		Ħ	1							ļ	ļ				L		t			
			1					Ħ	4			F	Ħ	Ħ	1		Ħ	4		1			Ħ	1	Ŧ	ŧ		Ħ		F	Ħ			Ħ	
		TE/DEDZ Buyunud	+			F		Ш	_			F	Ħ	Ħ	1		Ħ	4					H	_	Ŧ	Ŧ		П		F	Ħ	F		H	
		BE\TCOS geleaff QE\RSOS geleaff	Ŧ					111	4			F	H	Ħ	4		Ħ	7		-				4	Ŧ	F				F	Ħ			H	
		SE\REGE grimming TE\REGE grimming	Ŧ						-			F	H	H	-		Ŧ	-						-	Ŧ	F		П		F	H			H	
								Ш									H								ł	-				E					
		EE/EDD Supress											h				i									ı									
		OC/SIDE SUPPLIES		8.61				80 00									Ħ						1 0											1	
		contruction (Column 5 plus Column T)) Phasing, 2017/18		9 11 1					A .	,		-	-	1	7 0	~	- 0	-	۰	~	n n		1 10	-	,					F		0	-	0 1	
		demolished or change of use underway) Total estant units (le No of units remaining on application which are either not started or under	0 0								L		0		0 0			0	0	1 0							L			Ļ.	- 0	0	-		
		Units completed during the survey year No of units lost during the survey (i.e. units	0 11	000	0	٥	0 0	00	0 -	- 0		0 0	0	00		0	0 11	0	-	00	99		0 0	0	0	0 0		00	0 00		0 0	1	0	4 0	
		bahsts fon stinu to old notherstenos sabeu stinu to old	80	* 000	-	0			0.0			- 0	0		8 0	0	- 0	0	0	0 1			0 0	0	4					-	0 1	0	0	1 0	
		(constant)  (constant)	2 0		1 7	4		8 1	-			0 1	1	0 0			Ш	1	1	1 1	Ė		0 0	1	9			1 0			0 1	1 0	0	0 1	
		No of units permitted on application (gross) No of units lost on application through demolition or Permit and units loss forms)	W		+-1	+		+	~		-		H	-	+	- ~	╫	-	-	~ -	F		8 -	+	4	+.	-		+ +	┾-		-	-	-	
		wmin / sobo brail begolverity brained 2 - Greenfield	ď o	D) D)	ğ	0	o 8	ž.	Ď,			g o	'n	ď o	9 0		11	Y.	ğ	NG.	٥		0 00		0	g s	5	ď.,	g g g		g g	PO.	ğ	NO.	
			SQ.	at Offe shore	a hone		4	Ш		uileo.		o at Ciffe			pherdovel	shore	& Shidden			at Office						1900		cough ple Ewell	at Offe			at Ciffe	at Ciffe	Stene	
			oute Hank	t Magnet's tfe 2cc/A	tte 20ur/h	acte	yates	Fad gards reproced	phonon			apd to Fern	vorth	orth Deal regwoodd	Whome/Shi	tte Sou/A	Todale Deut	14.0	Radgards	t Marganet's	Vedar		Yedan	Authors	Antheid	registern registern		Voodvesbor rdden/Ters	Mergant's		ander of	t Mirgaret's	Marganet	own&Per tte Sou/A	
The control of the		gridthon R2	14169 0	16476 51	156641	156605	155100	14506	148258 II	9		188720	1563.5	152356	147920	16063	15251		142605.51	145998 S	1520081		1577@ M	1448CF W	146000 W	148375		15620D A	16602	4103	15088	16674		161822 U	
	platon	Razona ya	631756		802.23	62/0011	630710	630354	637576	enger Cognie		625260			63/271	28/929	63000	630268	630065	610019	tsree		62800	630078	63000	63.091	10000	628622	0300	1000	63051	03/0/0			
	Planning Ap	Application area (ha)	9100		610	1037	700	900	100	8 8		020	600	00131	0.2	950	9000	180	2100	0.42	1.1		0.28	910	032	029		000	010				022	000	
The control of the co	Dear	obbb Yriqes (14 ,MM, CL, RM, FL)	0.8 PA	1480	1 10	) SEC	M DEC	10800	DIST.	7 M		OD FL	14 600	1460	13 600	) Jaco	n n n n	1,600	15 000	13 600	West		DE STORY	D SEC	D D D L	19 80		n do	-	H	OB CL	1400	) Jaco		
THE COLOR OF THE C			20/10/2			20/11/02	27/11/2	06/13/2				2/10/50			27/01/2	10/03/2	12/02/21	1602/2	17,00,71	1982/2	2900/2		2402/2	01/03/10	2/20/20	20000		21,003,2	_	1			13/05/2	18,05/2	
The control of the co		edab molitorica	20/10/201	0/11/201 D/11/201	20/11/201	20/11/201	2011/201	06/12/201 00/12/201	5/12/201	10/11/0	100000	05/01/201	107/10/11	2001/201	100/10/07	X\02/201	10/07/20/1	#\02/201	100/00/0	2002/201	26/02/2011		2402/201	0,00,00,001	05/03/201	04/03/201	100000	21/03/201	0,04/201	100.000	0\05\201 1\05\201	1002/50/0	10/02/301	RADS/201	
The control of the co		noliqitoriid	İ		ktadwed		dreto dires.	e			pa	n, partial			2			-		and find		a) distribution	therwith	hers	thing and	Sugar	g dwelling	Ħ	ž	П					
The control of the co			O B Flats	B, hicorpor d three du ferd bleet on to the re	dors and ad	ng garage a	ioditural bull tached dwe ng leistaing	ters ris ave	shed	lated infrast genelos lon lated infrast e demolishe	andassocial	rat on to ban	n of shighs s	Ш	Oder access	Aer access, c	900	ce unitalities		) Buywed pu	07/00/81 fc	andlandica	welling toget	p for 20 Arc	at keess y be	en Sant de	ore (esisting		dattached dattached proud floor existing gara		d) a vehicular a		d groundfloor	es idential	
The control of the co			rice fill(a)) nete	two dwelling ling, terrace drugs to be o drug external two counties	rearestern	deddell	nion d'agn r of sent de rd landscapi	dflat Ing (alfreat	o be derrole	beeling, rel to outline p lings and rel al dings to b	prugatore	ettre, estre	and erection	94000	Son of vehicu	on of whice to be derroil	demotified demotified	and two offs		lar access ar	astion DOW	oussade	s identist du	overt grap	n of wehicula	anau Auro	g and pin sp		caports and profession of existing g		o demolárses Ing and nes	egudponse	demolithe ffce on the	odaženatom suldingto a	
The control of the co			use from d or to reaso	udding Into tax hed dwe and outbull and ling tax to and associa-	eredion of g to be den	on of a deta	ed sug espe ed sug s baj ed sug s	of-containe tached due	g dwelling t	on of the c listers care threat duel	drg (exitin	adentiat du	radersal di tal duelling	ou of vehicu	ges and cra	g buddings	nape to be	Bu pand p		on of whicu	office appli	yar, scale	arage to a n	and replace	atth creato	by the vilag	rd udreg a k		ath violand conversion sking and la		welling to to tached dwd	as ingle du	welling to be storage to o	gricultural	
The control of the co			d change of r ground fix	of existing by or of exercion by a distriction of the color of the col	al dwellings loutbuilding	worls. or fre erects os (detals)	tal denot to of 1 detach of a sociate	ton of a de	ings (existic	or freereds and E (deta not 73 real	ocietal parl	of barmtone ts and asso	na singen	and orea.	off regulary	ings and ga ping (existin	g and form	t a respect		lings, creat	o yarang	v acons, is	of establing g	Band Brail	stogeter	Brightonpo	8 prope	arroug 1	Controls  Contro		(othing o	of the Spate	To Mary of	fuse of an independent	
The control of the co			ra propose nd and lowe	donversion alde, enetic hing galdin ing outbuild	ee residant	an sociated splication is thiodaraco	errobed deta version par ts, erredion to garage a	for the enx	ached dard	pplication is on Stes A, C or the enette restion of m	ion and ass	Seriolished convention esto caroo	conversion	sed dwelling	stacked dus denot blood and dused to	ached dad tedlandica	ned dwell n	in as easitin	ran	ached dad colahed	å.	ppleation f	and front a	ned dwell in	ed dwelling	ersent due	ed dwell in	hi land bac	red dwelling we detached Inc. attach d flat, and a		red dweb ru for the erac	cocversion	nd dwell ru	he dange o rational des	
The control of the co			son of grou	to rear ato abon of par abon of eath	soning fr	gacons and idinatters a dion of a v	AVDDSZĘGIN of Use, con 3 holi day le d on of shed folle demo	application	nothrode	id reatters a adose land 4/00842 - fo r with the c	nofaburga	of use and fon of stabl	of use and	not a detail	drestobe	nof two det	not a dead	ops to rema	ntersion to	n of two der gs to be der of use to a	diratters a	dratters	of use and stoney side	and a detail	ping not 4 detail	nof angle	nofadead	arolshat) nof a detad	not a ostad not the se enection of eff contains thed;		nof a detad	of use and	of use and	provalfort oxisted ope	
A STATE OF THE PROPERTY OF THE		postaggies postaggies	CORNER	Construction of the constr	Conver	Reserve	Dange Drowide Corners	Change			line	363	Charge	Eredio			Ш	works)	toek	du din	Reav	Ragy	Ourgo a single	Court	credio	Erectio	Eredio	ugh to be d fredto	Credio (proge (reo a s derrole				Checkio	Prior ay and ass	
A STATE OF THE PROPERTY OF THE			MY.	Margaret's piton	odnestone	a de	Ary openhood	unoppi	unopph			pelle ferne	the contract	pport	ephyrd; und	uote	9 9	7	Mic	Margarets	index.		repara	190	MET	unopia.		oodnesboro ver	Margarets		d	Marganets	nth Mil	ner h	
A TOTAL CONTROL OF THE PROPERTY OF THE PROPERT		zauppe letro?	ŏŏ	3/6/6	5 8	8	3 3	o o			T	8 8	8	o G	5 5	3	ő	ŏ	ŏ	Ť			9 3	ŏ	0	0 8	T	% ŏ.	2 2/2	Г	20 8	ä	2	A OC	
A TOTAL CONTROL OF THE PROPERTY OF THE PROPERT									4.070.00	D Preston		eme								, CT15 662	÷	:	rion Hone			VCT16800			Bay,CTIS 6			W.W			
A TOTAL CONTROL OF THE PROPERTY OF THE PROPERT								CT1488U	opposite property	Of Begunsh	1	d Capelile								ets-actif	arion Hora		aw (necsn		×	, North down			Marginets			OPS, CTE			
				1	COLLEGE		12000	nadegaper.	1000	stor, CT3 II		Ower Roa		797		n, CT3 IDR				3. Margar	hirt (North	i	New, CTS S	CT1639P	Delt CT16	pper Street		CIISORO	oweny St.			rgaret's at			
				ne, cris ev	adveton		n, Eastry Cl	7 CSA PY COTE POSIC	14800	e Road, Pro	1	n Park, Ne		Coed, CTA	rds well	rstal, Prests	UCT14973	3.34		geood Rox	raion, Ayles		ra on Aye 1A6	(Whitelett	Hoad, Wh	or House, L		hesboroug sell, CT163	SS, The D		CTISON	Road, 9. N	CISSIV	8 21W	
			7117 6 187	grets a Ci	Powling G		e, Gore Lary	Dover, CT1 ween, Clan	Esdown, C	achor Gro		Offis Carava	U,CT1406	tanley Rose Lang Pingu	ine, Shephe	rand, The Fo	Deat, CTM hPath, Dea	Www.CTL	r, CTD 016	tage, Colling	Allege Expa		Wage Espa apham, CT3	Court Rose	e, Sander d	to The Mac		Board, Wood I, Terriple Ex	reduding 4	,	A THE nesborough	olet, Douer	Methyl	er, CELTSO rsh, Ash, CT	
			Dover, CTIL	vet, 9 Mary vet, Predor	'g Cottages,	Street, Rapid	ingenated.	Crabble Hill, erst and Bill	Ill Poat, IOn	North and Sc		rs. The Street	Hoad, Wo	hurchital, 5 Hangman's	Jan, AMILL	daulders	f100, Church	You head, W	- Board Dow	reprood Cd.	Ayleibura		Street, Wr.	f 20 Archen	февона	to Adjacen		se, Harmrall Implar Road	rear of and		Valne, Wood	Netcourth	Jornan Road	vs, Wednes	
			stury float.	Vir. Hgh Str Vile, The Str	over houle	rdtes, The	Gustfare	hitet & Min	Off, Chalk I	4 Salvatori, P	:	Sandbarg. Eathdola	O good, Dea	decent to C see Cottage,	ALUption No.	Y NUMBER	otherear o	ard, 109 9ar	19 Londor	Ange & Coll	1,01Pat1		HOUSE, High	o the rear o	dorne we	r Carpark S		No.57-9 To	rd Garagos	- Charles	over Road -	Se Bern, Wa	etras, GdF	20, Snargab	
(a) (b) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c		Allocated Site Policy No	8 Mar	Mood Wood	1831	do Orde	i i	The Cr			H	Store	Worth	Steh 99 Box Ta	pur			The Ya	157.8	Ancho	Phase	-	Coach.	dredb	Ske	S forms	H	Sheat	The state of the s	1	Tava	The S	The B	Berna	
2 C C C C C C C C C C C C C C C C C C C		(M no Y) notitalitique "lisiboniw" a sirti si f=l/y bnal nebnag sirti si	2 2	889	- 2	5 z	2 2	2 2	2	2 2	Ė	2 2	e e	W A	> >	2		2	2	2 2			2 Z	>			Ė	2 2	2 2 2	F		N A	2	2 2	
		Apprı status (Not Started, UC, CP)	28	3 2 2			2 2	2 2	3 8	5 15	F	2 3	2	2 2	20	8	86		8	88	8		2 2	22	22	2 1		28	2 2 2	F	5 2	ъ	8		
1 C C C C C C C C C C C C C C C C C C C			15,0082	15,0020	15,00%7	6800/51	15,000.2	15,000	15,0082			15,0000	15,0000	15,0000	15,0008	15/00/81	15,01100	15,01284	221051	1000351	15,01004		15,0086	15,00298	15,01365	14,000.0		1600078	LEGOCO L		16,0028	16,003.0	8200391	16,003.2	

	parent on soon of the parent o	Net gan of 9 ferefore dabat 1	from tetal physing figure (in SYRLS)			Net gan of 0 herefore date; 1 from teal phasing figure (in 50%).					Net gain 1 Peredone deduct 1 from total phasing figure (in 5794.9)		The IRCA are convertly marketing the side with class to fresh non- the STATUT of the web's to free the side with class the class of the the side with copies and with the side with copies and with the side of the side of the side becomes and account forces in a becomes and account forces in the side becomes a side of the side of	Phoning suparaphorometricat current build out raises which the doubt gore was the too make an Thomas was no before an extra cur- Thomas was no before an extra cur- Conscience on the build state are conscience on the build state are						Net loss of 1 threefore deduct 1 from scal phasing figure ??			Net gin 02 Revelore dab.cc.1 from best phasing figure (in SML 4)							Net gan of 2 Perefore debut 1	From Mali philate (gure (n 5744.9)	
	CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  CONTEXT Browney  LOUGHT BROWNEY  LOUGH												**	8													- 1 1					
	The committee of the co	3 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	8 8 00 0 0 00 6 1	0 2 2 0 0 0 2 2				Ш	90. 10 0 10 10 0 0 0 10 10 10 10 10 10 10 1		1 2 0 0 0 2	0 0 0	3 3 5 5	2 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	3 4	0 0 0 7 7 0	0		8 8 0 0 0 0 mm	0 0 0		0 0 0 0 0	0		0 1 0 1 1	0 0	1 0 0 0 1	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 10 10 0 0 0 10 10	2 0 3 0 1	
SEATT FAIRTING TO CO.	Dud executability in principle of the controlling o	005 63627 15120 WILHT POL 2	019 62884 144420 Lydder/Terrple Ewell POL 10	0.12 62/846 157928 Little Scory/Myhone POL 2	0.2 639004 1600006 itte-80ar/le/here PCL 1		0 Mile 60000 15112 Manhana	GUICA 151500 Middle Deal & Shidden GUICA 142005 Tower Hankes	152436 Middle Deal & Shidden 155745 Sandwich	0.53 625629 162838).tde-80ur/ks/herve	0.00 637881 147934 (kngwoodd PCL 2	051 6287% 14120 Capd te Ferre FO. 4	2.236 GGZZTY 1,624/G MANETHEL PT.C. 64	7.5 62.0000 15.000 (september 5.500)	142468 St Bad gards	0.14 G2-6771 157108-Life-Book/Mahtene 5 4	0.01 633032 142566 St Radigands PCs. 1	15746 Sardel di	016 65999 144970 ki Marganet's at Offe PO. 3 0017 657746 15252 from Deal	62856 158300 Little Stour/As home	0.00 6.0033 12000B Little Roar/Mehore PCL 1 0	0.2 G3024 14332 Maxon, thris Varid Procy Ptt. 9	0.00 G3855, 15738 Jite Sou/Netere PCL 1	63-800 15-10-9 Monthle Deal & Syna Gen 0 63-801 1519/26 (salary 0	GORAS 1522D Wednes	orth Deal	of systy where	0.14 (3/962) 1561.3 Little Zour/Minbros 10 0 0.11 (5/31/2) 141.31 Mandery Ehrs V # deBritory 7 0	over Hawlets	0.06 633448 14140' Muston, Dras V a 66 Priory 10	0.015 G3E42 14218 TowerHarket PX. 3	
A CARPAN	The War You had sold under sold u	TOTA METICULAR ACOSS AVVICADES TRUTHS TO THE TOTAL ACOSS AVVICADES TO THE TOTAL ACOSS AVVICADES TO THE TOTAL ACOSS AVVICADES TO THE TOTAL ACOSS AVVICADES TO THE TOTAL ACOSS AVVICADES TO THE TOTAL ACOSS AVVICADES TO THE T	ethicular access and patring. 27/05/2016, 27/05/2029 FL.	27/04/2016 27/04/2019 04	right dwelling house and appropriate an artistic building who an office 27/06/2016 27/06/2019 Ft.	with outer access (entiting DRANGOOM DRANGOOM)	at access, and codated parking represents on the second services of	07/06/2019 FL	21/06/2029 FL	and evention of a trained single and security, and associated g and secusing.	sisted with outer access Zaybe/2016 25/06/2029 FL	and erection of garage than of three buildings 2006/2016 2006/2029 Ft.	or of the bid dealings, broppositions to the dealings, deligation of the dealings, deligation of the dealings, deligation of the dealings,	ion DONOYPUXEL pursuent burt to DON/14/0028 and Skaping scale and naviority in anyzonia	T2000 06,0772016 06,0772030	19 00/2010 010/2010 0	self contained flat, 22/07/2016, 22/07/2019 FL may remain the programment of the programm	deg vio žno. deelings Z <sub>1</sub> 07/2016 Z <sub>2</sub> 07/2016 DA	www.pus, eracon or uno.  dood lease into ino.  28/07/2016 28/07/2019 L.  doctors to The Avenue Sevin 2016 28/07/2019 L.  GAVELZOUR DAVELOUR II.	19/06/2029 FL	22,08(2029 PA 24,08(2029 PA	rage limitating buildings to be Zickel/2016 26/08/2019 Ck.	all developer with a single logary doos, insert on of losary elevation of and rese side two residential deal lings viding boundary wall and a symptomic of a symptomic or a symptomic action of a symptomic or a symptomic or a symptomic or a a symptomic or a sympt	942016 01,0942020 942016 05,0942020	20/2016	29/2016 12/09/2029 FL	cces zyvoyzote zovoyzozen.	3,09/2016 21,09/2029 F. 28,09/2016 23,09/2029 F.	COTANGO COTANGO DA	11/10/2016 11/10/2018 04	11/10/2016 11/10/2019 FL	
	percentage of a financial control of the control of	previous in it.  Execution of a pair of somi obtained there ings and oreation of a whicular access	Errection of ten sensi-obtached dwellings and creation of whicular access and pashing swell. Application of the property of the pashing state of the purpose and paraging to be developed the property of the angle property developed the property of the property benefit to the property of		Change of use and conversion of two existing barns to a single dwelling house and detached gateget, together with the during of use of an existing building into an off co () we close this			Freed on of a debated two storey dwelling associated access and parking OTKA, 2011 Convention of dwelling into a two bedroom if it and is 5 bedroom majoriette MANA, 2011		Conversion of existing redundard building to residential and receive die linked single stoney deed ling to form one dwelling and erect on of a works Ing. and associated an errorability diesely and consistently also for deed ling and our linking a real control physicial outside to deed linking and our linking.	Errection of two obwellings with obtached granges and associated with other access in featuring developing to obredshind;	-	Active against white a mister recovering the received of to be dealing.  In the control and the control and the control and to be dealing.  In the control and	Ris erved natters spoketion pursare to out he application DV/IA/DXR0 pursare to the outside pursare to DV/IA/DXR0 (pursare to DV/IA/DXR0 pursare) DV/IA/DXR0 for approved of 2777 deel lings, scores, landscaping, scale and measures.	ritarnal alterations to fact take the consens on of three stud of its viol two one- bedoor fits to against with the wind between to the redelign the eld strip entrance shot reconfluention of the east refreedration.	Т	П	П	Attended and destruction currential to a support on twe care con or use detached deading change of use and convexion of did dated leave into this that they creation of partier and formation with date access to The Avenue Change of use from a supplementation of partier and on the supplementation of the control of the		Pri or approval application for the charge of use from apric Pri or approval for the change of use of apricultural build n Chalme and cation for the enetion of an deribative com	2 dealings principles on a constitution of the second of t			Credi on of a datached dwelling and oreaton of white dans Oberge of use and convenion of that floor of the to six on	apartments this or approval for the drange of use of apricultural building to dweling house and	sa coaked operational development irreds on of a databased dwelling and girtage and aboration	credition of kin dealings and associated garages, parking and vehicular access freedom a brazina of 7 ms. deelings in freedom a brazina of 7 ms. deelings in the contract of t	And the particular of the part	(paxe so.)	Charge of use and convention into Ino. self-contained its	
	wage proj	ASSET DESCRIPTION	191 and Forge Bungalow , London Poast, Temple Ewell	Alber Tree Cottage, The DMT ahygound, High Street, Wrighten, CT3 180. Minglane and deposit Makeuer CT4 200. Minglane CT4 200.	Street Road, Art, CT3.0W	None Station Road St. Morranet's at Cliffs CTIS SES.	3		Size at, 45 Didahwana, Deut, CT1.65GH Engine Siech and access at Harriff Bridsworle, Harriff Boat, Woodwaloonugh, CT1.5 GD Moodwaloonugh	os and the Former All Saless Church, Church Lans, West Scourmouch, CD 345 (Aves Soc	pingdown	fouten Hougham, CTLS 70P Hougham	PH BINTER DOWN TOUR CHENTHONS	rdon (Phasellic, Adelbare Barrat Homes)		Mregham CD 11.X Meditary CD 11.X Mregham CD 11	SCHITT/TEE Averag Door, CIG 231. Source	Dreich, Cutto Jal. X. uro Farry, Guil Food Road, Sandwich Bay, CTL3 56F Sandwich Sandwich	Dodo & Gafeer House, bing down houd, st. Margaret's at CFFs, CT15 GAV. ST Nargaret's bright not Deal, CT 9 TID.		ANCTE AD.  Cottage, The Fortal Prestor, CTE LOT  Prestor	Werdriel sea Road, Dover, CT17 9TT Dover	w Did bushers, 31 H. ph. Street, Wengiurs, CT3 All	WW, CTIS OH 6		who Maniery, Including, 1-11 Queen Street, Deal, CTM (ET)	Ouriger, Ouget are, Overland Lave, Adv. CTS.2.F Ash. Ouriger, Ouget are, Adv. B. Scion, CTLS SNC.	And Albert Real Dayer Street, AN, CTS 200 Ash Makers Read, Dayer Dayer Street, AN, CTS 200 Doer	Outin Gen Cité AP	tows, C117 95.2	ver, CTIG HU DOME	
	THE STATE OF THE S	SAVORE UC Y T GOMENIA DEAL OF	15/0023 NS Y N Landat 191 and Forge	16/0035 NS Y N Willow Tree Cotago, 7	NS Y IN Whet View Parrs, Cop	1500000 IX V N Official Station Statio	-	2 × 2	15/0027 OF Y Y See a, 45 Delahamat 15/0071 NS Y W Kngine Sheb and acce	16,00003 U.C. Y N (The Wilderness and Th	15,0106 NS Y N Codel III, Victoria Boxe	16,00399 ns y n houtonfam, feditor	15,000 de of ferrer comma	manifolde to the control of the cont	8	15,01201 NG Y N Landadacet to Seast 16,0036 NS Y N Ghachist Sanley R	П	IGACOCOS NO Y N. CONTINUENTAL WIRE	15,VOR9 UC Y N CM5470048 Gaffeet Tococce CP Y N Stereleith Floor Deal	NS Y N	2 2	12,0020 N6 Y N Arribulance Depot, We	14,00000 NS Y W The Claburance, 31 H	2 2	A11 M A 30	O A N	UC Y N The Black B	15/010/3 NS Y N LAZZ Landadoring MITNE 15/010/3 NS Y N LIMBAR Road, Dover	N N	IS,00064 NS Y N 65 February Poud, Dover, CT17 99.2	16,000 UC Y N 18 Sel Bury Road, Do	

	go muser)						New rate of the referended by	from telephasing figure (in STMLS)			Las recorded 16/17 surveybut site complete so nothing to deduc from total phasing figured										Net gain of O therefore deduct 1 from total phasing figure (in SYMLS)	Net gin of O herefore diduct 2 from total phasing figure (in STMLS)		Net box of 2 threefore deduct 3 from total phasing figure (in STNLS)	Net gan of 2 therefore dadact 1	STALS				Net gan of 1 herefore debot 1. from phaing figure (in 57HLS)	Net gain of 0 herefore proports from phasing figure (in SYHLS)	Net gan of 1 therefore obtact 1	from phasing figure (in SYHLS)			┙
	QE/SEDZ puncked passed stem to oth		Ħ		Ė	Ħ			=	H		+	Ħ	#	Ŧ		Ħ		H	H			#		Ŧ	#	#	=		Ħ	#	#	ŧ	#	Ħ	
E	TEL/SEDS galando		H		F	H			=			1	H	7	Ŧ	H			H	H			1		F	+	#			H	7	Ŧ	Ŧ	Ħ	H	
F	SE/SEDZ Bunnya				Æ				4	Н				#	#	Ħ							-		F	1	+		Ħ	H	4	#	#	₽	Ħ	H
E	9E/EECZ Busseyd				ഥ									$\pm$	$\pm$															▤	⇉	#	$\pm$	Щ		士
-	EE/EEGE Busseld		Н	Н	⊬	₩	-	-	-	Н		+	+	+	+	Н			Н		-		4		+	+	+	-	H	Н	+	+	+	₩	Н	+
E	TE/DEDZ BURRUS DE NATUR BURRUS				Æ									#	Ŧ								1		F				Ħ	П	#	Ŧ	Ŧ	Ħ		4
E	6Z/SZOZ Punenja				世								$\blacksquare$	#	士												+		H	Н	1	±	$\pm$	Ш	Н	$\pm$
H	TE\AZOS generile RE\TSOS generile		Н		╙	#	_	_	-	Н		_	$\blacksquare$	+	+	Н	Н		Н	Н			+		+	+	+	4	#	Н	+	+	+	щ	Н	+
E	9E/SZOZ Buyunud				仜									#	I				П				1			1				Ħ	I	#	I	ш		I
-	SC/SZZZ Burning		H	Н	╙	₩	_	_	$\dashv$	Н		+	Н	+	+	Н			Н	+			+		+	+	+	-	$^{+}$	H	+	+	+	₩	Н	+
E	EZ/EZOZ Bujonija		П																				1		I	1			I		_	#		Ħ		
	TZ/DZDZ Buyen <sub>ed</sub>		H			#	-	-	-	H		+	+	-	Ħ	Ħ			H	H			19		۲	+	4	7	Ħ	Ħ	+	#	+-		Ħ	
	OE/SIDE Business		П						6 3	1		-	2	10 10	15 20		4 -		-	, ,		-	10	-	~	+	3	-		~	-		4 4	T	7	
	BI/CIOX Busseld	1		~					_			~		-		-		٠.					1			20,			Ш					14		•
	application which are either not started or under recurrention (Column 5 plus Column 1))	-			ΠĒ	П	-	-			ŭ		1	×	9			-					×			~	2 -			-			7 2	Ш	n	Ĭ
	(Annuapun sen jo süure) to paquijouse	0	00	٥		•	٥	٥	00	٥	-	٥	0 0	-	0 0	0	0 0	0.0		0 0	0 0	0	00		•	-	00	0	000	٥	0	0	0 0	-	٥	- 00
	Chilits completed during the survey year	٥	0 =	٥	•		٥	٥	00	٥	27	0	0 0	۰	0 0	٥	0	9	0	0	0 0	٥	00	0	•	٥	00	00	000	°	۰	۰	0 0	00	٥	00
E	No of units under construction	-	L,	-	H.	4	- 4	- 4	8 0	Ĭ	0		- 4	-	9	H	2 0	0	H	- ~		- 4	2 1		+	0	1 1	-[	#	-	4	+	74 :	#	H	- 0 4
	Column C)	-	-	~	~ -	+	~	+	0 -	-	=	~	- 14	Z	9	+	74 -		+	4 ~	- 0	۰	1		~	~	1.6	-	#	+	-	+	- 2	200	~	0 11
	cyauths of use (gross)	0	0	٥	0	+	-	+	- 0	0	-	٥		-	0 0	0	0 0	- 0		0	-		00	1	+	+	00	0	+	H	+	-		+	0	- 00
ľ	No of units permitted on aplication (gross)	-	+	~	1	۲	**	**	е	-	2	~	- "	z	9 9			٠.	H	~	-	-	19		1	60	14	~	-	*	-	1	7 2	200	ľ	9 11
H	Ward code / name PDL - Previously Developed Land or G - Greenfield	ğ	10.	ğ	g g		g	g	g .	0		ğ		. 0	ğ	9		ğ	0	g o	g g	ğ	00	g .		ď,	ď,	9	g .	ģ	ğ	0	g .	, 8	0	- 00
			arre		ghiory	8	8	difficery	ladon, Ehrs V.d.dSPriory Ide Sour/Mildene	8	dden	3He	o pan	3	seco, Chris ValeBhiory pd le Ferne			dden		ngowell			Water, EnsyldeBriory Widdle Ded & Shidden			dden	dden	8 8	e	3ffe	arre	8	laston, Ehrs V. didBhlory.	Ш	8	жe
			ret's at o		Vancon, Ehris V. diddini it Radigands	or/Wshte	ur/lishte	Ehrsva	Ehrs V.d	te Rou/Miltone	68 85	Megant's at Office	oder/Terple Evel	dder/Tarple Ewel	ChrsV4			idde Deal & Shidder		ver zhorne/Shipherdowell	arries erre		Eves Val	3		ed & Sh	Wildle Ded & Shoden	Little Sour/Ashtone	or year	Marganet's at Office	Margaet's at Office	itle 2cur/Ms hone	Ehrsva	Ш	Utfe Rour/No Hone	A Marganet's at Office salety
		Ayleshar	State	Castle	Markon, St Radig	Otte 30	Utfe 20	Maton	Waston, Urf e 2o	Utfe 80	Widdle	St.Mrrgs	Utfe 80 Lydden/	Lydden/	Meston, Capit le	Pingwoodd	Ayleshare Town & Pier	Widdle D	Auges	Flytome	Cacel le I	MEHI	Waston, Wadde D	North Dea	Whithek	Widdle D	Middle D	Utfe 30	Town & I	St Marga	St Marga	Utfe 80	Waston	Mil HI Sardeld	Utfe 20	St.Merga
	Spirithon SO	153423	141542	141500			157370	141638	141330	16039	152420	145535	155971	145490	141240	147677		152260	155720	14280	11044	151457	151020	153466	14570	15206	152480	159900	141148	164146	144571	155506	141100	15001	158268	15503
E	Spitters 90		633081	632062			3600	3200	631330		1621	_	627011		33000	683831		38715	SELUS	619886		naco	63,000		020029	398.90	15847	620849	31833	63633	69667	_		63000	639267	
H	Application area (ha)	9000	9 5100	9 9000		60	9	9	9 9 9 0	200	0.10		9 200	147	2 8	9 900	900	900	900	015		900	9 9600	610	60	9 910	033 6	9 000	9 510	990	012	_		000	0.15	0.5 6
L	(ty 'WW (to e) edit uddy		00	ď	Ľ	#	4	ď	Ţ	Ĺ		4	$\perp$	4	+				H			ЬĨ	10	6	1	1	Ц	1	ľ	$\mu$	4	4		111		
E	Expiry date Appr hype the OL. RM. FL)	J. GIL	14 60	700.0	14 60	WEG	) ac	) ac	100	N d di	T day	) and	N M	78 61	Ti da	N6 600	A SE	9	1000	OBEL	1 1	ų g	70000	1/00	100	1,000	1000	V COD DA	1 2 2	į	9	100	0 0	000 O.C. 000 F.C.		14 000
		12/10/20	25/11/16	04/11/2019	08/11/2029	06/11/30	11/11/10	11/11/10	16/11/2020	271172	23/11/20	23/11/20	25/11/2020	01/12/202	02/12/20	08/12/2016	18/12/201	15/12/20	15/12/20	22/12/22	27/17/2	13/12/20	04/01/2020	11,01,720	12/01/21	16/01/20	17/01/24	17/01/2020	20/10/22	30/01/2020	03/00/200	03/03/2020	07/02/200	20/20/20 20/20/20	15,02/2020	0002/200/22 22/202/2000
F	edeb notation	72016	72016	04/11/2016	72016	00/11/2016	72016	72016	K/11/2016	72016	72016	-	9 9	-	72016	72016	72016	E/12/2016			72016	,72016	72017	72017	71017	72017	72017	_	72017		_		_	72017	-	
L		2/10	26/10	00/11	00/11	08/11	11/11	11/11	17/11	20/11/2	28/11.	25/11	2/11/201		07127	08/12/2016	102/2301	5/12	15/12/2016	20/12	2/12	20/12	04/01/2017	107/10/11	η,	26,01	17/01	7/01/2017	TOUT	102/10/X	08/00/201		08/00/201		5,02/201	7,002/2012
	vations	fred on of a replacement build refer use as residential institution (Ne Chast Ct) reducing the provision of ancillary coveres accommodation (self-string building to be bernoldered longsthere with all treatment to existing account.   22)	or of a disturbed dwelling and orest on of whicular access rings of use and conversion to a single residential dwelling.	ings of use and convenion to 2 maleoniths, erection of a style storey rain on ton and second sted abends on	dition of a nodestansion to provide two self contained flats  read from blackous to black as in Multiple Cicopaten including insertion of around floor window and four nodilights	or agrovalize the durings of use of agricultural building into 3 dwellings ings of use and convention to two dwellings (1.1.5 bed and 1.14 bed.), works to	one is parting in a recent or downery preventing in prevention of details and string level to details and strong favorable of the following the control of the following the control of the following	yersion of dwell trg into two sdf contained flats provious fromer zue hove. Until brown and has enventille trols studentlist and	construction transition from the property of the proof of	or approval for the change of use of two agricultural buildings into a dwelling trus e	Bernal blon of eals ting dwelling (retrospective) and erection of heavie bags, provision of memoral and acces, associated parking and replacement parking to easible from and lands afring.	on on of the objection due they will not posts are under ing or easing versionary to not develope broughts and proge to be derived into X approval for the change of use from agricultural building to cheek highous eard.	odated operational development. Y approval for the thangs of use front two agricultural buildings into two dwellings	freed on of all has and free storey dwellings, together with as polated access, car parking and land caping to the storey dwellings, together with as polated access, car parking of load of land to link late the erection of a real-derstal care home comprising 6.	associated parking and huming area also not 40 chedings, creation of access, assicuated parking, lands caping and open ce	and natters spakation for the eredion of a detached dwelling (details pursuant, autiting permis son DOV/12/X0728).	or agroval for the drange of use of two agricultural bull drags into two dwellings of on of a obtacked dwelling incorporating an integral garage, formation of access Handscaping	Convenience de abbig gare home to prouble from Tilles, erection of also abony restricted of the ordinary restricted and the service or and first from the ordinary from the development are core; and restricting and any properties of the service of	the application for the encitor of a dearhad dealing (binducing, appearance is also be reserved).	of on of a wige storey building for Cluse comprising four files of on of the obtained durings, aforetoes to a sizing vehicler accoss, driver as, age and or parking.	nc firerchiobon, Jino Juli ette bak ceries and retrospeche appliation for the atl on of a replacement dwellingand detached gange (a läting bungs) on to be solihed and creation of vith cale access	Conversion of existing building from two flats to two deeling houses with a two storey existes ion to 24 (existing existes ons to be demokrach and exection of a fruit floor conservatory to no 22.	The application with an institution reserved for the rendon in all developing associated for the server of the ser	Per recropacitive agglazion for the charge of use and convension to a single cheeling at this let before the art has cented distration. Erred on of 200, sorth-databad cheelings, oredit or it acres and parking (nisking barn	to derrole heath	freed on of 11 dealings, a detached building to one dealing of the code of 15 freed on of 11 dealing to be of the code of 15 freed on of 11 dealings, a detached building the cryositing 5 self cortained filts,	vatruction of vehicular access and associated parking. ed on of a datached dwelling, creation of vehicular access and parking.	or approval for the drange of use from appointural buildings to three residential delings.  All lines	one eign anomine me ene on on in ene energon in en enements par enements en enement.  di on of a detatoried doel for creation of vehicle are core and lands anomine et doel on of a detatoried doel for creation of vehicle are core and lands anome.	rection of he o detached the divigs and creation of access (set sting cheeling to be sore obtained)	Treat on of a data deed dwelling (a stang to be deer oblaved). This among a confession for the channe of use of an action described for to	of Approximations	Change of use to a studio flat and malponete front one of 22 order logogethre walk associated internal access road, pathing, and confer and alteration to eld then with other one or.	Of of program and Metabourous area, ever commence on a three application for the erection of time deselvings (alreations reserved) above for bookselving (internal and transform or by).	thre application (with some matters reserved) for the erection of two detached diegs	rreat on of the detected the direct, orest on of vehicular scores sand associated car- unisting.  The distribution of a distribution between and oreston of associated parking.
	yananggang	fre, ind, sington den	Atargón frei	On Out		Mrgtare Mo	rightm addition	44 (00)	der form	. Prio	Der pros	s june	taple asso		pet ferre spac	Reserved to a	onlegton Prior Gred over and I	o plane	Worth and	5	ele Perre dere	Con.	Down Acc		Nec 101		Deal com Sholden Ered		Down Char		s Gree	Wrigher ded	er Ose	dark One	Ove Ove	St.Margaret's park Eastry Ered
	assrbbe letro?	Non	East Dog	000	90	w	w	80	O O	N,CT32DW Ash	Dea	Str			oo Oo	No.	No	200	West	Shen	90	Dea	wo g	Det	00	20	SPG	and and	000	SER	115	W	Doc	Des	Ash	
		Ske at The Old Court House, Pervers HR, Novington, Dover, CLIS 4LL	Land adjacent to 16 Wests dis East Langdon, CT15 546 45 Gadle Breet, Dower, CT16 3PT	(O Castle Street, Dower, CT16 JP)	A Pricoy Street, Dovey, CT179A A 67 and near of 66. London Road, Dovey, CT17 69P	Apricultural Buildingat Dambridge Farm, Stagle Pool, Wregham, CTS 1UJ	Red Linn Cartestuay Road, Wingham, CT3 188	14 Nort an Breet, Down, CTD' 95	ht 66, felkestone Road, Dover, CTJ 950 If the Oblitationach Muh Street, Worthers, CD: 30.0	Tractor Shed and Hay Barn, Upper Goldstone Farn, Upper Goldstone, Aut, CT3 2D W	and it and land near of \$26-100, Ourth Law, Oak), CTM 90,	Hib Ids, Collingwood Road, St. Marginet's at Giffe, CT15 6EX	Site at Summert eld Farm, ill arnol e Road, illernoole, Sagle, CIS ILD Agriculturi Build reg, Sun Valley Farm, London Road, Temple far et (I I I I I I I I I I I I I I I I I I I	pun	Site roar of 162 Follestone Road, Vale View Road, Dover, CT17 SNP Land south of New Dover Road, Capel-le-ferrer (Savis Herres)	Land Adjoining Remed s, Covernadown Road, Myspadown, CTL4 88F	Names at Hightess, Old Court Hill, Nonington, CT3 316. Land at North Brid, Charred Mew Road, Dover, CT17 977.	Posehust, 182 Outch Park, Dail, CT14.973	Science, Februaries, Worth, CT14 080	Moherton Court, Albran V day Road, Albran, CTD 705 24 Westcourt Lans, Shipherdheel, CTS 797	AS High Street Down, CTG-LEG	22, 24 & 2 AA, MII HIL DRAL CTIA 95 W	Land adjacent to alterners, Folkestone Road, Dover, CTLT 90U. Te Haye and Gross, Geel, CTLE 599.	20 The Marra, Deal, CTM 6WG	Lenagre Court Farm, Lenacre Lane, WHISH of CTL6 3H.	180 Lendon Road, Deal, CTLA SPT	Southern Water Pumpi ngStati on, St Richards Road, Dreil Site at Pegusus, London Road, Sholden, CTL4 DND	Descentant Fam, Descentant, Preston, CT3 JHN sociocosts Tax Soc. Based and Baseds. State CT3 115	Area objects in the road, custrations much custrations, assigns, t. is suc (6.1 Stargate Street, Dovy, CT17 SQC Size Added or The Cottage of Marie and Double More chosen CT14 SQC	Dal Housing 23 St. Marganets Road, St. Margared 18ay, CT15 62.0	Southgale, 17 Grand le Road, 9 Margaret's Bay, CTIS 60 R	Terber Ban, Groduland Farm, Crockburd Hill, Wingburn, CT3.1NY	180 Chreston Street, Dover, CTLT 998 and east of 18.2. Woodnetonach Lene, CRL 100.x	And elik of 18 a, was an as an agent many, case	Land Adjacent to, 49 New Street, Adv, CTS 28H	
L	Affocated Site Policy No		Ц	Ц	4	Ц.	_	_	_	Ш		4	Ш	OWI	3	Ц	Ш		Ц	Ш	1	Ш	4	Ш	L	1	Ц	4	#	Ш	4	4	1	Щ	Ц	(94)
E	(M to Y) noticelity application (Y or M)  (noticelity application)	, z	* *	>	2 2 2 2	je je	>	>	2 2		>	>	2 2	z	z z	>	IGUIZA NG Y N ISUIAS NG Y N	2 2	>	z > > > 2 2	2 2	>	2 2	>		>	2 > > 2	N X SM PORTONS	2 2 2	>	× 92	2 >	2 2	* * *	2	8 2 2 2
F	PERMITTED APPLICATION number Appn status (Not Started, UC, CP)	9	86	16/00/92	84 950001 160000 NS	12	12	12	29	2	8		2 2	2	2 2	8	2 2	85	16,0153 NS	16,0097 76	2 2	2	15,01082 NS 16,01271 NS	9		8	22	2 1	2 2 2	16,01034 PS	16,01285 NS	2	24 601009 16,0091 86	150070 160070 160070 160140	12	00 990001 00 990000 00 99000 00 90000 00  90000 00  90000 00 90000 00 90000 00 90000 00 90000 00 90000 00 900000 00 90000 00 90000 00 90000 00 90000 00 90000 00 90000 00 9000
		8	8 2	8	N 08	181	282	920	1600067	60154	187	6,0101.7	16,0006	15,01.84	15,00225	8	ă â	8 9	H 2	8 8	3 E	95	8 5	020030	#	3	818	200	18 8	1 4	8	591091	8 5		28	982

		_	_	_	, —	_	r	_	_	_	_	_	_		_	_		_	_		_
(manno)							Net gain of 1 therefore distact 1 from total phasing figure (in 5794.5)										Net gan of 2 ferrefore datast 2 from total phasing figure (in 509.5			Reserved neutors application has been application but is not yet. determined (11/2005/k). The applicant is 100 km to Verced to its derment the permit sid on.	
		l					pin of Life bealphas S										an of 2 th total phases is			applied (L) rened (L) rancis (D)	
bestard fon stim to of	_	1	L	L			from total	L					_			+	from to	ŀ	L	heser deter applic rrole	0
9505 broyed beautig stiru to oil		#	t	t				L							Ш	İ		İ			0
BE\TECC galantities ec\tecc galantities		t	t	t				L					_			t		t			0 0 8 0 05 111 111 111 111
TE/SECE British?		Ŧ	F	F												Ŧ		F			05 05
20,9505 grins/4		İ	t	t												t		İ	t		211
9E/EEGE BANNIA		+	╀	ŀ				L					_		_	ļ		ļ	L		2115
Et/ttot Basset		t	t	t				H	Н				H		Н	t		t	H		11511
EE/DEDE BANNAT		I														I					21 211 21 211 211
es/acos grinning os/acos grinning		+	╀	╀				L					_		_	ļ		ļ	L		211 21
BZ/CZOZ Basseyd		t	t	t		_		H	Н	Н	Н	Н	Н		Т	t		t	H		115
TS/2005 British44		Ţ	L	F												Į		I			25, 130
SZ/9202 Bannida		t	t	t				H	Н				H		Н	t		t	H		250 248 185
AS/SSSS grinning		I		F												I		l			8 250
EZ/EZOZ Businya		8	H	H				H							-	ł		ł	H	9	357 538
TE/GEGE Busin44	- 1	8	İ	İ	12			L								İ		İ		91	GD)
97/8102 griss/9 02/8102 griss/9		8		╀	10	-		_		-	-		ó		- 5	ľ	_	ľ	- 20		25, 469
BI/LICE Business		t	t	t			~	t	Н				H	-		t		t	H		5 111 9000
application which are either not started or under construction (Column 5 plus Column T))	-	1	Г	٥	32	~	~	-	~	7	1	~	6	,	10	-	,	2	-	25	90000
demokand or change of use underway)  Total extent units (le No of units remaining on	þ.	ļ	l	0		٠	-	٥	-	٥	۰	٥	0			Ļ	-	L	١.		110
No of units lost during the survey (i.e. units			0		0	0	0	0	0	0	0	0	0	0	0	-	-	0.	0		100
nothern ander construction to off		+	l	0 0	-		~	o	0	0	0	0	0		0	t	-	١	-		4222 387 420
betheir fon zilnu io oli	-	Ī	ľ	٥	2	~	°	ľ	~	7	ľ	~	5	_ °	10	İ	Ľ	ľ	_	E	4222
Net number of units on application (Ne Column 9 minus Column Q)	-	T	ſ	-	×	**	-	-	~	2	-	~	6	-	10	ľ	-	7	**	25	628
change of use (gross)	_	1	٥	0		٥	-	0	٥	٥	٥	٥	o	-	٥	ľ	Ì٦	ř	0	۰	3
No of units permitted on aplication (gross)	:		İ	İ	×	~	~	ľ	~	-	ľ	~	5		10	İ	Ľ	ľ	Ľ	25	1229
PDL - Previously Developed Land or G - Greenfield	-3	1	l,	ď		PO.	ğ		9	Ď.		ğ	10.0	70'		ļ	9				ŀ
, -,000 party	1	8	pand	0.04 633550 146046 KrNingaret's at Ciffe PGL			ulp	l.	L		Te	14168 Maton Dritt ValeBriory	Ì		1,0	l		Ì	1		l
	1	0.00	Paphera	Saton		Wehton	Viddle Deal & Shiddlen	itte Sou/Ashone	Wehters	We have	SACK	31746	L	We have	's as Of	tte SourMethore		Ì	1		l
	-	the contract	st/acco	Argret	- Switch	e Sour/	de Deal	e Sour	e goar)	e 2cur/	Sargaes	ton, th	Jägg guno	e Sour/	Syreams	4080	a	-betch	3	96	ı
gridhor 50		100	440 (47)	OMBSER	15628 Sardeich	198 Utf.	12 Mid	100,259	92 114	158280 Utfle Rour/No Hone	146230 St Margaer's at Office	288 Max		154597 Utte 8cur/Nehtone	100 St. P.	1	000	145 San.	151346 Eastry	1	ł
			1484	1464	1561	1571	1528	0.69951	1555				Ø1191	1546	1463	100	Į š	1555		1460	L
Spitter \$5	41,000	63.000	625254	633856	402 63817	62869 15719 Little Rour/M-hone	610016	62.843	0.03 623687 155958 Jutle Rour/Mihtone	6258.50	63,982	633091	19000	625671	G130 G13615G 14G19R St Norcent's at Ciffo	17,900	461200 141506 Cadle	633541	634684	8328 620040 Le6000 WHEFE	ľ
убарустро выв (уля)	-	100	0.12	900	400	900	8	5100	000	000	000	200	200	000	0.33	000	8	000	0.13	823	t
Pra Natur Pers and gridle - while-		1	L			L	-	Ĺ			_		L		-	ł	-	ļ	┝		╀
Appropriet (No OL. 8M. FL)	H	4	1,50	1400	140	ય	ı i	w a	Vd Q	1/4	wda	130	1,500	3	13 0	24.0	-	1/4	ŏ	ğ	L
atab vies 2	-	27/02/202	01/03/203	01/03/1000	03/03/2000 Ft.	13 000/00/00	06,03/2020	06/03/2020	06/03/2020 PA	10,03/2020	10/03/2000 PA	0002/10/01	0002/10/2	22/03/2020 F1	2403/2020 Ft.	Antonio.	24.004.700.61	703/203	29/03/2000 Ox.	00071000	
Set in notifice and set of the contribution of		+				17.00	-	-				-	13					117 286			
	1000000	77,007,00	02/03/201	01/05/2017	08/03/2017	04/03/2017	00/00/201	102/2020	04/03/2017	10/03/2013	XX03/2017	102/20/08		7,03,2017	26/03/2017	07/20/90	36,016,2017	75,037,20	20/03/2017	G/01/2013	
noitytused		f	ť	ť				۰		,	ŕ	ŕ	ŕ	con	Т	f	t i	ť			t
	Outline application for a misred use cheelegen ent incorporating M2 residential units, (Copyre III Office, 3 Tritopri of M1, 250 paper of D1, and a link resid between A bent Road	l	l	ĺ	eenvel metars application pursuant to cutfi ne application 15,00780 for the cletals of the appearance, landscaping, layout and scale of \$2 the dings with public open space, addocks and car part for allage half.	god ated	rey rear	hi or approval for the change of use from an agricultual building to a cheelinghouse	adental	rredd on of ha o deladned da dings with as sod ated parifing and parifing for No. 41 Ne- arest.	PEDB	70	ĺ	geresis socess tion	on of 30 dealings (2 with air barrs) analton of whicular access, purhay, and mis control landuation.	ļ	42	30,	Authre application (all matters reserved) for the erection of one detailbed and one pai 6 seni-beteached dwell fress, orestoon of associated vehicular access and suith re-	Shari ya rengaga santo fer temana sanda ina aran maki hakibing ceren, carpini gifi hakibah nada kale ceren (dan ili; real aque (dan ili; real aque (dan ili; real aque (dan ili; real aque (dan ili; real aque (dan ili; real aque) (dan ili; r	l
	2 resida Hueen A	l	l	ĺ	more.	onvention of outbuilding to he oresidential dwellings and forestion of associated anticipances.	Shriston of building into two self contained dwellings, erection of altwo stony rear Institution, creation of vehicular crossovers and dhiveways	o a dure.	ri or agrovná for the dhange of use of an agricultural buildingi não two residential se dings	or graves	and in the septional application for the change of use of an agricultural building trious well inglicate.	hange of use and conversion of five floor was a self-contained has bed flat, splacement UPV C-windows/ door and as odated external abarations	ĺ	creds on it is anybe storey rare estims on to fit after conversion into a single read about they excell on of detailed parago-bare and creation of new with cuts races as they provide to be dended heats, and installation of door to front elevation amended description).	end'ssax	and sheet no	hange of use and convention into 4 dwellings (2 má sometres in No. 22 and 2 absorption in No. 24	chi on of a droc seriel detaic had dawlinus and creation of access and partition	Outline application (all matters reserved for the erection of one detached and on of sent-detached dwellings, creation of accounted vehicular access and parifice	Subsective graphic to the control for of a new connect to Achielia Contents, or profit of ITT have been objected and or the control for the co	١
	afrig M	l	55,000%	l	on 15,00. Year wild	dorest	tion of L	U láng t	drigino	xi pue 3	organist	ared to abreats.	Ì	ersion i of rieus or to fro	icolar ac	tosne	tes in N	800,600	doned	correct (Class D n. suppic incorpor rision of diambas	l
	noorpon vd a link	l	Pácular a	340	ppt catt	ng and	6 ered	distrib.	ord but	dparkin	vale or .	sef cont.	salibis	nte conv reation c on of dos	n of with	ratham	14 sone	1thon of	vertout	fanau deglec spusio and pro-	l
	of DL ar		in jour	d dwell	de of 3	at duet.	dwellin	n agrio	apricuts.	1000	d use of	veo a s		ofacility vazallatic	oveafor	erin dia	ngs(2 n	andera	or the ex	udionic cialcan als indu anky an ovisioni frastruc	l
	athre application for a related us e developm Dagni 81 Office, 370 agni of AJ, 280 agni of C	N LOSGIA	fred on of a detached duesting and onestion of whicular access	Ounge of use from holiday lid to no idential dwelling.	anttook tandsc 41	eaderth	wision of building into two self contained dwellings, ered attention, created mysers and diversitys	e froma	e or an	s with a	harge o	Thange of use and conversion of first floor into a self-contained haloba epiac errent UPV C windowy door and associated external abstaclons	hange of use and convension to nine self-contained flats	ge/son ge/son ), and in	rbams).	) from a	4 dwd h	vd fress	notes	the extra tigged stand for the control for the control of the cont	ľ
	seduse of A1, 29	The same	4 tog and	taton	renved nation application pursuant he appearance, landscaping, layout a addocks and car park for village half	o More	self on Air gros	to of us.	enpad	Shirte	or frech	Vator a		earests sedgara olishadi	with car	out po a.	oninto	: had de	person	Audine planet repapal aution for the constront entry, correpting (BY thut, health and so 11 All), and 100 no. 2-5 bed residential or 10 all China Chip provision of learning and comm- fe primary school including early years por frequencies, all a sood actories probleming.	
	TOuges of	to socomed more participations of		Appropri	pleator deaping victoria	adrig t	'rto two Xvertou	Busing or	in dung	ф рэкря	cation it	serveral virdous		fotach fotach be dem	Ings(2)	o dane	onwersk	"H detac	dinat	plication 12-5 bes of hearn nobading sociates	
	Mice, 33	Attenta	deade	efrores	tters app noe, lane, dicar par	of outbo	ulding i.	afforth.	artorth	the order	at apple	- UPVC to		strigle: adjoind diesto l scriptio	thub di	Morth	n No. 2	210. Ser	tation (	ringspi prising 8 1100 no. wisions schoolin 5, all ass wedfor	ı
	pre appli	and the	ou of a	so or us.	vedrat ppearar.	Sorwerston of o	on of by	exoutle.	hiorapprova du dings	gouog P	Yor approvata Se direptouse	geofus.	en po as	redion of a single stor had ling, eredion of de esisting porches to be amended description)	redion of 30 dealings as obliged landscaping	or agreement for the chain	vange of use and convious absorption to No. 26.	conor a	ne appli	neptan 6, cont 3); and 1C3) po rinay s rinay s	
1080381385	00th	Trees.		Chang		con	DA-66 estare	Price	hito	Street	a	Chan	Chan	durd durd (est st (arner		H	Own	ched			1
1		l	hephyde well	Eastlangdon		e			Ш		uopauryseg		ĺ	ooquegous	Cast Landon			I	Sred Mongehan		l
	L	O Company	Shephar	testan	Worth	Wrighter	pa q	aptras	Staple	5	Sagtan	эмор	JIPO D	3oodne	Sastan	OUDOU	DOME	Worth	Sreat	Jose	
zembbe letro9	Γ.	ľ	ľ	ľ		Ĺ	Ľ	ĺ		ľ	ľ		ĺ		ľ	ľ		ľ	Γ		Ĭ
		l	l	ĺ				١	Ш				Ì			ĺ	1	Ì	1	Addition (Across, (led to ead of sorded) lead and onthe ect of legitester flood).	l
		l	l	ĺ				101	Ш				Ì			ĺ	1	Ì	1	day).	l
		l	l	ĺ				14 CT3.5		CT3.288	R		Ì			ĺ	1	Ì	1404	th west	gras.
		Ļ	Ļ	4%				drys pe	CISE	34 A8 h	CTISS		Ì	73.1%		ĺ	1	10	am, CD	and nor.	of the
	8	11410	120	on cus		3		Swer Rox	q Suple	New Stre	angdon			Spine, C	92	×		Worth, CTM 001	Morael	P Post	a tream
	-	, and		ttago		en,cra		Wey, Le	Surrect.	976.	1 Cast L		V05 LTL:	Joodve	CIISS	W CTR		Worth	Greek	Sandari	A treat
	-	e Does	Shepha	cet, tas	CTAGO	(Wings	>	To 8 No.	le fload,	% acces	on ua,		DOMY, L	es Hill.	anedon	Part of	3	te Road	mtan	18	i byte ffu
		The fle	W Road	The Sw	Worth,	the Roard,	738 SEV	len Cert	Barris of	photographic	am, Sol	9100		4, Sadd	o fast t	remont an	CTIGIE	25,3003	HE, Che	(pad to	nemedo
	-	of real	downline	te Farre,	Street, 1	44, 810	Deal	out Gard	dfam.	19 8 41	Vanor Fa	er,CT16		Cottage	Wester	Tr. Dee	Done		e Cotto	tuge.	100 000
		WOL.	v, Masc	68,589	ey, The	Outfar	warse,	4 Layes	merfield	reards	Solton	ret, Down		Corner	1 Side. V	Non Fast	Strone	-£ to Ma	*to A B	tantito	ľ
		and editors were used a reserving the procedure CTA Dis	Dene Cottage, Meadow View Road Shepherds well, CTE-793.	Old Stables, East Side Parry, The Street, Bust Langdon, CTLS Sal	18mile	Dambridge Glet Farm, Staple Road, Wingham, CTB LLU	2 Ordand Averse, Deal, CTM 98W	Potting Shed, Laybam Ganden Centre & Plansery, Lower Road, Stapin, CT3 LLH	arn at Surr merfield Fare, Barns ole Road, Barnsol q, Steple, CT3 & D	and to the rear of 39 & 41 ind od ng at oes strip, New Street, Ash, CT3 28H	Call House Soloon Marror Farm, Soloon Lane East Langdon, CT15 518	Biggin Street, Dover, CT16 180	YOREAH OUSE, Waterloo Crescers, Dover, CTL7 99W	& 2 North Corner Cottagos, Saddles HB, Goodna tone, CT3 119	at West	Month Deponding Decompany Deponded	2004 Custo Street, Doors, CT161PW	and adapters to Manifelrids, Judice Board.	and adjacent to Also Cattage, Cherry Lane, Great Mongeham, CT14 046	Weffeld Urban I	ı
vinocesso gen bojick yo		100	Direct		WOYGE (6) My Nursery, The Street, Worth, CT14 COD	Dar.	22.0	Potts	Darm	pun	Cali	rain c	prote	182			200	pur			
Any one native and history		1	L		WOK	L		L	Ц		L	L	Ļ	$\vdash$	PEVI	4	L	ļ	1487	Ē	1
(M so Y) noblesigge "Eelbriw" e sirb si fahr houf nahega sirb si	H	1	A A 54	A 7	7 ×	>	- 2	A.	>	2	2	2	M A	- 2	N N SN	1		٨	z z	2 >	t
PERMITTED ARRESTATION number Appn status (Not Started, UC, CP)	,		92	ô	76		- 8	92	20	22	22	22	94	8		П		Г	2		L
		1	L.	L		1							1					1	1		1
	9	0000	110	0.0	118	11463	1483	6000	900	1135	1427	2000		200	9300.	11.86	000	91111	900	1001	
	90.70	CHUANT	501091	16/01/01	16/01361	16,01463	16,0143	60000/41	17/00/09	16,01385	16,0147	17,00005	90010/91	17/00014	16,0000	160136	17,00062	61110/91	17,00063	1001001	L

1067

### Notes on permissions that involve losses of dwellings

The spreadsheet shows that the planning permissions include the loss of 62 dwellings in total. The phasing of each permission is, however, based on the gross number of dwellings permitted. Losses are accounted for in the following way:

- Those permissions that have been implemented in the monitoring year record losses and gains and the net outcome is used in the overall total of completions (8 dwellings involve 8 applications (11/00127, 12/00329, 14/00190, 14/00432, 14/00913, 15/00164, 15/00502, 15/01167).
- Permissions which involve a net loss of dwellings but have yet to be implemented are phased as a negative number (3 permissions involving a net loss of 5 dwellings - 14/00182, 14/00157 & 16/00743)
- The remaining permissions which involve a net gain but have yet to be implemented are phased using the gross number of dwellings permitted in order that this will tally with on-the-ground completions. This involves 49 dwellings of which 45 have been phased within the 5 year period and 4 dwellings phased beyond that. In order to account for phased losses 45 dwellings are deducted from the gross 5 year supply of 2,136 to give a net total of 2,091. It is this figure that is used in the 5 year land supply calculation.

### 145

### **Appendix 5 Infrastructure Delivery Table**

Table 5.1

Infrastructure Type	Infrastructure Required	Broad Timing	Comment
Transport	Terminal 2 - Dover Western Docks Ferry Terminal (Port of Dover Masterplan)	2006-2011 2011-2016 2016-2021 2021-2026	A Harbour Revision Order was granted for Terminal 2 in November 2011 and work on the construction of the signalisation of junctions has been completed.
Transport (cont)	Package of sustainable transport measures for Dover (identified in Dover Transport Strategy)	2006-2011 2011-2016 2016-2021 2021-2026	Dover District Council, working in partnership with KCC Highways and Highways England have commissioned WSP/Parsons Brinckerhoff to update the 2007 Dover Transportation Study. Part of this commission involves reviewing and updating the Dover Transportation Strategy and using the updated Model to test a number of interventions that have been suggested by a range of partners.
	Dover town centre to Whitfield express bus link (Dover Transport Strategy)	2006-2011 2011-2016 2016-2021	Agreement has now been reached with the owners of WCBP for the

Infrastructure Type	Infrastructure Required	Broad Timing	Comment
		2021-2026	ability to call on a BRT route through the WCBP. A Marginal Growth bid has been submitted to the HCA for the BRT bridge across the A2 and a link through the WCBP
Transport (cont)	Identification of access arrangements into Whitfield from A2 and A256	2006-2011  2011-2016  2016-2021  2021-2026	Outline planning permission has been granted for Phase 1 (1,400 dwellings) and a reserved matters application has been granted for 90 units.  Construction of a roundabout on the
Affordable Housing	Provision of forms of non-market housing - the Regional Spatial Strategy seeks 30% of total housing completions to be affordable. This equates to at least 3,030 affordable homes by 2026 and 4,200 in relation to the Strategy's total provision of 14,000 homes. (see also the Strategic Housing Market Assessment)	2006-2011 2011-2016 2016-2021 2021-2026	During the monitoring period of 2015/16, 185 affordable housing units were completed. These units were completed throughout the District.
Education	New secondary school facilities in Dover and Deal	2006-2011 2011-2016 2016-2021	Construction of new facilities at the Dover Christchurch Academy has been completed.

Infrastructure Type	Infrastructure Required	Broad Timing	Comment
		2021-2026	Permission for a new teaching block and sports hall at Castle Community College in Deal was granted in January 2016.
	Primary School provision	2006-2011 2011-2016 2016-2021 2021-2026	Phases 1 and 1a at Whitfield include 2 2FE primary schools.
Health	Replacement facility for Buckland Hospital, Dover (PCT/Hospital Trust programme)	2006-2011 2011-2016 2016-2021 2021-2026	The new Community Hospital in Coombe Valley opened in June 2016.
	Two/ three new general practitioner based facilities in Dover (PCT advice 2008).	2006-2011 2011-2016 2016-2021 2021-2026	There has been a resolution to grant planning permission for a new Health Care facility in the Village Centre as part of the Whitfield urban expansion.
Social Infrastructure	Replacement indoor sport and recreation facility, Dover	2006-2011  2011-2016  2016-2021  2021-2026	Indoor Sports Facility Strategy was adopted in July 2016. Construction is currently underway at Whitfield for a new District Leisure Centre.

Infrastructure Type	Infrastructure Required	Broad Timing	Comment
Туре	Indoor sports facility at Aylesham (District Sport and Recreation Strategy 2008)	2006-2011 2011-2016 2016-2021 2021-2026	Phase 1 of the Aylesham Welfare Leisure Centre opened in October 2011. Phase II, the indoor sports facility, will be funded via development contributions once a significant of number of dwellings are occupied in the Aylesham expansion area.
Green Infrastructure	Wetland nature reserve - Worth Minnis (Regional Spatial Strategy Policy EKA7)	2006-2011 2011-2016 2016-2021 2021-2026	Planning permission (DOV/09/00780) was granted on 10/2014 for change of use from agriculture to nature reserve for 94.7Ha at Willow Farm, Worth; Planning permisson granted (DOV/09/00780) for change of use from agriculture to nature reserve for 113.4 Ha at Minnis Farm, Worth.  Work is currently ongoing on these projects.
	Improve condition of AONB, especially chalk grassland (Kent Wildlife Habitat Survey 2003 and	2006-2011 2011-2016	Up on the Downs has created, restored and improved 175ha of

Infrastructure Type	Infrastructure Required	Broad Timing	Comment
	Kent Downs AONB Management Plan)	2016-2021 2021-2026	chalk grassland habitat for the benefit of wildlife and people within and adjacent to the AONB, including the creation of two new nature reserves .  Kearnsey Parks HLF project is underway, which includes plans to restore about 0.5ha of chalk grassland.
	Improve condition of Kingsdown to Walmer Local Wildlife Site (Kent Area Agreement 2008)	2006-2011 2011-2016 2016-2021 2021-2026	Management plan developed, but lacks local support. Local progress being undertaken in discharge of a unilateral undertaking linked to planning permission DOV/12/00770.
	Develop Green Infrastructure Framework	2006-2011 2011-2016 2016-2021 2021-2026	The Green Infrastructure Strategy is being updated as part of the Local Plan Review.
Utility Services	Water supply (Water Cycle Study 2008)	2006-2011 2011-2016 2016-2021	Work is ongoing with Affinity Water to determine how Whitfield Urban

Infrastructure Type	Infrastructure Required	Broad Timing	Comment
		2021-2026	Extension (WUE) will be supplied with water.
	Waste water system (Water Cycle Study 2008)	2006-2011 2011-2016 2016-2021 2021-2026	The issue of waste water services for the WUE is subject to public enquiry.
	Gas mains	2006-2011 2011-2016 2016-2021 2021-2026	The planning applications for Phase 1 and 1a at Whitfield include gas main reinforcement works to ensure supplies to 2,600 dwellings
	Electricity supply (EDF Energy Assessment 2008)	2006-2011 2011-2016 2016-2021 2021-2026	The planning applications for Phase 1 and 1a at Whitfield include works to an existing substation which would support some 3,000 dwellings
Flood Defences	New flood defence system required from Sandwich to Pegwell Bay	2006-2011  2011-2016  2016-2021  2021-2026	Sandwich flood defences were completed during the summer of 2015. In March and April 2016 the Kingsdown sea defence scheme was implemented.

Subject: RIVER DOUR ENHANCEMENT WORK AND REPAIRS TO

**DOLPHIN HOUSE GARAGES** 

Meeting and Date: Cabinet – 4 December 2017

Report of: Roger Walton, Director of Environment and Corporate Assets

Portfolio Holder: Councillor Trevor Bartlett, Portfolio Holder for Property

**Management and Environmental Health** 

Decision Type: Key Decision

Classification: Unrestricted

**Purpose of the report:** To consider the business case to carry out riverside enhancement

works and repairs to Dolphin House garages.

**Recommendation:** To approve the business case to carry out riverside enhancement

works and repairs to Dolphin House garages.

### 1. Summary

1.1 The St James's retail and leisure development is due for completion in February 2018. At its westerly boundary the St James's development abuts a very unsightly stretch of the river Dour and the Council-owned Dolphin House garages which are in a very dilapidated condition.

- 1.2 This very unpleasant scene will be in full view to all those who use Flying Horse Lane to access the St James's development, which is one of the primary routes to and from the town centre into St James's.
- 1.3 This report provides the business case to carry out improvements to this stretch of the river Dour and also to carry out repairs to the Dolphin House garages.
- 1.4 It is anticipated that this work will cost £90,000.

### 2. Background

- 2.1 Dolphin House was purchased by Dover District Council on 2 August 2007 for regeneration purposes, including the possibility of enabling connections from the St James's development through to the Market Square. Constructed in the 1950s, the property consists of 6 commercial units leased by DDC as shops/cafeterias, residential apartments let either on long leases with 60 years remaining or those which have had their leases extended and have 150 years remaining, and 15 garages let on weekly tenancies.
- 2.2 The option to demolish or partially demolish the garages in order to create a direct link into the St James's development has proven to be cost prohibitive and is no longer being considered.
- 2.3 The river Dour runs immediately behind the Dolphin House garages and past Flying Horse Lane which will be one of the primary routes from the town into St James's.

Dover District Council 174

- 2.4 It has been recognized over a number of years that the garages were in need of major repair but, because there was a possibility of the buildings being demolished to form access routes, this has not happened.
- 2.5 Historically the rear of Dolphin House has been a little frequented area with very little amenity value; over the past 40 years or so the multi-storey car park (now demolished) has dominated the streetscape. The development in St James's fundamentally changes the importance of this area.
- 2.6 The proposed enhancement work to improve the visual amenity of this area includes removing the overgrown vegetation from the river banks/garage walls and replacing the riverside railings with railings more aesthetically appropriate. The work will also entail smartening up the garages, for example, carrying out essential repairs such as providing a new roof covering, new fascia, new rainwater goods, repairs to windows and cleaning the brick walls.
- 2.7 It is anticipated that the cost of this work will be £90,000. This work cannot be recharged to either the residents or commercial tenants of Dolphin House as the garages are in a separate block which has always been the Landlord's (now Dover District Council's) responsibility to maintain.
- 2.8 Originally it was proposed to carry out a more ambitious scheme to enhance the visual amenity in this location. This included the construction of a tensile canopy over the existing flat roofed garages with it projecting over the river with down-lighters situated in the soffit. The budget set aside in the Medium-Term Financial Plan (MTFP) for this is £230,000.
- 2.9 This scheme will no longer be carried out as, apart from the obvious cost saving, carrying out a more moderate scheme will give the Council flexibility as to the long term future of the garages.
- 2.10 Although the cost of the work referred to in this report will be approximately £90,000, it is recommended that the full £230,000 set aside in the MTFP should be released. This is necessary as, although the proposed works will have an immediate impact on improving the visual amenity of this area, it is likely that further enhancements will be necessary in the vicinity. This could be to improve the appearance of the rear elevation of Dolphin House and/or to improve public realm land on the peripheries of the St James's development such as the river Dour in Mill Lane which is only a few metres away from Dolphin House.

### 3. Identification of Options

- 3.1 Option 1. Is to do nothing. This is not recommended as the garages are in disrepair and delaying the work or not carrying out these repairs could lead to further deterioration. The remedial works to the garages and the riverbanks will inevitably have to be carried out anyway. If not changed for a new design the existing riverside railings will not be in keeping with the surrounding street furniture and adjacent new buildings.
- 3.2 Option 2. Undertaking the works would ensure that the garages remain watertight and will be seen to be well maintained and cared for. The proposed works will greatly improve the appearance of this area and will be seen by all those who use Flying Horse Lane to access St James's, and may even encourage people to venture from St James's into town.

### 4. Resource Implications

It is intended to fund the cost of the works from the £230,000 provision included in the current Medium-Term Financial Plan.

### 5. Corporate Implications

- 5.1 Comment from the Section 151 Officer: Accountancy has been consulted and has no further comment to add. (KW)
- 5.2 Comment from the Solicitor to the Council: The Solicitor to the Council has been consulted in the preparation of this report and has no further comments to make.
- 5.3 Comment from the Equalities Officer: 'This report does not specifically highlight any equalities implications, however in discharging their responsibilities members are required to comply with the public sector duty as set out in section 149 of the Equality Act 2010 http://www.legislation.gov.uk/uk/ukpga/2010/15 '

### 6. Appendices

Appendix 1 - Location Map and Photos

### 7. Background Papers

Property Services' files


Contact Officer: Frank Thompson, Asset Manager

Frank.thompson@dover.gov.uk

Ext 42237

### Appendix 1

# RIVER DOUR ENHANCEMENT WORK AND REPAIRS TO DOLPHIN HOUSE GARAGES LOCATION MAP AND PHOTOS







View from Dolphin House Rear Yard Access Bridge



Dolphin House Rear Yard Bridge

Subject: OVERNIGHT OPENING OF DEAL PIER

Meeting and Date: Cabinet – 4 December 2017

Report of: Roger Walton, Director of Environment and Corporate Assets

Portfolio Holder: Councillor Trevor Bartlett, Portfolio Holder for Property

**Management and Environmental Health** 

Decision Type: Non-Key

Classification: Unrestricted

**Purpose of the report:** To reduce overnight opening of Deal Pier.

**Recommendation:** To approve a reduction in overnight opening at Deal Pier to once

a month, from April to November.

### 1. Summary

1.1 Overnight opening occurs on Deal Pier each Saturday night/Sunday morning (00.00hrs – 08.00hrs) for the summer timetable, between April and November. The drivers for reviewing this service include low usage and income figures and staff challenges in covering these hours.

- 1.2 The income generated by the overnight opening has been analysed and this includes tickets that can be purchased in advance of 00.00hrs. The findings demonstrate that current arrangements are not financially viable.
- 1.3 Over the past year it has also been challenging to staff the overnight opening and this has resulted in six unplanned closures in 2017. Recruitment of casuals is now underway to help address this issue but given the nature of casual working, the risk of not covering the overnight opening is reduced but not removed under current staffing arrangements as there is no contractual obligation for casuals to accept a shift.
- 1.4 Formal staff consultation was undertaken given the potential impact on employment contracts. Stakeholder engagement was also undertaken inviting clubs, retail units, town and parish councils to comment. Feedback from stakeholders indicated a desire to retain overnight opening. Please see appendix one for more detail.
- 1.5 Although the Pier can be hired overnight as well as during the daytime, the proposal, taking account of the finances, the challenges with staffing and stakeholder feedback is to reduce overnight opening to once a month from April to November. The proposal also considers the approved future investment at Deal Pier that will potentially attract more users and bring improvements to services and facilities it offers with better promotion of angling on our website.

### 2. Background and Introduction

2.1 The pier is a significant landmark and public amenity visited by many thousands of tourists and locals. It provides pleasant walking with a café restaurant at the pier end offering spectacular panoramic views of the coastline and channel at no charge for entry. The location has more recently been used by the film industry with productions such as Liar and the Tunnel featuring many iconic scenes on and around the pier.

Dover District Council 179

- 2.2 The pier is internationally recognised as an angling venue and has facilitated national and local fishing competitions. Sport England rank angling the 16th highest participation sport in England in terms of weekly participation. Angling contributes to preventative and restorative health and well-being. It is a means by which people access natural environments, peace and quiet and de-stress, lessening the likelihood of mental ill health. It is regularly used by the local angling community and is frequented by anglers travelling from outside the district. It can be hired for overnight fishing a cost of £200. The Deal & Walmer Sea Angling Club operate from the cabin on the lower deck. There are also two retail outlets, a fishing tackle shop and a tourist shop at either side of the entrance.
- 2.3 At Cabinet's meeting in November Members approved the business case for expenditure of £587,500 to undertake essential works to the pier. This will also help to bring about visual improvements in particular with proposed seating and stem surface refurbishment. It will potentially attract even more users.
- 2.4 The public opening times for the pier change from Summer (April to November) to Winter (December to March) timetables. The pier can be hired privately at anytime for events which include fishing or filming.

2	2.5		Summer	Winter
		Monday to Thursday	08.00hrs - 22.00hrs.	08.00hrs -18.00hrs
		Friday	08.00hrs – 24.00hrs	08.00hrs – 18.00hrs
		Saturday	Overnight open	Overnight closed
		Sunday	08.00hrs – 22.00hrs	08.00hrs – 18.00hrs

- 2.6 The pier attendant mans the pier during opening hours. Day to day operational duties include helping to ensure safety of public, regulating vehicle access, issuing fishing tickets, taking requests for fishing or film hire, keeping it clean and tidy, reporting maintenance defects, answering visitor/tourists queries and general administration including Fish of the Month competition.
- 2.7 During the early summer of 2017, various medium term sick leave among employees resulted in sustained difficulties in covering the overnight shift (Saturday night into Sunday morning) and led to the pier closing overnight on six occasions. Recruitment of casuals is now complete to help address this issue however there is no contractual obligation for casuals to accept a shift and the risk of not staffing overnight remains.
- 2.8 The business case for the overnight opening has recently been reviewed. The average income for overnight periods, which includes combined day/night and overnight tickets between 01/04/2016 and 31/03/2017 amounts to £45.07. The total average cost to the council is £116.33, demonstrating that retaining current overnight opening arrangements is not financially viable. Income and usage during the overnight period remains low during the current calendar year.
- 2.9 Consideration to the ceasing of overnight opening involved formal staff consultation undertaken in consultation with EKHR and the Union, given the impact on employment contracts. Feedback from this exercise indicated that staff were generally accepting of the changes of overnight opening arrangements on their contracts and suggested some improvements that could be introduced to the service. Stakeholder engagement was also undertaken inviting clubs, retail units, town and

parish councils to comment. A total of four formal responses were received and were not in favour of ceasing overnight opening and expressed concern at this proposal. See appendix one for more detail.

### 3. Identification of Options

- 3.1 **Option 1:** To retain existing overnight opening.
- 3.2 **Option 2:** To cease overnight opening.
- 3.3 **Option 3**: To reduce overnight opening to once a month from April to November.

### 4. Evaluation of Options

- 4.1 Option one to retain existing overnight fishing is not recommended. The records of fishing income and usage levels for overnight opening are significantly low. It is not financially viable and given staffing challenges to cover this period under current arrangements it is not preferred.
- 4.2 Option two to cease overnight opening is not recommended. The pier is very high profile among the local community and people outside the district. Particularly following recent Member approval to proceed with significant investment in the Pier over the coming year which will undoubtedly attract more users. Although the pier can continue to be hired during this period by parties or groups at a cost of £200, this is not an affordable route for the smaller pairs or groups of sea anglers for overnight usage. More affordable prices will encourage more frequent usage with improved promotion. Stakeholder consultation indicated they were not in favour, this option would see the council face significant public criticism and is not preferred.
- 4.3 Option three to reduce overnight opening to once a month from April to November is recommended. This option is a reasonable comprise that seeks to facilitate overnight fishing once a month. With the forthcoming investment proposals that will involve continued engagement with sea angling clubs, a once a month overnight opening will potentially see growth in usage and income. Better promotion will also help to attract significantly more users by way of improving the DDC website. This includes highlighting the overnight opening dates, the costs, promoting the health benefits & well-being angling can offer and communicating these changes to Sea Angling Clubs and others to share and promote the service. The service would be more affordable by individuals or smaller groups of sea anglers and encourage more frequent fishing in contrast to hiring the pier at a cost. It would help to reduce public criticism and to alleviate concerns from stakeholders. The changes to staff contracts would see this option covered only by contracted staff in contrast to current staffing arrangements.

### 5. **Resource Implications**

- 5.1 The average income for the overnight periods, which includes combined evening/overnight tickets between 01/04/2016 and 31/03/2017 amounts to £45.07 per overnight period.
- 5.2 The basic hourly rate including national insurance and superannuation for staff is £12.34, equating to a total of £98.72 for overnight opening. Average utility costs equate to £17.61. The total average overnight cost is £116.33.

### 6. Corporate Implications

- 6.1 Comment from the Section 151 Officer: Accountancy has been consulted and has no further comments to add. (DL)
- 6.2 Comment from the Solicitor to the Council: The Solicitor to the Council has been consulted in the preparation of this report and has no further comments to make.
- 6.3 Comment from the Equalities Officer: This report does not specifically highlight any equalities implications, however in discharging their responsibilities members are required to comply the public sector duty as set out in section 149 of the Equality Act 2010 <a href="http://www.legislation.gov.uk/ukpga/2010/15">http://www.legislation.gov.uk/ukpga/2010/15</a>
- 6.4 Other Officers (as appropriate):

### 7. Appendices

Appendix 1 – Summary of Consultation & Engagement Exercise

8. **Background Papers** 

Contact Officer: Laura Corby Extn 2448

### **Appendix 1**

# Summary of Consultation & Engagement on Overnight Fishing at Deal Pier

**Subject:** Sunday 00.00hrs - 08.00hrs - To cease overnight fishing at Deal Pier

**Staff consultation:** 11 July – 10 August 2017

Stakeholder engagement: 13 July – 27 July 2017

### Methodology:

Staff consultation was undertaken with support from EKHR and followed DDC policy and guidance. The purpose was to consult on the impact of ceasing overnight fishing (every Sunday morning 00.00hrs to 08.00hrs) during the summer timetable from April to November. on employee contracts. This involved consulting with a total of five employees.

Stakeholder engagement was undertaken by email. This involved contacting seven organisations or clubs connected to the Pier and are listed below:-

Deal & Walmer Sea Angling Club
Deal 1919 Sea Angling Club
Channel Angling Tackle Shop
Ward Councillors through Dover Town Council
Ward Councillors Walmer Parish Council
Jasin's Restaurant on Deal Pier
Ice Cream Shop on Deal Pier

It should also be noted that Portfolio Holder engagement has continued throughout this process.

### Feedback:

Valuable feedback was received and it was agreed to extend the period of review to fully consider and investigate it, a summary of which is provided below.

Staff member A was satisfied with the proposed hours and rota option.

Staff member B was satisfied with the proposed hours and rota option as this did not affect their current allocation. Staff member B explained that he would not like to lose any more hours should there be a revision to the proposed hours and rota option.

Staff member C had no comments to make in relation to the review.

Staff member D explained that the existing rota works well and ideally would like to have more hours; (D) is satisfied with the current allocation and is not in favour of the proposed hours and rota option.

Staff member E commented on the working pattern particularly over the weekend periods and asked if this could be reviewed. Staff member E would be willing to reduce hours to help enable the above.

There was no alternative staff rota proposals put forward by members of staff.

General feedback from staff relating to the proposals included some constructive points such as improving communications among the team, adding further details to work task sheets, review of times for fishing tickets, possible introduction of benefits to customers such as loyalty cards and review of casual review for staff cover on bank holidays.

A total of four responses were received following stakeholder engagement. General feedback included consideration to income generated from other tickets sold such as combined day/night purchased in advance of the midnight shift. Deal Pier was recognised as a community asset and better promotion of the fishing on the pier was suggested. Two comments stated that vulnerability of lone working staff should not attribute to reasons for ending this service. All four responses were not in support of the proposal to cease overnight fishing on the pier from 00.00hrs – 08.00hrs on Sunday mornings.

### In response to the feedback the following changes are proposed:-

Staff working shifts have been altered to accommodate the individuals concerns raised within the consultation; this includes some change in hours and working days where necessary.

It is recommended there will be a midnight shift, 00.00hrs to 08.00hrs, once every four weekends during the summer timetable. This is reflected within the revised rota and has an add-on effect for the change in opening hours. As staff is rotated to work one midnight shift every eight weeks, there is an expectation that annual leave requests will not be made during the week of working the Midnight shift. The dates of midnight fishing will be promoted on the Pier website and on the Pier itself.

Improving team communications will be undertaken by way of introducing new ICT skills as necessary, adapting electronic communications, reducing use of paper forms and phasing in East Kent People Manager.

It was recognised that to support the above changes, a review of Pier Supervisor hours needs to take place. It is proposed that this is considered by Employment Management Group and subject to approval, an increase in hours can be implemented from 1 January 2018 or as soon as possible.

Better promotion of overnight fishing is required and will be addressed on the DDC website, highlighting when this takes place and providing more background information to this service. Communications with the Sea Angling clubs & others will be undertaken to share and promote the service.

Times of fishing ticket charges will be revised to provide a more effective operational approach for administration and ticket management, taking effect from 1st April 2018.

### Next Steps subject to Cabinet approval:-

To circulate a copy of End of Consultation Report to Deal Pier staff.

To write to stakeholders to thank them for their participation and share the final recommendation.

To implement recommendations as set out by Cabinet.